

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+20.58)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	1,175 CY		
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,250 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	310 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,250 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	170 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	20 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	228 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	32 LF		
0015	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	52 LF		
0016	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	88 LF		
0017	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	72 LF		
0018	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0020	0995000000-E	340	PIPE REMOVAL	221 LF		
0021	1220000000-E	545	INCIDENTAL STONE BASE	120 TON		
0022	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,665 TON		
0023	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,095 TON		
0024	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	775 TON		
0025	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	124 TON		
0026	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	47 TON		
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0028	2022000000-E	815	SUBDRAIN EXCAVATION	115 CY		
0029	2033000000-E	815	SUBDRAIN FINE AGGREGATE	85 CY		
0030	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0031	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0032	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0033	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0034	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	5 EA		
0036	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	400 LF		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3030000000-E	862	STEEL BM GUARDRAIL	450 LF		
0038	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0039	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0040	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0041	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
0042	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0043	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	2 EA		
0044	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	187.5 LF		
0045	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	2 EA		
0046	3649000000-E	876	RIP RAP, CLASS B	255 TON		
0047	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,570 SY		
0048	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	437 SF		
0049	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0050	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	57 SF		
0051	4430000000-N	1130	DRUMS	15 EA		
0052	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0053	4450000000-N	1150	FLAGGER	160 HR		
0054	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	25 EA		
0055	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,600 LF		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,180 LF		
0057	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	150 LF		
0058	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	40 LF		
0059	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	4 EA		
0060	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4" (III))	840 LF		
0061	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	8,780 LF		
0062	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	150 LF		
0063	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	40 LF		
0064	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	4 EA		
0065	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	25 EA		
0066	5327400000-E	1510	24" WATER LINE	1,263 LF		
0067	5540000000-E	1515	6" VALVE	2 EA		
0068	5559400000-E	1515	24" VALVE	2 EA		
0069	5649000000-N	1515	RECONNECT WATER METER	1 EA		
0070	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0071	5691300000-E	1520	8" SANITARY GRAVITY SEWER	893 LF		
0072	5775000000-E	1525	4' DIA UTILITY MANHOLE	4 EA		
0073	5776000000-E	1525	5' DIA UTILITY MANHOLE	1 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	9 LF		
0075	5782000000-E	1525	UTILITY MANHOLE WALL, 5' DIA	5 LF		
0076	5813000000-E	1530	ABANDON 24" UTILITY PIPE	1,179 LF		
0077	5816000000-N	1530	ABANDON UTILITY MANHOLE	3 EA		
0078	5836400000-E	1540	36" ENCASEMENT PIPE	70 LF		
0079	5872400000-E	1550	TRENCHLESS INSTALLATION OF 36" IN SOIL	35 LF		
0080	5872410000-E	1550	TRENCHLESS INSTALLATION OF 36" NOT IN SOIL	35 LF		
0081	5876000000-N	SP	STEEL PILE PIERS	5 EA		
0082	6000000000-E	1605	TEMPORARY SILT FENCE	1,400 LF		
0083	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0084	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	240 TON		
0085	6012000000-E	1610	SEDIMENT CONTROL STONE	285 TON		
0086	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0087	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0088	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.75 TON		
0089	6024000000-E	1622	TEMPORARY SLOPE DRAINS	65 LF		
0090	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0091	6029000000-E	SP	SAFETY FENCE	300 LF		
0092	6030000000-E	1630	SILT EXCAVATION	805 CY		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,450		SY
0094	6037000000-E	SP	COIR FIBER MAT	25		SY
0095	6042000000-E	1632	1/4" HARDWARE CLOTH	120		LF
0096	6070000000-N	SP	SPECIAL STILLING BASINS	8		EA
0097	6071010000-E	SP	WATTLE	195		LF
0098	6071020000-E	SP	POLYACRYLAMIDE (PAM)	72		LB
0099	6071030000-E	SP	COIR FIBER BAFFLES	165		LF
0100	6071050000-E	SP	*** SKIMMER (1-1/2")	4		EA
0101	6084000000-E	1660	SEEDING & MULCHING	5.5		ACR
0102	6087000000-E	1660	MOWING	3		ACR
0103	6090000000-E	1661	SEED FOR REPAIR SEEDING	50		LB
0104	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25		TON
0105	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125		LB
0106	6108000000-E	1665	FERTILIZER TOPDRESSING	3.5		TON
0107	6114000000-N	SP	SPECIALIZED HAND MOWING	2		HR
0108	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12		EA
0109	7060000000-E	1705	SIGNAL CABLE	420		LF
0110	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	3		EA
0111	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	1		EA
0112	7252000000-E	1710	MESSENGER CABLE (1/4")	290		LF

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0113	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	650 LF		
0114	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	4 EA		
0115	7360000000-N	1720	WOOD POLE	2 EA		
0116	7372000000-N	1721	GUY ASSEMBLY	4 EA		
0117	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	220 LF		
0118	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	990 LF		
0119	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0120	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0121	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	5 EA		
0122	7901000000-N	1753	CABINET BASE EXTENDER	1 EA		
0143	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	9 LF		
0144	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		

STRUCTURE ITEMS

0123	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+20.50-L-)	Lump Sum	L.S.	
0124	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	34.5 LF		
0125	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	25 LF		
0126	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	10 LF		
0127	8113000000-N	SP	SID INSPECTION	2 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0128	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0129	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	7,107 SF		
0130	8161000000-E	420	GROOVING BRIDGE FLOORS	6,299 SF		
0131	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	93.8 CY		
0132	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+20.50-L-)	Lump Sum	L.S.	
0133	8217000000-E	425	REINFORCING STEEL (BRIDGE)	19,306 LB		
0134	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,217 LB		
0135	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	905.63 LF		
0136	8364000000-E	450	HP12X53 STEEL PILES	475 LF		
0137	8482000000-E	460	THREE BAR METAL RAIL	175.58 LF		
0138	8503000000-E	460	CONCRETE BARRIER RAIL	183.31 LF		
0139	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	329 TON		
0140	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	376 SY		
0141	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0142	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1036/Oct07/Q82885.82/D686756600000/E144

Total Amount Of Bid For Entire Project :

Contract No **C201898**

County (ies): **Cabarrus**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General