

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1	ACR	
0003	0057000000-E	226	UNDERCUT EXCAVATION	300	CY	
0004	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0005	0106000000-E	230	BORROW EXCAVATION	55,400	CY	
0006	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	4	EA	
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	120	CY	
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100	SY	
0009	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	100	CY	
001C	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	212	TON	
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	420	LF	
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	60	LF	
0013	0660000000-E	310	****BIT COAT CS PIPE CULVERTS, TYPE A ***** THICK (15", 0.064")	132	LF	
0014	0680000000-E	310	*** BIT COAT CS PIPE ELBOWS, TYPE A ***** THICK (15", 0.064")	4	EA	
0015	1110000000-E	510	STABILIZER AGGREGATE	10	TON	
0016	1121000000-E	520	AGGREGATE BASE COURSE	2,476	TON	
0017	1220000000-E	545	INCIDENTAL STONE BASE	30	TON	
001E	1275000000-E	600	PRIME COAT	1,473	GAL	

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	110 TON		
002C	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	880 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	58 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	22 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	5 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	30 CY		
002E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
003C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0031	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
0033	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	25 LF		
0034	2556000000-E	846	SHOULDER BERM GUTTER	550 LF		
003E	3030000000-E	862	STEEL BM GUARDRAIL	825 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
003E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
003E	3649000000-E	876	RIP RAP, CLASS B	38	TON	
004C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	483	SY	
0041	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3	EA	
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	104	SF	
0043	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	176	SF	
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	70	SF	
004E	4430000000-N	1130	DRUMS	130	EA	
004E	4435000000-N	1135	CONES	10	EA	
0047	4445000000-E	1145	BARRICADES (TYPE III)	56	LF	
004E	4455000000-N	1150	FLAGGER	75	MD	
004E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	25	EA	
005C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	33,120	LF	
0051	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	160	LF	
0052	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	300	LF	
0053	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	25	EA	
0054	5326200000-E	1510	12" WATER LINE	887	LF	

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	5328000000-E	1510	30" WATER LINE	225	LF	
005E	5540000000-E	1515	6" VALVE	4	EA	
0057	5558000000-E	1515	12" VALVE	4	EA	
005E	5560000000-E	1515	30" VALVE	2	EA	
005E	5648000000-N	1515	RELOCATE WATER METER	2	EA	
006C	5666000000-E	1515	FIRE HYDRANT	2	EA	
0061	5691300000-E	1520	8" SANITARY GRAVITY SEWER	230	LF	
0062	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	5	EA	
006E	5775000000-E	1525	4' DIA UTILITY MANHOLE	4	EA	
0064	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	6	LF	
006E	5801000000-E	1530	ABANDON 8" UTILITY PIPE	337	LF	
006E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	1,397	LF	
0067	5814000000-E	1530	ABANDON 30" UTILITY PIPE	273	LF	
006E	5816000000-N	1530	ABANDON UTILITY MANHOLE	2	EA	
006E	5835600000-E	1540	12" ENCASEMENT PIPE	165	LF	
007C	5871500000-E	1550	TRENCHLESS INSTALLATION OF 8" IN SOIL	65	LF	
0071	5871510000-E	1550	TRENCHLESS INSTALLATION OF 8" NOT IN SOIL	65	LF	
0072	5871700000-E	1550	TRENCHLESS INSTALLATION OF 12" IN SOIL	83	LF	
0073	5871710000-E	1550	TRENCHLESS INSTALLATION OF 12" NOT IN SOIL	83	LF	

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	5872300000-E	1550	TRENCHLESS INSTALLATION OF 30" IN SOIL	60	LF	
007E	5872310000-E	1550	TRENCHLESS INSTALLATION OF 30" NOT IN SOIL	60	LF	
007E	5882000000-N	SP	GENERIC UTILITY ITEM 1" AIR VACUUM VALVE AND VAULT	2	EA	
0077	5882000000-N	SP	GENERIC UTILITY ITEM CLASS B CONCRETE ENCASEMENT BLOCK	1	EA	
007E	5888000000-E	SP	GENERIC UTILITY ITEM 6" DUCTILE IRON FORCE MAIN SEWER PIPE, PC 350	1,415	LF	
007E	6000000000-E	1605	TEMPORARY SILT FENCE	2,800	LF	
008C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100	TON	
0081	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	250	TON	
0082	6012000000-E	1610	SEDIMENT CONTROL STONE	125	TON	
008E	6015000000-E	1615	TEMPORARY MULCHING	4.5	ACR	
0084	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150	LB	
008E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75	TON	
008E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	400	LF	
0087	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7	EA	
008E	6029000000-E	SP	SAFETY FENCE	300	LF	
008E	6030000000-E	1630	SILT EXCAVATION	5,755	CY	
009C	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,050	SY	

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6037000000-E	SP	COIR FIBER MAT	30	SY	
0092	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,020	SY	
0093	6042000000-E	1632	1/4" HARDWARE CLOTH	200	LF	
0094	6071030000-E	SP	COIR FIBER BAFFLES	250	LF	
0095	6084000000-E	1660	SEEDING & MULCHING	8	ACR	
0096	6087000000-E	1660	MOWING	5	ACR	
0097	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0098	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0099	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200	LB	
0100	6108000000-E	1665	FERTILIZER TOPDRESSING	6	TON	
0101	6114000000-N	SP	SPECIALIZED HAND MOWING	2.5	HR	
0102	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
0103	6123000000-E	1670	REFORESTATION	0.5	ACR	

WALL ITEMS

0104	8801000000-E	SP	MSE RETAINING WALLS	4,633	SF	
------	--------------	----	---------------------	-------	----	--

STRUCTURE ITEMS

0105	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (28 + 71.39-L-)	Lump Sum	L.S.	
0106	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	6,314	SF	

County : New Hanover

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8161000000-E	420	GROOVING BRIDGE FLOORS	5,840 SF		
010E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	68.6 CY		
010E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (28 + 71.39-L-)	Lump Sum	L.S.	
011C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	8,446 LB		
0111	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	381,000 LS		
0112	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	1,430 LF		
011E	8391000000-N	450	STEEL PILE POINTS	22 EA		
0114	8503000000-E	460	CONCRETE BARRIER RAIL	379.79 LF		
011E	8524000000-E	SP	*** CHAIN LINK FENCE (60")	372 LF		
011E	8531000000-E	462	4" SLOPE PROTECTION	16 SY		
0117	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
011E	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1058/Sep11/Q525913.89/D540145260000/E118

Total Amount Of Bid For Entire Project :

Contract No **C201921**

County (ies): **New Hanover**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General