

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	10,100 CY		
0005	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	140 SY		
0006	0192000000-N	260	PROOF ROLLING	3.5 HR		
0007	0255000000-E	SP	GENERIC GRADING ITEM EXCAVATION AND STOCKPILING OF CONTAMINATED SOIL	100 TON		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	1,160 TON		
0009	0344000000-E	310	18" SIDE DRAIN PIPE	2,480 LF		
001C	0345000000-E	310	24" SIDE DRAIN PIPE	84 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	860 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	312 LF		
0014	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	132 LF		
0015	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	272 LF		
0016	0995000000-E	340	PIPE REMOVAL	3,440 LF		
0017	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	23,980	SY	
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,220	TON	
002C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	4,660	TON	
0021	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,490	TON	
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	645	TON	
0023	2000000000-N	806	RIGHT OF WAY MARKERS	26	EA	
0024	2253000000-E	840	PIPE COLLARS	0.9	CY	
002E	2264000000-E	840	PIPE PLUGS	0.209	CY	
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	14	EA	
0027	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.31	LF	
002E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1	EA	
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	13	EA	
003C	2535000000-E	846	***X *** CONCRETE CURB (8" X 12")	510	LF	
0031	2612000000-E	848	6" CONCRETE DRIVEWAY	220	SY	
0032	3649000000-E	876	RIP RAP, CLASS B	19	TON	
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	53	SY	
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	300	SF	
003E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	100	SF	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0037	4430000000-N	1130	DRUMS	200 EA		
003E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	15,000 LF		
003E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	21,000 LF		
004C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	65 EA		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	60,000 LF		
0042	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	130 EA		
0043	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	325 EA		
0044	5325600000-E	1510	6" WATER LINE	10 LF		
004E	5325800000-E	1510	8" WATER LINE	48 LF		
004E	5326200000-E	1510	12" WATER LINE	7,200 LF		
0047	5540000000-E	1515	6" VALVE	1 EA		
004E	5558000000-E	1515	12" VALVE	7 EA		
004E	5572200000-E	1515	12" TAPPING VALVE	2 EA		
005C	5589200000-E	1515	2" AIR RELEASE VALVE	3 EA		
0051	5648000000-N	1515	RELOCATE WATER METER	33 EA		
0052	5649000000-N	1515	RECONNECT WATER METER	10 EA		
0053	5672000000-N	1515	RELOCATE FIRE HYDRANT	8 EA		
0054	5801000000-E	1530	ABANDON 8" UTILITY PIPE	50 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	5804000000-E	1530	ABANDON 12" UTILITY PIPE	7,145 LF		
005E	6000000000-E	1605	TEMPORARY SILT FENCE	530 LF		
0057	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	610 TON		
005E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	45 TON		
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	310 TON		
006C	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0061	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0062	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
006E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0064	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
006E	6030000000-E	1630	SILT EXCAVATION	625 CY		
006E	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,500 SY		
0067	6042000000-E	1632	1/4" HARDWARE CLOTH	320 LF		
006E	6084000000-E	1660	SEEDING & MULCHING	4 ACR		
006E	6087000000-E	1660	MOWING	0.5 ACR		
007C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
007E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0075	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
0903/Sep09/Q175780.769/D275342100000/E75			Total Amount Of Bid For Entire Project :			

**Contract No**     **C201810**

**County (ies):**   **Robeson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General