

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+55.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	300 SY		
0008	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	11 TON		
0009	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	98 LF		
0010	1121000000-E	520	AGGREGATE BASE COURSE	15 TON		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	240 TON		
0012	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	300 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	30 TON		
0014	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0015	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0016	2022000000-E	815	SUBDRAIN EXCAVATION	25 CY		
0017	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0018	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0020	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0021	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0022	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0023	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.6 LF		
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0025	2556000000-E	846	SHOULDER BERM GUTTER	40 LF		
0026	3030000000-E	862	STEEL BM GUARDRAIL	375 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0028	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0029	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0030	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0031	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,210 SY		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	289 SF		
0033	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0034	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0035	4430000000-N	1130	DRUMS	30 EA		
0036	4435000000-N	1135	CONES	30 EA		
0037	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4455000000-N	1150	FLAGGER	10 MD		
0039	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,600 LF		
0040	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	14 EA		
0041	6000000000-E	1605	TEMPORARY SILT FENCE	3,550 LF		
0042	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	450 TON		
0043	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	5 TON		
0044	6012000000-E	1610	SEDIMENT CONTROL STONE	80 TON		
0045	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0046	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0047	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25 TON		
0048	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0049	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0050	6029000000-E	SP	SAFETY FENCE	800 LF		
0051	6030000000-E	1630	SILT EXCAVATION	5 CY		
0052	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,200 SY		
0053	6042000000-E	1632	1/4" HARDWARE CLOTH	275 LF		
0054	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0055	6087000000-E	1660	MOWING	1 ACR		
0056	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0058	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0059	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0060	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0061	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0062	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0063	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+55.00-L-)	Lump Sum	L.S.	
0064	8112730000-N	SP	PDA TESTING	1 EA		
0065	8112740000-N	SP	PDA ASSISTANCE	1 EA		
0066	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+55.00-L-)	Lump Sum	L.S.	
0067	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	45.2 CY		
0068	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+55.00-L-)	Lump Sum	L.S.	
0069	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,184 LB		
0070	8364000000-E	450	HP12X53 STEEL PILES	660 LF		
0071	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	880 LF		
0072	8393000000-N	450	PILE REDRIVES	16 EA		
0073	8503000000-E	460	CONCRETE BARRIER RAIL	329.5 LF		

County : Wayne

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8590000000-E	876	RIP RAP, CLASS ** (I)	218 TON		
0075	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	242 SY		
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,810.88 LF		
0824/Sep12/Q29688.03/D351645570000/E77			Total Amount Of Bid For Entire Project :			

Contract No **C202019**

County (ies): **Wayne**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General