

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	1,700 CY		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+52.500)	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	16 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	120 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	45 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	60 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	105 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	10 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	10 TON		
001E	2000000000-N	806	RIGHT OF WAY MARKERS	12 EA		
002C	2022000000-E	815	SUBDRAIN EXCAVATION	68 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	51 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0027	2354200000-N	840	FRAME WITH GRATE, STD 840.24	1 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	184 LF		
003C	3030000000-E	862	STEEL BM GUARDRAIL	300 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (TEST LEVEL 2)	1 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0034	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
003E	3628000000-E	876	RIP RAP, CLASS I	9 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3649000000-E	876	RIP RAP, CLASS B	3 TON		
0037	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	250 SY		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	242 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
004C	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,400 LF		
0042	6000000000-E	1605	TEMPORARY SILT FENCE	260 LF		
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	135 TON		
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	110 TON		
0046	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0049	6024000000-E	1622	TEMPORARY SLOPE DRAINS	40 LF		
005C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0051	6029000000-E	SP	SAFETY FENCE	280 LF		
0052	6030000000-E	1630	SILT EXCAVATION	265 CY		
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	500 SY		
0054	6037000000-E	SP	COIR FIBER MAT	30 SY		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	255	LF	
005E	6071030000-E	SP	COIR FIBER BAFFLES	45	LF	
0057	6071050000-E	SP	*** SKIMMER (1-1/2")	3	EA	
005E	6084000000-E	1660	SEEDING & MULCHING	2	ACR	
005E	6087000000-E	1660	MOWING	1	ACR	
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
0064	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
006E	6123000000-E	1670	REFORESTATION	0.1	ACR	

WALL ITEMS

0067	8802031000-E	SP	PRECAST GRAVITY RETAINING WALLS	1,088	SF	
------	--------------	----	---------------------------------	-------	----	--

STRUCTURE ITEMS

006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+52.50-L-)	Lump Sum	L.S.	
006E	8096000000-E	SP	PILE EXCAVATION IN SOIL	10	LF	

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
007C	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	50 LF		
0071	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (17+52.50-L-)	Lump Sum	L.S.	
0072	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	2,678 SF		
0073	8161000000-E	420	GROOVING BRIDGE FLOORS	2,637 SF		
0074	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	32.7 CY		
0075	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+52.50-L-)	Lump Sum	L.S.	
0076	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,696 LB		
0077	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	80,200 LS		
007E	8364000000-E	450	HP12X53 STEEL PILES	115 LF		
0079	8503000000-E	460	CONCRETE BARRIER RAIL	196.67 LF		
008C	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	90 TON		
0081	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	100 SY		
0082	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1337/Oct02/Q104305.72/D362493811000/E82			Total Amount Of Bid For Entire Project :			

Contract No **C202138**

County (ies): **Ashe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General