

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13 + 64.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	450 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0010	0344000000-E	310	18" SIDE DRAIN PIPE	56 LF		
0011	0995000000-E	340	PIPE REMOVAL	24 LF		
0012	1077000000-E	SP	#57 STONE	15 TON		
0013	1121000000-E	520	AGGREGATE BASE COURSE	78 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	118 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	150 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	15 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	4 EA		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
002C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	145 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	75 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3575000000-E	SP	GENERIC FENCING ITEM TEMPORARY 4 STRAND BARBED WIRE FENCE WITH POSTS	350 LF		
0033	3642000000-E	876	RIP RAP, CLASS A	5 TON		
0034	3649000000-E	876	RIP RAP, CLASS B	130 TON		
003E	3651000000-E	SP	BOULDERS	35 TON		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	5,065 SY		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	425	SF	
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	96	SF	
004C	4430000000-N	1130	DRUMS	8	EA	
0041	4445000000-E	1145	BARRICADES (TYPE III)	72	LF	
0042	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,840	LF	
0043	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	96	EA	
0044	6000000000-E	1605	TEMPORARY SILT FENCE	1,550	LF	
0045	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	500	TON	
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	125	TON	
0047	6012000000-E	1610	SEDIMENT CONTROL STONE	230	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0049	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
005C	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25	TON	
0051	6029000000-E	SP	SAFETY FENCE	475	LF	
0052	6030000000-E	1630	SILT EXCAVATION	205	CY	
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,150	SY	
0054	6037000000-E	SP	COIR FIBER MAT	100	SY	

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	160 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0057	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
005E	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
005E	6087000000-E	1660	MOWING	1 ACR		
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25 TON		
0064	6111000000-E	SP	IMPERVIOUS DIKE	50 LF		
006E	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0067	6126000000-E	SP	STREAMBANK REFORESTATION	0.12 ACR		
006E	6138000000-E	SP	GENERIC EROSION CONTROL ITEM IMPERVIOUS SELECT MATERIAL	55 CY		

***** BEGIN SCHEDULE AA *****
 ***** (3 ALTERNATES) *****

006E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	36 LF		
AA1						

*** OR ***

007C	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	24 LF		
AA2						

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	12 LF		
*** OR ***						
0072 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	24 LF		
0073 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	12 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0074	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (13+64.00-L-)	Lump Sum	L.S.	
0075	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+64.00-L-)	Lump Sum	L.S.	
0076	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	36 LF		
0077	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	24 LF		
0078	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	31.4 LF		
0079	8113000000-N	SP	SID INSPECTION	1 EA		
0080	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0081	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	1,100 CY		
0082	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	54.8 CY		
0083	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+64.00-L-)	Lump Sum	L.S.	

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0084	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,753 LB		
008E	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,496 LB		
008E	8364000000-E	450	HP12X53 STEEL PILES	165 LF		
0087	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	283.03 LF		
008E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	615 TON		
008E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	685 SY		
009C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0091	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,271.16 LF		

1032/Oct03/Q35728.26/D396539440000/E91

Total Amount Of Bid For Entire Project :

Contract No **C201974**

County (ies): **Granville**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General