

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13+64.00)	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (13+83.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	2 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	300 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	450 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	400 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	22 TON		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	56 LF		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	24 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	24 LF		
0014	0995000000-E	340	PIPE REMOVAL	44 LF		
0015	1077000000-E	SP	#57 STONE	15 TON		
0016	1121000000-E	520	AGGREGATE BASE COURSE	113 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	298 TON		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	500 TON		
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	46 TON		
0021	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0022	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
002E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
002E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	7 LF		
003C	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0031	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	210 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	400 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	8 EA		
003E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3575000000-E	SP	GENERIC FENCING ITEM TEMPORARY 4 STRAND BARBED WIRE FENCE WITH POSTS	350 LF		
003E	3642000000-E	876	RIP RAP, CLASS A	5 TON		
003E	3649000000-E	876	RIP RAP, CLASS B	135 TON		
004C	3651000000-E	SP	BOULDERS	35 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	6,175 SY		
0042	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0043	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	737 SF		
0044	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	190 SF		
004E	4430000000-N	1130	DRUMS	8 EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	136 LF		
0047	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,520 LF		
004E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	163 EA		
004E	6000000000-E	1605	TEMPORARY SILT FENCE	4,450 LF		
005C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	725 TON		
0051	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	340 TON		
0052	6012000000-E	1610	SEDIMENT CONTROL STONE	305 TON		
0053	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0054	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
005E	6029000000-E	SP	SAFETY FENCE	975 LF		
0057	6030000000-E	1630	SILT EXCAVATION	555 CY		
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,250 SY		
005E	6037000000-E	SP	COIR FIBER MAT	100 SY		
006C	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	160 SY		
0061	6042000000-E	1632	1/4" HARDWARE CLOTH	90 LF		
0062	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0063	6071030000-E	SP	COIR FIBER BAFFLES	100 LF		
0064	6084000000-E	1660	SEEDING & MULCHING	7 ACR		
006E	6087000000-E	1660	MOWING	2 ACR		
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
006E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	2.5 TON		
007C	6111000000-E	SP	IMPERVIOUS DIKE	50 LF		
0071	6114000000-N	SP	SPECIALIZED HAND MOWING	10 HR		
0072	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	24 EA		
0073	6126000000-E	SP	STREAMBANK REFORESTATION	0.12 ACR		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6138000000-E	SP	GENERIC EROSION CONTROL ITEM IMPERVIOUS SELECT MATERIAL	55 CY		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
007E AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	36 LF		
007E AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	48 LF		
*** OR ***						
0077 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	24 LF		
007E AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	12 LF		
007E AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	48 LF		
*** OR ***						
008C AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	24 LF		
0081 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	12 LF		
0082 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	48 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0083	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (13+64.00-L-)	Lump Sum	L.S.	
0084	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (13+83.00-L-)	Lump Sum	L.S.	

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0085	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+64.00-L-)	Lump Sum	L.S.	
0086	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+83.00-L-)	Lump Sum	L.S.	
0087	8096000000-E	SP	PILE EXCAVATION IN SOIL	48 LF		
0088	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	32 LF		
0089	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SOIL	36 LF		
009C	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	24 LF		
0091	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	31.4 LF		
0092	8113000000-N	SP	SID INSPECTION	1 EA		
0093	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0094	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	1,100 CY		
009E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (13+83.00-L-)	Lump Sum	L.S.	
009E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	88.3 CY		
0097	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+64.00-L-)	Lump Sum	L.S.	
009E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+83.00-L-)	Lump Sum	L.S.	
0098	8217000000-E	425	REINFORCING STEEL (BRIDGE)	16,684 LB		
010C	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,496 LB		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0101	8364000000-E	450	HP12X53 STEEL PILES	325 LF		
0102	8391000000-N	450	STEEL PILE POINTS	8 EA		
0103	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	457.83 LF		
0104	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	965 TON		
0105	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,065 SY		
0106	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0107	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	786.61 LF		
0108	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,271.16 LF		
1032/Oct03/Q60600.92/D475592570000/E108			Total Amount Of Bid For Entire Project :			

Contract No **C202187**

County (ies): **Granville**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General