

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (16 + 29.96)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0008	0314000000-E	300	SELECT MATERIAL, CLASS ***** (IV)	20 TON		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	5 TON		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	36 LF		
0011	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	440 TON		
0013	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	380 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	42 TON		
0015	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0016	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
001E	2556000000-E	846	SHOULDER BERM GUTTER	113 LF		
002C	3030000000-E	862	STEEL BM GUARDRAIL	600 LF		
0021	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0022	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0024	3649000000-E	876	RIP RAP, CLASS B	3 TON		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	4,665 SY		
002E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0027	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	95 LF		
002E	4102000000-N	904	SIGN ERECTION, TYPE E	15 EA		
002E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	13 EA		
003C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	425 SF		
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114 SF		
0032	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,500 LF		
0034	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	12 EA		
003E	5325600000-E	1510	6" WATER LINE	300 LF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	5540000000-E	1515	6" VALVE	2	EA	
0037	5666000000-E	1515	FIRE HYDRANT	2	EA	
003E	6000000000-E	1605	TEMPORARY SILT FENCE	3,200	LF	
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	450	TON	
004C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	105	TON	
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	250	TON	
0042	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0043	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
0045	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50	LF	
0046	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
0047	6029000000-E	SP	SAFETY FENCE	525	LF	
004E	6030000000-E	1630	SILT EXCAVATION	185	CY	
0049	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,200	SY	
005C	6042000000-E	1632	1/4" HARDWARE CLOTH	130	LF	
0051	6070000000-N	SP	SPECIAL STILLING BASINS	8	EA	
0052	6071030000-E	SP	COIR FIBER BAFFLES	40	LF	
0053	6084000000-E	1660	SEEDING & MULCHING	2.5	ACR	
0054	6087000000-E	1660	MOWING	1	ACR	

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
005E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0057	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
005E	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
006C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0061	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS

0062	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (16 + 30.50-L-)	Lump Sum	L.S.	
006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16 + 30.50-L-)	Lump Sum	L.S.	
0064	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	78.35 LF		
006E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	20 LF		
006E	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	58 LF		
0067	8113000000-N	SP	SID INSPECTION	2 EA		
006E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
006E	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	870 CY		
007C	8156000000-E	SP	CONCRETE WEARING SURFACE	4,363 SF		

County : Johnston

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8161000000-E	420	GROOVING BRIDGE FLOORS	5,380 SF		
0072	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	86.4 CY		
0073	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16 + 30.50-L-)	Lump Sum	L.S.	
0074	8217000000-E	425	REINFORCING STEEL (BRIDGE)	20,228 LB		
0075	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,220 LB		
0076	8364000000-E	450	HP12X53 STEEL PILES	340 LF		
0077	8503000000-E	460	CONCRETE BARRIER RAIL	267.38 LF		
0078	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	243 TON		
0079	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	271 SY		
008C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0081	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0082	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,602.75 LF		

1335/Oct01/Q58916.23/D413230310000/E82

Total Amount Of Bid For Entire Project :

Contract No **C201971**

County (ies): **Johnston**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General