

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
000E	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	600 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
000E	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	11 TON		
001C	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	52 LF		
0011	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	44 LF		
0012	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0013	1220000000-E	545	INCIDENTAL STONE BASE	45 TON		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	150 TON		
001E	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	135 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	16 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
001E	2022000000-E	815	SUBDRAIN EXCAVATION	101 CY		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2033000000-E	815	SUBDRAIN FINE AGGREGATE	76 CY		
002C	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	450 LF		
0021	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0022	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0024	2209000000-E	838	ENDWALLS	1 CY		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0026	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0027	3030000000-E	862	STEEL BM GUARDRAIL	50 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0029	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350, TEST LEVEL II)	4 EA		
003C	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0031	3628000000-E	876	RIP RAP, CLASS I	4 TON		
0032	3649000000-E	876	RIP RAP, CLASS B	12 TON		
0033	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	605 SY		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	740 SF		
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	76 SF		
0036	4445000000-E	1145	BARRICADES (TYPE III)	120 LF		

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,592	LF	
003E	6000000000-E	1605	TEMPORARY SILT FENCE	400	LF	
0039	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	135	TON	
004C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	35	TON	
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	115	TON	
0042	6015000000-E	1615	TEMPORARY MULCHING	1.5	ACR	
0043	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0044	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
004E	6029000000-E	SP	SAFETY FENCE	250	LF	
004E	6030000000-E	1630	SILT EXCAVATION	165	CY	
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	950	SY	
004E	6037000000-E	SP	COIR FIBER MAT	30	SY	
0049	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	150	SY	
005C	6070000000-N	SP	SPECIAL STILLING BASINS	4	EA	
0051	6071010000-E	SP	WATTLE	60	LF	
0052	6071020000-E	SP	POLYACRYLAMIDE (PAM)	23	LB	
0053	6071030000-E	SP	COIR FIBER BAFFLES	190	LF	
0054	6071050000-E	SP	*** SKIMMER (1-1/2")	5	EA	
005E	6084000000-E	1660	SEEDING & MULCHING	7.5	ACR	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6087000000-E	1660	MOWING	0.5	ACR	
0057	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0058	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0059	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0060	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75	TON	
0061	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
0062	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
STRUCTURE ITEMS						
0063	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+17.50-L-)	Lump Sum	L.S.	
0064	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+17.50-L-)	Lump Sum	L.S.	
0065	8070000000-E	410	FOUNDATION EXCAVATION	18.2	CY	
0066	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	17	LF	
0067	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	25	LF	
0068	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	15.3	LF	
0069	8113000000-N	SP	SID INSPECTION	2	EA	
0070	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1	EA	
0071	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15+17.50-L-)	Lump Sum	L.S.	

County : Wilkes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	58.9 CY		
0073	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,720 LB		
0074	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	808 LB		
0075	8364000000-E	450	HP12X53 STEEL PILES	75 LF		
0076	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	224.8 LF		
0077	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	86 TON		
0078	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	95 SY		
0079	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
008C	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	896.917 LF		

0922/Sep30/Q25174.867/D371779950000/E80

Total Amount Of Bid For Entire Project :

Contract No C201973

County (ies): Wilkes

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General