

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	6,400 CY		
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** STA. 13+17	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	15 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	5 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	100 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	45 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	240 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	200 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	24 TON		
0018	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0019	2022000000-E	815	SUBDRAIN EXCAVATION	68 CY		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	51 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	300 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	9 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0026	2407000000-N	840	STEEL FRAME WITH TWO GRATES, STD 840.37	1 EA		
0027	2535000000-E	846	***X *** CONCRETE CURB (9" x 12")	30 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	175 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	175 LF		
0033	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (TYPE B-77)	4 EA		
0034	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0035	3649000000-E	876	RIP RAP, CLASS B	17 TON		
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	559 SY		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	270 SF		
0038	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128 SF		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0040	4430000000-N	1130	DRUMS	20 EA		
0041	4435000000-N	1135	CONES	20 EA		
0042	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0043	4455000000-N	1150	FLAGGER	120 MD		
0044	4480000000-N	1165	TMIA	1 EA		
0045	4609000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY TRAFFIC SIGNAL SYSTEM	180 DAY		
0046	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	13,100 LF		
0047	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	34 LF		
0048	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	224 LF		
0049	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	17 LF		
0050	6000000000-E	1605	TEMPORARY SILT FENCE	1,500 LF		
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	135 TON		
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180 TON		
0053	6012000000-E	1610	SEDIMENT CONTROL STONE	150 TON		
0054	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0055	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0056	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6029000000-E	SP	SAFETY FENCE	400 LF		
0058	6030000000-E	1630	SILT EXCAVATION	300 CY		
0059	6036000000-E	1631	MATTING FOR EROSION CONTROL	4,400 SY		
0060	6037000000-E	SP	COIR FIBER MAT	10 SY		
0061	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0062	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0063	6071010000-E	SP	WATTLE	170 LF		
0064	6071020000-E	SP	POLYACRYLAMIDE (PAM)	63 LB		
0065	6071030000-E	SP	COIR FIBER BAFFLES	30 LF		
0066	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0067	6084000000-E	1660	SEEDING & MULCHING	3.5 ACR		
0068	6087000000-E	1660	MOWING	1.5 ACR		
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0070	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0073	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0074	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0075	6123000000-E	1670	REFORESTATION	0.1 ACR		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** (2 ALTERNATES) *****						
0076 AA1	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	12 LF		
*** OR ***						
0077 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	12 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0078	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (13+17.50-L-)	Lump Sum	L.S.	
0079	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (13+17.50-L-)	Lump Sum	L.S.	
0080	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+17.50-L-)	Lump Sum	L.S.	
0081	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	24.2 LF		
0082	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	10 LF		
0083	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	20.5 LF		
0084	8113000000-N	SP	SID INSPECTION	3 EA		
0085	8114000000-N	SP	SPT TESTING	3 EA		
0086	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0087	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (13+17.50-L-)	Lump Sum	L.S.	
0088	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	51.3 CY		

County : Ashe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+17.50-L-)	Lump Sum	L.S.	
0090	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,142 LB		
0091	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	656 LB		
0092	8364000000-E	450	HP12X53 STEEL PILES	130 LF		
0093	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	163.17 LF		
0094	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	77 TON		
0095	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	85 SY		
0096	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0097	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	734.25 LF		
1510/Nov06/Q43500.02/D443466650000/E97			Total Amount Of Bid For Entire Project :			

Contract No **C202037**

County (ies): **Ashe**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General