

County : Caldwell

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|--------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0030000000-N | SP | BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+71.50 -L-) | Lump Sum | L.S. | |
| 0004 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 0005 | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB-BING | 1 ACR | | |
| 0006 | 0057000000-E | 226 | UNDERCUT EXCAVATION | 840 CY | | |
| 0007 | 0080000000-E | SP | CLASS IV SUBGRADE STABILIZATION | 1,500 TON | | |
| 0008 | 0134000000-E | 240 | DRAINAGE DITCH EXCAVATION | 5 CY | | |
| 0009 | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 1,600 SY | | |
| 0010 | 0318000000-E | 300 | FOUNDATION CONDITIONING MATERIAL, MINOR STRS | 8 TON | | |
| 0011 | 0344000000-E | 310 | 18" SIDE DRAIN PIPE | 56 LF | | |
| 0012 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 16 LF | | |
| 0013 | 1121000000-E | 520 | AGGREGATE BASE COURSE | 325 TON | | |
| 0014 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 100 TON | | |
| 0015 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 405 TON | | |
| 0016 | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 250 TON | | |
| 0017 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 34 TON | | |
| 0018 | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 14 EA | | |

County : Caldwell

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|-----------|-----------|--------|
| 0019 | 2022000000-E | 815 | SUBDRAIN EXCAVATION | 117 CY | | |
| 0020 | 2033000000-E | 815 | SUBDRAIN FINE AGGREGATE | 88 CY | | |
| 0021 | 2044000000-E | 815 | 6" PERFORATED SUBDRAIN PIPE | 520 LF | | |
| 0022 | 2055000000-E | 815 | 6" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 16 EA | | |
| 0023 | 2066000000-N | 815 | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 2 EA | | |
| 0024 | 2077000000-E | 815 | 6" OUTLET PIPE (SUBDRAINS) | 12 LF | | |
| 0025 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 1 EA | | |
| 0026 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 1 EA | | |
| 0027 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 45 LF | | |
| 0028 | 3030000000-E | 862 | STEEL BM GUARDRAIL | 150 LF | | |
| 0029 | 3150000000-N | 862 | ADDITIONAL GUARDRAIL POSTS | 5 EA | | |
| 0030 | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 4 EA | | |
| 0031 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 4 EA | | |
| 0032 | 3559000000-E | 866 | ** STRAND BARBED WIRE FENCE WITH POSTS (2) | 210 LF | | |
| 0033 | 3563000000-E | SP | TEMP *** WOVEN WIRE FENCE, COMPLETE W/POSTS (48") | 200 LF | | |
| 0034 | 3564000000-E | 866 | SINGLE GATES, *** HIGH, *** WIDE, *** OPENING (36", 20', 20') | 1 EA | | |
| 0035 | 3649000000-E | 876 | RIP RAP, CLASS B | 2 TON | | |
| 0036 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 710 SY | | |

County : Caldwell

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|-------------------------------------|--------------|-----------|--------|
| 0037 | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 50 SF | | |
| 0038 | 4405000000-E | 1110 | WORK ZONE SIGNS (PORTABLE) | 100 SF | | |
| 0039 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 40 SF | | |
| 0040 | 4430000000-N | 1130 | DRUMS | 35 EA | | |
| 0041 | 4435000000-N | 1135 | CONES | 35 EA | | |
| 0042 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 35 LF | | |
| 0043 | 4455000000-N | 1150 | FLAGGER | 180 MD | | |
| 0044 | 4507000000-E | SP | WATER FILLED BARRIER | 220 LF | | |
| 0045 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 11,000 LF | | |
| 0046 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 1,350 LF | | |
| 0047 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 75 TON | | |
| 0048 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 415 TON | | |
| 0049 | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 365 TON | | |
| 0050 | 6015000000-E | 1615 | TEMPORARY MULCHING | 2.5 ACR | | |
| 0051 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 100 LB | | |
| 0052 | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEEDING | 0.5 TON | | |
| 0053 | 6029000000-E | SP | SAFETY FENCE | 300 LF | | |
| 0054 | 6030000000-E | 1630 | SILT EXCAVATION | 1,100 CY | | |
| 0055 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 1,260 SY | | |

County : Caldwell

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|------------------------|--------------|-------|---|--------------|-----------|--------|
| 0056 | 6038000000-E | SP | PERMANENT SOIL REINFORCEMENT MAT | 1,070 SY | | |
| 0057 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 20 LF | | |
| 0058 | 6070000000-N | SP | SPECIAL STILLING BASINS | 12 EA | | |
| 0059 | 6071030000-E | SP | COIR FIBER BAFFLES | 350 LF | | |
| 0060 | 6084000000-E | 1660 | SEEDING & MULCHING | 3 ACR | | |
| 0061 | 6087000000-E | 1660 | MOWING | 2 ACR | | |
| 0062 | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 0063 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0064 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 75 LB | | |
| 0065 | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 2.25 TON | | |
| 0066 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 2 HR | | |
| 0067 | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 12 EA | | |
| 0068 | 6123000000-E | 1670 | REFORESTATION | 0.1 ACR | | |
| STRUCTURE ITEMS | | | | | | |
| 0069 | 8017000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15+71.50-L-) | Lump Sum | L.S. | |
| 0070 | 8021000000-N | SP | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+71.50-L-) | Lump Sum | L.S. | |
| 0071 | 8105540000-E | SP | 3'-6" DIA DRILLED PIERS IN SOIL | 168.58 LF | | |
| 0072 | 8105640000-E | SP | 3'-6" DIA DRILLED PIERS NOT IN SOIL | 25 LF | | |

County : Caldwell

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 0073 | 8111400000-E | SP | PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER | 117.25 LF | | |
| 0074 | 8113000000-N | SP | SID INSPECTION | 1 EA | | |
| 0075 | 8115000000-N | SP | CROSSHOLE SONIC LOGGING | 2 EA | | |
| 0076 | 8119000000-E | 412 | UNCLASSIFIED STRUCTURE EXCAVA- TION | 950 CY | | |
| 0077 | 8156000000-E | SP | CONCRETE WEARING SURFACE | 3,686 SF | | |
| 0078 | 8161000000-E | 420 | GROOVING BRIDGE FLOORS | 3,948 SF | | |
| 0079 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 67.7 CY | | |
| 0080 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (15+71.50-L-) | Lump Sum | L.S. | |
| 0081 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 19,728 LB | | |
| 0082 | 8238000000-E | 425 | SPIRAL COLUMN REINFORCING STEEL (BRIDGE) | 4,791 LB | | |
| 0083 | 8364000000-E | 450 | HP12X53 STEEL PILES | 330 LF | | |
| 0084 | 8468000000-E | 460 | ONE BAR METAL RAIL | 248.65 LF | | |
| 0085 | 8517000000-E | 460 | 1'-***X ***** CONCRETE PARA- PET (1'-0" X 2'-0") | 264.8 LF | | |
| 0086 | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 318 TON | | |
| 0087 | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 353 SY | | |
| 0088 | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0089 | 8692000000-N | SP | EVAZOTE JOINT SEALS | Lump Sum | L.S. | |

County : Caldwell

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|----------------|-----------|--------|
| 0090 | 8762000000-E | 430 | 3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS | 1,321.15 LF | | |

1130/Nov05/Q61832.73/D422863110000/E90

Total Amount Of Bid For Entire Project :

Contract No **C201920**

County (ies): **B-3624**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General