

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (21 + 82.5)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
000E	0057000000-E	226	UNDERCUT EXCAVATION	700 CY		
000E	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	13,300 CY		
000E	0134000000-E	240	DRAINAGE DITCH EXCAVATION	1,950 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
001C	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	15 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0013	0344000000-E	310	18" SIDE DRAIN PIPE	20 LF		
0014	0345000000-E	310	24" SIDE DRAIN PIPE	20 LF		
001E	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	60 LF		
001E	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK (15", 0.064")	4 EA		
0017	0995000000-E	340	PIPE REMOVAL	80 LF		
001E	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	730 TON		
002C	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	410 TON		
0021	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	390 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	80 TON		
0023	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	293 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	900 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
002E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
003C	3575000000-E	SP	GENERIC FENCING ITEM 2-STRAND ELECTRIC FENCE	140 LF		
0031	3628000000-E	876	RIP RAP, CLASS I	380 TON		
0032	3649000000-E	876	RIP RAP, CLASS B	2 TON		
0033	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,075 SY		
0034	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	26 LF		
003E	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		
003E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	10 EA		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	68 SF		
003E	4430000000-N	1130	DRUMS	10 EA		
003E	4435000000-N	1135	CONES	10 EA		
004C	4445000000-E	1145	BARRICADES (TYPE III)	144 LF		
0041	4455000000-N	1150	FLAGGER	30 MD		
0042	6000000000-E	1605	TEMPORARY SILT FENCE	1,200 LF		
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115 TON		
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	210 TON		
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	55 TON		
004E	6015000000-E	1615	TEMPORARY MULCHING	4.5 ACR		
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.5 TON		
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	350 LF		
005C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0051	6029000000-E	SP	SAFETY FENCE	450 LF		
0052	6030000000-E	1630	SILT EXCAVATION	620 CY		
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,400 SY		
0054	6037000000-E	SP	COIR FIBER MAT	25 SY		
005E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,260 SY		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	70 LF		
0057	6071030000-E	SP	COIR FIBER BAFFLES	195 LF		
005E	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0059	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
006C	6087000000-E	1660	MOWING	2.5 ACR		
0061	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0062	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0063	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0064	6108000000-E	1665	FERTILIZER TOPDRESSING	3 TON		
006E	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0067	6126000000-E	SP	STREAMBANK REFORESTATION	0.1 ACR		
<b>STRUCTURE ITEMS</b>						
006E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21 + 82.50-L-)	Lump Sum	L.S.	
006E	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (21 + 82.50-L-)	Lump Sum	L.S.	
007C	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,824 SF		
0071	8161000000-E	420	GROOVING BRIDGE FLOORS	3,728 SF		
0072	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	46.9 CY		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21 + 82.50-L-)	Lump Sum	L.S.	
0074	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,544 LB		
0075	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	125,600 LS		
0076	8364000000-E	450	HP12X53 STEEL PILES	320 LF		
0077	8503000000-E	460	CONCRETE BARRIER RAIL	226.6 LF		
0078	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	505 TON		
0079	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	562 SY		
008C	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1207/Nov05/Q170644.35/D346498580000/E80			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202032**

**County (ies):**   **Union**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General