

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0015000000-N	205	SEALING ABANDONED WELLS	1 EA		
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16 + 93.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	45 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
001C	0241000000-E	SP	GENERIC GRADING ITEM ROCK PLATING	145 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	10 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	24 LF		
0013	0995000000-E	340	PIPE REMOVAL	22 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	320 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	340 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	340 TON		
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	52 TON		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	11 EA		
002C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0021	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	0.22 LF		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	65 LF		
0024	3030000000-E	862	STEEL BM GUARDRAIL	375 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0027	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
002E	3628000000-E	876	RIP RAP, CLASS I	50 TON		
0029	3635000000-E	876	RIP RAP, CLASS II	280 TON		
003C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	605 SY		
0031	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	13 LF		
0032	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0033	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	9 EA		
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	422 SF		
003E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0036	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0037	4430000000-N	1130	DRUMS	25 EA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4435000000-N	1135	CONES	25	EA	
003E	4445000000-E	1145	BARRICADES (TYPE III)	96	LF	
004C	4455000000-N	1150	FLAGGER	12	MD	
0041	6000000000-E	1605	TEMPORARY SILT FENCE	600	LF	
0042	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120	TON	
0043	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	210	TON	
0044	6012000000-E	1610	SEDIMENT CONTROL STONE	125	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
004E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0047	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
004E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	30	LF	
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1	EA	
005C	6029000000-E	SP	SAFETY FENCE	250	LF	
0051	6030000000-E	1630	SILT EXCAVATION	430	CY	
0052	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,600	SY	
0053	6037000000-E	SP	COIR FIBER MAT	20	SY	
0054	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	550	SY	
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	300	LF	
005E	6071030000-E	SP	COIR FIBER BAFFLES	130	LF	

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6071050000-E	SP	*** SKIMMER (1-1/2")	3	EA	
005E	6084000000-E	1660	SEEDING & MULCHING	12	ACR	
005E	6087000000-E	1660	MOWING	1	ACR	
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
0064	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
006E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

\*\*\*\*\* BEGIN SCHEDULE AA \*\*\*\*\*  
\*\*\*\*\* ( 3 ALTERNATES ) \*\*\*\*\*

006E AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	52	LF	
-------------	--------------	-----	------------------------------------	----	----	--

\*\*\* OR \*\*\*

0067 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28	LF	
-------------	--------------	-----	------------------------------------	----	----	--

006E AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	24	LF	
-------------	--------------	----	---	----	----	--

\*\*\* OR \*\*\*

006E AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28	LF	
-------------	--------------	-----	------------------------------------	----	----	--

007C AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	24	LF	
-------------	--------------	----	----------------------------------	----	----	--

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0071	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+93.00-L-)	Lump Sum	L.S.	
0072	8096000000-E	SP	PILE EXCAVATION IN SOIL	61 LF		
0073	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	34 LF		
0074	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+93.00-L-)	Lump Sum	L.S.	
0075	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	34.3 CY		
0076	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+93.00-L-)	Lump Sum	L.S.	
0077	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,524 LB		
0078	8364000000-E	450	HP12X53 STEEL PILES	225 LF		
0079	8391000000-N	450	STEEL PILE POINTS	9 EA		
0080	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	195.5 LF		
0081	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	550 TON		
0082	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	610 SY		
0083	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0084	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,075.25 LF		

0831/Dec09/Q17431.52/D358714380000/E84

Total Amount Of Bid For Entire Project :

**Contract No**     **C202048**

**County (ies):**   **Alamance**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General

Signature Sheet (Bid - Acceptance by Department)