

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15 + 70.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	245 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	5 TON		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	12 LF		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	20 LF		
0013	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0014	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	190 TON		
0015	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	150 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	20 TON		
0017	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	2033000000-E	815	SUBDRAIN FINE AGGREGATE	35 CY		
001E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
002C	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0021	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0022	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0024	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
002E	2556000000-E	846	SHOULDER BERM GUTTER	72 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	150 LF		
0027	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
002E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
003C	3628000000-E	876	RIP RAP, CLASS I	16 TON		
0031	3649000000-E	876	RIP RAP, CLASS B	3 TON		
0032	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	285 SY		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	221 SF		
0034	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	84 SF		
003E	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,440	LF	
0037	6000000000-E	1605	TEMPORARY SILT FENCE	200	LF	
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120	TON	
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120	TON	
004C	6012000000-E	1610	SEDIMENT CONTROL STONE	40	TON	
0041	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
0044	6029000000-E	SP	SAFETY FENCE	180	LF	
004E	6030000000-E	1630	SILT EXCAVATION	300	CY	
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	850	SY	
0047	6037000000-E	SP	COIR FIBER MAT	25	SY	
004E	6042000000-E	1632	1/4" HARDWARE CLOTH	40	LF	
004E	6071030000-E	SP	COIR FIBER BAFFLES	200	LF	
005C	6071050000-E	SP	*** SKIMMER (1-1/2")	4	EA	
0051	6084000000-E	1660	SEEDING & MULCHING	6.5	ACR	
0052	6087000000-E	1660	MOWING	0.5	ACR	
0053	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0054	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0057	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
005E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
STRUCTURE ITEMS						
005E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 70.50-L-)	Lump Sum	L.S.	
006C	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15 + 70.50-L-)	Lump Sum	L.S.	
0061	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	24 CY		
0062	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 70.50-L-)	Lump Sum	L.S.	
006E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	3,748 LB		
0064	8364000000-E	450	HP12X53 STEEL PILES	275 LF		
006E	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	105.21 LF		
006E	8590000000-E	876	RIP RAP, CLASS ** (I)	84 TON		
0067	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	93 SY		
006E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
006E	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	526.04 LF		

Contract No **C202021**

County (ies): **Henderson**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General