

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (17 + 35.50)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	109 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	295 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	50 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	32 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	36 LF		
0013	0345000000-E	310	24" SIDE DRAIN PIPE	32 LF		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	196 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	80 LF		
0016	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	76 LF		
0017	0995000000-E	340	PIPE REMOVAL	104 LF		
0018	1121000000-E	520	AGGREGATE BASE COURSE	270 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	560	TON	
002C	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	380	TON	
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	50	TON	
0022	2022000000-E	815	SUBDRAIN EXCAVATION	112	CY	
0023	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84	CY	
0024	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500	LF	
0025	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15	EA	
0026	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
0027	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5	EA	
0029	2355000000-N	840	FRAME WITH GRATE, STD 840.29	5	EA	
003C	2556000000-E	846	SHOULDER BERM GUTTER	30	LF	
0031	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	320	LF	
0032	3630000000-E	862	STEEL BM GUARDRAIL	500	LF	
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0034	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6	EA	
0035	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4	EA	
0036	3635000000-E	876	RIP RAP, CLASS II	35	TON	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3649000000-E	876	RIP RAP, CLASS B	250	TON	
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,705	SY	
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	430	SF	
004C	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	180	SF	
0041	4430000000-N	1130	DRUMS	30	EA	
0042	4445000000-E	1145	BARRICADES (TYPE III)	80	LF	
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,200	LF	
0044	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	20	LF	
004E	6000000000-E	1605	TEMPORARY SILT FENCE	1,600	LF	
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	350	TON	
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180	TON	
004E	6012000000-E	1610	SEDIMENT CONTROL STONE	270	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	3	ACR	
005C	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0051	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5	TON	
0052	6024000000-E	1622	TEMPORARY SLOPE DRAINS	160	LF	
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	3	EA	
0054	6029000000-E	SP	SAFETY FENCE	1,000	LF	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6030000000-E	1630	SILT EXCAVATION	850 CY		
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0057	6037000000-E	SP	COIR FIBER MAT	50 SY		
005E	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	50 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	100 LF		
006C	6070000000-N	SP	SPECIAL STILLING BASINS	8 EA		
0061	6071030000-E	SP	COIR FIBER BAFFLES	480 LF		
0062	6071050000-E	SP	*** SKIMMER (1-1/2")	6 EA		
006E	6084000000-E	1660	SEEDING & MULCHING	15 ACR		
0064	6087000000-E	1660	MOWING	1.5 ACR		
006E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006E	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
006E	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
006E	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
007C	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0071	6123000000-E	1670	REFORESTATION	0.25 ACR		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0072	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (17 + 35.50-L-)	Lump Sum	L.S.	
0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17 + 35.50-L-)	Lump Sum	L.S.	
0074	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	33.2 LF		
0075	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	29 LF		
0076	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	26.4 LF		
0077	8113000000-N	SP	SID INSPECTION	2 EA		
0078	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0079	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	795 CY		
0080	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	5,054 SF		
0081	8161000000-E	420	GROOVING BRIDGE FLOORS	4,636 SF		
0082	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	130.8 CY		
0083	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17 + 35.50-L-)	Lump Sum	L.S.	
0084	8217000000-E	425	REINFORCING STEEL (BRIDGE)	25,497 LB		
0085	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,695 LB		
0086	8262000000-E	430	45" PRESTRESSED CONCRETE GIR- DERS	627.29 LF		
0087	8364000000-E	450	HP12X53 STEEL PILES	265 LF		
0088	8503000000-E	460	CONCRETE BARRIER RAIL	324.33 LF		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	333 TON		
009C	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	370 SY		
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0092	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0907/Dec04/Q63269.02/D420779760000/E92			Total Amount Of Bid For Entire Project :			

**Contract No**     **C202020**

**County (ies):**   **Henderson**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General