

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	20,500 CY		
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	500 TON		
0007	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	34,030 SY		
0008	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL CLASS III	30,800 CY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	160 TON		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	206 LF		
0011	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	462 LF		
0012	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	588 LF		
0013	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (108")	220 LF		
0014	0995000000-E	340	PIPE REMOVAL	242 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	19,700 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	990 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	8,730 TON		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,640 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	675 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	336 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	252 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,500 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	45 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	3 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	18 LF		
0027	2264000000-E	840	PIPE PLUGS	0.045 CY		
0028	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
0029	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	11 LF		
0030	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	7 EA		
0031	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	460 SY		
0032	2830000000-N	858	ADJUSTMENT OF MANHOLES	10 EA		
0033	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	192 SF		
0034	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192 SF		
0035	6000000000-E	1605	TEMPORARY SILT FENCE	9,658 LF		
0036	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	90 TON		
0037	6012000000-E	1610	SEDIMENT CONTROL STONE	144 TON		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0039	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2 TON		
0040	6036000000-E	1631	MATTING FOR EROSION CONTROL	400 SY		
0041	6042000000-E	1632	1/4" HARDWARE CLOTH	3,201 LF		
0042	6071010000-E	SP	WATTLE	441 LF		
0043	6071020000-E	SP	POLYACRYLAMIDE (PAM)	4 LB		
0044	6084000000-E	1660	SEEDING & MULCHING	15.8 ACR		
0045	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0046	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		
0047	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0048	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0811/Jan09/Q138605.845/D132532530000/E48			Total Amount Of Bid For Entire Project :			

Contract No **C202149**

County (ies): **Lenoir**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General