

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0022000000-E	225	UNCLASSIFIED EXCAVATION	5,700 CY		
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	210 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	800 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	800 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	30 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	78 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	148 LF		
0014	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	48 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,000 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	515 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	75 TON		
0019	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0023	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0026	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1 LF		
0027	2354200000-N	840	FRAME WITH GRATE, STD 840.24	3 EA		
0028	2355000000-N	840	FRAME WITH GRATE, STD 840.29	1 EA		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	4 EA		
0031	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0032	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	210 LF		
0033	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	10 EA		
0034	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	20 EA		
0035	3557000000-E	866	ADDITIONAL BARBED WIRE	100 LF		
0036	3569000000-E	867	BARBED WIRE FENCE RESET REMOVE AND RESET EXISTING 5 STRAND BARBED WIRE FENCING	100 LF		
0037	3628000000-E	876	RIP RAP, CLASS I	135 TON		
0038	3635000000-E	876	RIP RAP, CLASS II	125 TON		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3649000000-E	876	RIP RAP, CLASS B	165 TON		
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,385 SY		
0041	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	253 SF		
0042	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	104 SF		
0043	4430000000-N	1130	DRUMS	10 EA		
0044	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0045	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	6,480 LF		
0046	6000000000-E	1605	TEMPORARY SILT FENCE	480 LF		
0047	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	180 TON		
0048	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	185 TON		
0049	6012000000-E	1610	SEDIMENT CONTROL STONE	175 TON		
0050	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0051	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0052	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0053	6029000000-E	SP	SAFETY FENCE	225 LF		
0054	6030000000-E	1630	SILT EXCAVATION	600 CY		
0055	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,000 SY		
0056	6037000000-E	SP	COIR FIBER MAT	25 SY		
0057	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	85 SY		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0059	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0060	6071030000-E	SP	COIR FIBER BAFFLES	200 LF		
0061	6071050000-E	SP	*** SKIMMER (1-1/2")	4 EA		
0062	6084000000-E	1660	SEEDING & MULCHING	11 ACR		
0063	6087000000-E	1660	MOWING	1 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0068	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0094	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+85.00 -L-)	Lump Sum	L.S.	

STRUCTURE ITEMS

0070	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (18+85.00-L-)	Lump Sum	L.S.	
0071	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+85.00-L-)	Lump Sum	L.S.	
0072	8096000000-E	SP	PILE EXCAVATION IN SOIL	90 LF		
0073	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	32 LF		

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	5.4 LF		
0075	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	22 LF		
0076	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	11.4 LF		
0077	8113000000-N	SP	SID INSPECTION	1 EA		
0078	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0079	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	880 CY		
0080	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,395 SF		
0081	8161000000-E	420	GROOVING BRIDGE FLOORS	4,261 SF		
0082	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	56.5 CY		
0083	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+85.00-L-)	Lump Sum	L.S.	
0084	8217000000-E	425	REINFORCING STEEL (BRIDGE)	11,127 LB		
0085	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,169 LB		
0086	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	509 LF		
0087	8364000000-E	450	HP12X53 STEEL PILES	280 LF		
0088	8391000000-N	450	STEEL PILE POINTS	8 EA		
0089	8503000000-E	460	CONCRETE BARRIER RAIL	256.667 LF		
0090	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	500 TON		
0091	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	560 SY		
0092	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Lincoln

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0093	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0914/Jan08/Q48322.467/D437955360000/E93

Total Amount Of Bid For Entire Project :

Contract No **C202049**

County (ies): **Lincoln**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General