

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000960000-E	SP	GENERIC MISCELLANEOUS ITEM ROCK PLATING	120 SY		
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (23+85.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	450 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	1,900 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	300 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	25 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0012	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	116 LF		
0013	0995000000-E	340	PIPE REMOVAL	54 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	225 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	945 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	300 TON		
0018	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	61 TON		

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	12	EA	
0020	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2	EA	
0021	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	5	LF	
0022	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1	EA	
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1	EA	
0024	2556000000-E	846	SHOULDER BERM GUTTER	10	LF	
0025	3030000000-E	862	STEEL BM GUARDRAIL	575	LF	
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0027	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0028	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0029	3628000000-E	876	RIP RAP, CLASS I	10	TON	
0030	3635000000-E	876	RIP RAP, CLASS II	100	TON	
0031	3649000000-E	876	RIP RAP, CLASS B	16	TON	
0032	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	820	SY	
0033	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
0034	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	392	SF	
0035	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	131	SF	
0036	4430000000-N	1130	DRUMS	12	EA	
0037	4445000000-E	1145	BARRICADES (TYPE III)	108	LF	

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	7,200 LF		
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	12 EA		
004C	6000000000-E	1605	TEMPORARY SILT FENCE	1,100 LF		
0041	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	135 TON		
0042	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	205 TON		
0043	6012000000-E	1610	SEDIMENT CONTROL STONE	215 TON		
0044	6015000000-E	1615	TEMPORARY MULCHING	2.5 ACR		
0045	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
004E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25 TON		
0047	6024000000-E	1622	TEMPORARY SLOPE DRAINS	230 LF		
004E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
004E	6029000000-E	SP	SAFETY FENCE	275 LF		
005C	6030000000-E	1630	SILT EXCAVATION	550 CY		
0051	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,200 SY		
0052	6037000000-E	SP	COIR FIBER MAT	15 SY		
0053	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0054	6070000000-N	SP	SPECIAL STILLING BASINS	6 EA		
005E	6071030000-E	SP	COIR FIBER BAFFLES	250 LF		

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
0057	6084000000-E	1660	SEEDING & MULCHING	12	ACR	
005E	6087000000-E	1660	MOWING	1	ACR	
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
006C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
006E	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	
006E	6123000000-E	1670	REFORESTATION	0.1	ACR	
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
006E	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	28	LF	
AA1						
0067	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	56	LF	
AA1						
*** OR ***						
006E	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	28	LF	
AA2						
006E	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	56	LF	
AA2						
*** OR ***						
007C	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	28	LF	
AA3						

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (18", 0.064")	56 LF		
***** END SCHEDULE AA *****						
STRUCTURE ITEMS						
0072	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (23 + 85.00-L-)	Lump Sum	L.S.	
0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (23 + 85.00-L-)	Lump Sum	L.S.	
0074	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	19.5 LF		
007E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	30 LF		
007E	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	13.5 LF		
0077	8113000000-N	SP	SID INSPECTION	1 EA		
007E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
007E	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	705 CY		
008C	8156000000-E	SP	CONCRETE WEARING SURFACE	6,003 SF		
0081	8161000000-E	420	GROOVING BRIDGE FLOORS	6,717 SF		
0082	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	62.4 CY		
0083	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (23 + 85.00-L-)	Lump Sum	L.S.	
0084	8217000000-E	425	REINFORCING STEEL (BRIDGE)	14,458 LB		

County : Orange

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0085	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,950 LB		
0086	8364000000-E	450	HP12X53 STEEL PILES	400 LF		
0087	8475000000-E	460	TWO BAR METAL RAIL	380 LF		
0088	8517000000-E	460	1'-***X ***** CONCRETE PARA- PET (1'-2" X 3'-0 3/4")	395.5 LF		
0089	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	375 TON		
0090	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	415 SY		
0091	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0092	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0093	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	2,173.875 LF		

1300/Dec10/Q54228.125/D425254920000/E93

Total Amount Of Bid For Entire Project :

Contract No **C202047**

County (ies): **Orange County**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General