

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	16,000 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	950 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	1,500 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	390 CY		
0008	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	500 SY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,500 SY		
0011	0248000000-N	SP	GENERIC GRADING ITEM GRADING OF EXISTING ROAD	Lump Sum	L.S.	
0012	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	60 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	52 LF		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	44 LF		
0015	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	56 LF		
0016	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	372 LF		
0017	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	10 EA		
0018	0995000000-E	340	PIPE REMOVAL	84 LF		
0019	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1121000000-E	520	AGGREGATE BASE COURSE	200 TON		
0021	1330000000-E	607	INCIDENTAL MILLING	225 SY		
0022	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,110 TON		
0023	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	670 TON		
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	92 TON		
0025	2000000000-N	806	RIGHT OF WAY MARKERS	28 EA		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	6 EA		
0027	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0028	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0029	2556000000-E	846	SHOULDER BERM GUTTER	450 LF		
0030	3030000000-E	862	STEEL BM GUARDRAIL	537.5 LF		
0031	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0032	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0033	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0034	3649000000-E	876	RIP RAP, CLASS B	250 TON		
0035	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,020 SY		
0036	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	33 LF		
0037	4102000000-N	904	SIGN ERECTION, TYPE E	4 EA		
0038	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	360 SF		
0040	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	114 SF		
0041	4430000000-N	1130	DRUMS	20 EA		
0042	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0043	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	18,800 LF		
0044	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	60 EA		
0045	6000000000-E	1605	TEMPORARY SILT FENCE	2,900 LF		
0046	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	225 TON		
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	330 TON		
0048	6012000000-E	1610	SEDIMENT CONTROL STONE	150 TON		
0049	6015000000-E	1615	TEMPORARY MULCHING	8 ACR		
0050	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	250 LB		
0051	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2.75 TON		
0052	6024000000-E	1622	TEMPORARY SLOPE DRAINS	285 LF		
0053	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		
0054	6029000000-E	SP	SAFETY FENCE	355 LF		
0055	6030000000-E	1630	SILT EXCAVATION	1,300 CY		
0056	6036000000-E	1631	MATTING FOR EROSION CONTROL	6,400 SY		
0057	6037000000-E	SP	COIR FIBER MAT	20 SY		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	2,050 SY		
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
0060	6071010000-E	SP	WATTLE	125 LF		
0061	6071020000-E	SP	POLYACRYLAMIDE (PAM)	50 LB		
0062	6071030000-E	SP	COIR FIBER BAFFLES	340 LF		
0063	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
0064	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
0065	6087000000-E	1660	MOWING	3.5 ACR		
0066	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0067	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0068	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150 LB		
0069	6108000000-E	1665	FERTILIZER TOPDRESSING	4 TON		
0070	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0071	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0088	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (30+85.00 -L-)	Lump Sum	L.S.	

STRUCTURE ITEMS

0072	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (30+85.00-L-)	Lump Sum	L.S.	
0073	8112730000-N	SP	PDA TESTING	2 EA		

County : Randolph

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0075	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	4,972 SF		
0076	8161000000-E	420	GROOVING BRIDGE FLOORS	4,407 SF		
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	57.4 CY		
0078	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (30+85.00-L-)	Lump Sum	L.S.	
0079	8217000000-E	425	REINFORCING STEEL (BRIDGE)	10,693 LB		
0080	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	664.46 LF		
0081	8364000000-E	450	HP12X53 STEEL PILES	330 LF		
0082	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	360 LF		
0083	8503000000-E	460	CONCRETE BARRIER RAIL	336.615 LF		
0084	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,015 TON		
0085	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,125 SY		
0086	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0087	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
1304/Jan07/Q85208.775/D381110880000/E88			Total Amount Of Bid For Entire Project :			

Contract No **C202046**

County (ies): **Randolph**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General