

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (15+69.00-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	450 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	540 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	540 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	15 TON		
001C	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32 LF		
0011	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	48 LF		
0012	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	52 LF		
0013	0995000000-E	340	PIPE REMOVAL	72 LF		
0014	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	240 TON		
0016	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	72 TON		
0017	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	240 TON		

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	30 TON		
001E	2022000000-E	815	SUBDRAIN EXCAVATION	45 CY		
002C	2033000000-E	815	SUBDRAIN FINE AGGREGATE	34 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0022	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0024	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
002E	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0027	2556000000-E	846	SHOULDER BERM GUTTER	60 LF		
002E	3030000000-E	862	STEEL BM GUARDRAIL	150 LF		
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
003C	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0031	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0032	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	12.5 LF		
003E	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	1 EA		
0034	3559000000-E	866	** STRAND BARBED WIRE FENCE WITH POSTS (5)	800 LF		

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3575000000-E	SP	GENERIC FENCING ITEM 60" CHAIN LINK FENCE WITH POSTS AND BARBED WIRE	100 LF		
003E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	545 SY		
0037	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
003E	3684000000-E	SP	GENERIC EROSION CONTROL ITEM RIP RAP, CLASS B, NATIVE DARK- COLORED STONE	12 TON		
003E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	80 SF		
004C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	112 SF		
0041	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	30 SF		
0042	4430000000-N	1130	DRUMS	36 EA		
004E	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0044	4455000000-N	1150	FLAGGER	30 MD		
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	15,600 LF		
004E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	300 LF		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	2,200 LF		
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	160 TON		
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	90 TON		
005C	6012000000-E	1610	SEDIMENT CONTROL STONE	190 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.25	TON	
0054	6024000000-E	1622	TEMPORARY SLOPE DRAINS	40	LF	
0055	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1	EA	
0056	6029000000-E	SP	SAFETY FENCE	600	LF	
0057	6030000000-E	1630	SILT EXCAVATION	290	CY	
0058	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,100	SY	
0059	6037000000-E	SP	COIR FIBER MAT	15	SY	
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	220	LF	
0061	6070000000-N	SP	SPECIAL STILLING BASINS	4	EA	
0062	6071010000-E	SP	WATTLE	75	LF	
0063	6071020000-E	SP	POLYACRYLAMIDE (PAM)	27	LB	
0064	6071030000-E	SP	COIR FIBER BAFFLES	70	LF	
0065	6071050000-E	SP	*** SKIMMER (1-1/2")	2	EA	
0066	6084000000-E	1660	SEEDING & MULCHING	2	ACR	
0067	6087000000-E	1660	MOWING	0.5	ACR	
0068	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0069	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0070	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0071	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5	TON	
0072	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0074	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0075	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (15 + 69.00-L-)	Lump Sum	L.S.	
0076	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15 + 69.00-L-)	Lump Sum	L.S.	
0077	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (15 + 69.00-L-)	Lump Sum	L.S.	
0078	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	30.8 CY		
0079	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15 + 69.00-L-)	Lump Sum	L.S.	
0080	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,037 LB		
0081	8364000000-E	450	HP12X53 STEEL PILES	340 LF		
0082	8391000000-N	450	STEEL PILE POINTS	14 EA		
0083	8468000000-E	460	ONE BAR METAL RAIL	148.158 LF		
0084	8517000000-E	460	1'-**X ***** CONCRETE PARA- PET (1'-0" X 1'-10 1/8")	164.8 LF		
0085	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	245 SY		
0086	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0087	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	741.656 LF		

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8874000000-E	SP	GENERIC STRUCTURE ITEM RIP RAP,CLASS II (2'-0" THICK)	465	TON	

1103/Dec10/Q34060.514/D390570810000/E88

Total Amount Of Bid For Entire Project :

Contract No **C202022**

County (ies): **Surry**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General