

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0000720000-N	SP	FIELD OFFICE	40 MO		
0004	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (38 + 88.50)	Lump Sum	L.S.	
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0057000000-E	226	UNDERCUT EXCAVATION	8,400 CY		
0008	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	1 EA		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	335 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	4,350 SF		
0012	0234000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS III	8,200 CY		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	80 TON		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	20 LF		
0015	0344000000-E	310	18" SIDE DRAIN PIPE	24 LF		
0016	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	208 LF		
0017	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	300 LF		
0018	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	68 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	116 LF		
0020	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	4 EA		
0021	0973100000-E	330	*** WELDED STEEL PIPE IN SOIL (60")	120 LF		
0022	1121000000-E	520	AGGREGATE BASE COURSE	60 TON		
0023	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0024	1275000000-E	600	PRIME COAT	57 GAL		
0025	1330000000-E	607	INCIDENTAL MILLING	300 SY		
0026	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	2,610 TON		
0027	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,420 TON		
0028	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	205 TON		
0029	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200 TON		
0030	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0031	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0032	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0033	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0034	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0035	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0036	2209000000-E	838	ENDWALLS	36.7 CY		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2220000000-E	838	REINFORCED ENDWALLS	5.6 CY		
003E	2253000000-E	840	PIPE COLLARS	0.893 CY		
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	7 EA		
004C	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	10.2 CY		
0041	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3 LF		
0042	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0043	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0044	2556000000-E	846	SHOULDER BERM GUTTER	95 LF		
004E	3030000000-E	862	STEEL BM GUARDRAIL	2,750 LF		
004E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0047	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
004E	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
004E	3628000000-E	876	RIP RAP, CLASS I	74 TON		
005C	3649000000-E	876	RIP RAP, CLASS B	242 TON		
0051	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,584 SY		
0052	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	3 EA		
0053	4082000000-E	903	SUPPORTS, WOOD	41 LF		
0054	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
005E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	11 EA		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	40 SF		
0057	4430000000-N	1130	DRUMS	30 EA		
005E	4435000000-N	1135	CONES	95 EA		
005E	4445000000-E	1145	BARRICADES (TYPE III)	60 LF		
006C	4450000000-N	1150	FLAGGER	740 HR		
0061	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	3 EA		
0062	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	1 EA		
006E	4480000000-N	1165	TMIA	2 EA		
0064	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	249 LF		
006E	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	86 EA		
006E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5,330 LF		
0067	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	5,330 LF		
006E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (II)	8,000 LF		
006E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	6,000 LF		
007C	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	30,332 LF		
0071	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	59 EA		
0072	6000000000-E	1605	TEMPORARY SILT FENCE	8,100 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0074	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,085 TON		
007E	6012000000-E	1610	SEDIMENT CONTROL STONE	730 TON		
007E	6015000000-E	1615	TEMPORARY MULCHING	12 ACR		
0077	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	450 LB		
007E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.75 TON		
007E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	750 LF		
008C	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	16 EA		
0081	6029000000-E	SP	SAFETY FENCE	1,000 LF		
0082	6030000000-E	1630	SILT EXCAVATION	2,165 CY		
0083	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,380 SY		
0084	6037000000-E	SP	COIR FIBER MAT	20 SY		
008E	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
008E	6070000000-N	SP	SPECIAL STILLING BASINS	25 EA		
0087	6071030000-E	SP	COIR FIBER BAFFLES	750 LF		
008E	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
008E	6071050000-E	SP	*** SKIMMER (2")	1 EA		
009C	6084000000-E	1660	SEEDING & MULCHING	19 ACR		
0091	6087000000-E	1660	MOWING	11.5 ACR		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	6090000000-E	1661	SEED FOR REPAIR SEEDING	100 LB		
0093	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.5 TON		
0094	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	475 LB		
009E	6108000000-E	1665	FERTILIZER TOPDRESSING	13.75 TON		
009E	6111000000-E	SP	IMPERVIOUS DIKE	430 LF		
0097	6114000000-N	SP	SPECIALIZED HAND MOWING	6 HR		
009E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
009E	6123000000-E	1670	REFORESTATION	0.1 ACR		
010C	6129000000-E	1670	WETLAND REFORESTATION	3.05 ACR		
0101	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	3.05 ACR		
0102	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	3.05 ACR		
STRUCTURE ITEMS						
010E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (38 + 88.50-L-)	Lump Sum	L.S.	
0104	8028000000-N	SP	REMOVAL OF EXISTING STRUCTURES AT STATION ***** (38 + 88.50-L-)	Lump Sum	L.S.	
010E	8108000000-E	SP	***-*** DIA DRILLED PIERS (4'-6")	401 LF		
010E	8108000000-E	SP	***-*** DIA DRILLED PIERS (5'-6")	1,362 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8111000000-E	SP	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (4'-6")	10 LF		
010E	8111000000-E	SP	PERMANENT STEEL CASING FOR ***-*** DIA DRILLED PIER (5'-6")	517.2 LF		
010E	8112730000-N	SP	PDA TESTING	3 EA		
011C	8112740000-N	SP	PDA ASSISTANCE	3 EA		
0111	8113000000-N	SP	SID INSPECTION	12 EA		
0112	8114000000-N	SP	SPT TESTING	12 EA		
011E	8115000000-N	SP	CROSSHOLE SONIC LOGGING	4 EA		
0114	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	65,212 SF		
011E	8161000000-E	420	GROOVING BRIDGE FLOORS	53,997 SF		
011E	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	409.8 CY		
0117	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	667.4 CY		
011E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (38 + 88.50-L-)	Lump Sum	L.S.	
011E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	658,010 LB		
012C	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	80,157 LB		
0121	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	7,797.33 LF		
0122	8385000000-E	450	PP ** X **** STEEL PILES (12" X 0.375")	675 LF		
012E	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (12" X 0.375")	4,560 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0124	8385200000-E	450	PP ** X **** GALVANIZED STEEL PILES (24" X 0.500")	2,820 LF		
012E	8392000000-N	450	PIPE PILE PLATES	178 EA		
012E	8393000000-N	450	PILE REDRIVES	85 EA		
0127	8503000000-E	460	CONCRETE BARRIER RAIL	3,922.5 LF		
012E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	1,036 TON		
012E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	1,151 SY		
013C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0131	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0132	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM AT STA***** (38 + 88.50-L-)	Lump Sum	L.S.	
0133	8744000000-N	SP	SOLAR ARRAY SUPPORT PLATFORM	Lump Sum	L.S.	

0812/Jan07/Q990647.573/D608364320000/E133

Total Amount Of Bid For Entire Project :

Contract No **C201495**

County (ies): **Pitt**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General