

County : Polk

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000950000-E	SP	GENERIC MISCELLANEOUS ITEM TEMPORARY SOIL NAIL WALLS	2,170 SF		
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	130 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0010	0223000000-E	SP	ROCK PLATING	165 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	30 TON		
0012	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	30 LF		
0013	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	168 LF		
0014	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	6 EA		
0015	0995000000-E	340	PIPE REMOVAL	20 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	107 TON		
0018	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	63 TON		

County : Polk

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	9 TON		
0020	2022000000-E	815	SUBDRAIN EXCAVATION	30 CY		
0021	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0022	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0023	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0024	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0025	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0026	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0027	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.5 LF		
0028	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0029	2396000000-N	840	FRAME WITH COVER, STD 840.54	2 EA		
0030	2556000000-E	846	SHOULDER BERM GUTTER	19 LF		
0031	2619000000-E	850	4" CONCRETE PAVED DITCH	15 SY		
0032	3030000000-E	862	STEEL BM GUARDRAIL	25 LF		
0033	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (350 TL-2)	2 EA		
0036	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, SHOP CURVED)	4 EA		

County : Polk

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
0038	3628000000-E	876	RIP RAP, CLASS I	5 TON		
0039	3642000000-E	876	RIP RAP, CLASS A	20 TON		
0040	3649000000-E	876	RIP RAP, CLASS B	10 TON		
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	275 SY		
0042	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	238 SF		
0043	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0044	4430000000-N	1130	DRUMS	20 EA		
0045	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
0046	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,800 LF		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	450 LF		
0048	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120 TON		
0049	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200 TON		
0050	6012000000-E	1610	SEDIMENT CONTROL STONE	80 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0054	6029000000-E	SP	SAFETY FENCE	375 LF		
0055	6030000000-E	1630	SILT EXCAVATION	270 CY		

County : Polk

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6036000000-E	1631	MATTING FOR EROSION CONTROL	650 SY		
0057	6037000000-E	SP	COIR FIBER MAT	10 SY		
0058	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	20 SY		
0059	6042000000-E	1632	1/4" HARDWARE CLOTH	125 LF		
0060	6071030000-E	SP	COIR FIBER BAFFLES	75 LF		
0061	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0062	6084000000-E	1660	SEEDING & MULCHING	8 ACR		
0063	6087000000-E	1660	MOWING	1 ACR		
0064	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0065	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0066	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0067	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0068	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0069	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0070	6123000000-E	1670	REFORESTATION	0.2 ACR		

WALL ITEMS

0071	8801000000-E	SP	MSE RETAINING WALLS	1,600 SF		
------	--------------	----	---------------------	-------------	--	--

County : Polk

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
STRUCTURE ITEMS						
0072	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (12+69.00-L-)	Lump Sum	L.S.	
0073	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	2,604 SF		
0074	8161000000-E	420	GROOVING BRIDGE FLOORS	2,450 SF		
0075	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	58.7 CY		
0076	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (12+69.00-L-)	Lump Sum	L.S.	
0077	8217000000-E	425	REINFORCING STEEL (BRIDGE)	7,705 LB		
0078	8280000000-E	440	APPROX LBS STRUCTURAL STEEL	94,000 LS		
0079	8364000000-E	450	HP12X53 STEEL PILES	180 LF		
0080	8391000000-N	450	STEEL PILE POINTS	12 EA		
0081	8505000000-E	SP	VERTICAL CONCRETE BARRIER RAIL	214.91 LF		
0082	8590000000-E	876	RIP RAP, CLASS ** (A)	90 TON		
0083	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	100 SY		
0084	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0085	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1401/Jan13/Q118798.06/D364195130000/E85

Total Amount Of Bid For Entire Project :

Contract No **C202070**

County (ies): **Polk**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General