

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19 + 52.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	4 EA		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	6 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	65 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	500 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	20 LF		
0014	0995000000-E	340	PIPE REMOVAL	144 LF		
0015	0996000000-N	350	PIPE CLEAN-OUT	4 EA		
0016	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,090 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	970 TON		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	730 TON		
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	140 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	23 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	17 CY		
0023	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0025	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0026	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0028	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	2 LF		
0029	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	2 EA		
0030	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	4 EA		
0031	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2 EA		
0032	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0033	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,590 LF		
0034	2591000000-E	848	4" CONCRETE SIDEWALK	430 SY		
0035	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	3 EA		
0036	2612000000-E	848	6" CONCRETE DRIVEWAY	40 SY		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	30 SY		
003E	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	1 EA		
003E	2893000000-N	SP	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
004C	3030000000-E	862	STEEL BM GUARDRAIL	162.5 LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0042	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	2 EA		
004E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0044	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	350 SY		
004E	4082000000-E	903	SUPPORTS, WOOD	324 LF		
004E	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0047	4102000000-N	904	SIGN ERECTION, TYPE E	17 EA		
004E	4108000000-N	904	SIGN ERECTION, TYPE F	1 EA		
004E	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	2 EA		
005C	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	4 EA		
0051	4141000000-N	907	DISPOSAL OF SUPPORT, WOOD	4 EA		
0052	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	4 EA		
005E	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	14 EA		
0054	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	1 EA		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	295	SF	
005E	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	144	SF	
0057	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	124	SF	
005E	4430000000-N	1130	DRUMS	35	EA	
005E	4435000000-N	1135	CONES	31	EA	
006C	4445000000-E	1145	BARRICADES (TYPE III)	152	LF	
0061	4450000000-N	1150	FLAGGER	240	HR	
0062	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,521	LF	
0063	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,750	LF	
0064	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	52	LF	
006E	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	43	LF	
006E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	24	LF	
0067	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	2	EA	
006E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	2	EA	
006E	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	1,824	LF	
007C	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	17	EA	
0071	5325600000-E	1510	6" WATER LINE	130	LF	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	5648000000-N	1515	RELOCATE WATER METER	3	EA	
0073	6000000000-E	1605	TEMPORARY SILT FENCE	1,600	LF	
0074	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	135	TON	
0075	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	155	TON	
0076	6012000000-E	1610	SEDIMENT CONTROL STONE	280	TON	
0077	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0078	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0079	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.25	TON	
0080	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50	LF	
0081	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2	EA	
0082	6029000000-E	SP	SAFETY FENCE	500	LF	
0083	6030000000-E	1630	SILT EXCAVATION	200	CY	
0084	6036000000-E	1631	MATTING FOR EROSION CONTROL	350	SY	
0085	6037000000-E	SP	COIR FIBER MAT	15	SY	
0086	6042000000-E	1632	1/4" HARDWARE CLOTH	900	LF	
0087	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	750	SY	
0088	6071030000-E	SP	COIR FIBER BAFFLES	100	LF	
0089	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
0090	6087000000-E	1660	MOWING	1.5	ACR	

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0092	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0093	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0094	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0095	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0096	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0097	6123000000-E	1670	REFORESTATION	0.25 ACR		

STRUCTURE ITEMS

009E	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (19 + 52.00-L-)	Lump Sum	L.S.	
009E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19 + 52.00-L-)	Lump Sum	L.S.	
010C	8112730000-N	SP	PDA TESTING	2 EA		
0101	8112740000-N	SP	PDA ASSISTANCE	2 EA		
0102	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	22,426 SF		
0103	8161000000-E	420	GROOVING BRIDGE FLOORS	16,563 SF		
0104	8175000000-E	420	CLASS AA CONCRETE (BRIDGE)	238.2 CY		
010E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19 + 52.00-L-)	Lump Sum	L.S.	
010E	8224000000-E	425	EPOXY COATED REINFORCING STEEL (BRIDGE)	31,338 LB		

County : Beaufort

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	2,246.05 LF		
0108	8333000000-E	450	16" PRESTRESSED CONC PILES	4,985 LF		
0109	8393000000-N	450	PILE REDRIVES	40 EA		
0110	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	240 TON		
0111	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	260 SY		
0112	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0113	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0114	8867000000-E	SP	GENERIC STRUCTURE ITEM CLASSIC CONCRETE BRIDGE RAIL	909.1 LF		
1502/Feb02/Q99270.35/D491412800000/E114			Total Amount Of Bid For Entire Project :			

Contract No **C201731**

County (ies): **Beaufort**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General