

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+00-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
000E	0050000000-M	226	SUPPLEMENTARY CLEARING & GRUB- BING	1.2 HA		
000E	0057000000-M	226	UNDERCUT EXCAVATION	5,500 M3		
0007	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA- TION	12,000 MTN		
000E	0134000000-M	240	DRAINAGE DITCH EXCAVATION	5,900 M3		
000E	0141000000-M	240	BERM DITCH CONSTRUCTION	190 M		
001C	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	18,500 M2		
0011	0199000000-M	SP	TEMPORARY SHORING	323 M2		
0012	0255000000-M	SP	GENERIC GRADING ITEM EXCAVATION, HAULING, AND DISPOSAL OF CONTAMINATED SOIL	2,000 MTN		
0013	0318000000-M	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	1,410 MTN		
0014	0708000000-M	310	400MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	92.7 M		
001E	0714000000-M	310	450MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	17 M		
001E	0720000000-M	310	600MM BIT COAT CS PIPE CUL- VERTS, TYPE B 1.63MM THICK	20.8 M		
0017	0806000000-M	310	400MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	8 EA		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0808000000-M	310	600MM BIT COAT CS PIPE ELBOWS, TYPE B 1.63MM THICK	4 EA		
001E	0973100000-M	330	***MM WELDED STEEL PIPE IN SOIL (450MM)	44 M		
002C	0973100000-M	330	***MM WELDED STEEL PIPE IN SOIL (750MM)	38 M		
0021	0973100000-M	330	***MM WELDED STEEL PIPE IN SOIL (900MM)	52 M		
0022	0973300000-M	330	***MM WELDED STEEL PIPE NOT IN SOIL (450MM)	15 M		
0023	0973300000-M	330	***MM WELDED STEEL PIPE NOT IN SOIL (750MM)	13 M		
0024	0973300000-M	330	***MM WELDED STEEL PIPE NOT IN SOIL (900MM)	17 M		
002E	0995000000-M	340	PIPE REMOVAL	1,697 M		
002E	0996000000-N	350	PIPE CLEAN-OUT	1 EA		
0027	1121000000-M	520	AGGREGATE BASE COURSE	16,560 MTN		
002E	1220000000-M	545	INCIDENTAL STONE BASE	100 MTN		
002E	1297000000-M	607	MILLING ASPHALT PAVEMENT, **MM DEPTH (80MM)	1,580 M2		
003C	1489000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	13,641 MTN		
0031	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	6,375 MTN		
0032	1498000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	9,036 MTN		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	6,920	MTN	
0034	1519000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	13,668	MTN	
0035	1523000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	10,630	MTN	
0036	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,455	MTN	
0037	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	640	MTN	
0038	1693000000-M	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	750	MTN	
0039	1840000000-M	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	5,715	M	
0040	2000000000-N	806	RIGHT OF WAY MARKERS	161	EA	
0041	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	10	EA	
0042	2209000000-M	838	ENDWALLS	2.6	M3	
0043	2253000000-M	840	PIPE COLLARS	4.8	M3	
0044	2264000000-M	840	PIPE PLUGS	0.76	M3	
0045	2275000000-M	SP	FLOWABLE FILL	160	M3	
0046	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	152	EA	
0047	2308000000-M	840	MASONRY DRAINAGE STRUCTURES	12	M	
0048	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.16)	28	EA	
0049	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.20)	2	EA	

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005C	2354000000-N	840	FRAME WITH GRATE, STD 840.22	1 EA		
0051	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	31 EA		
0052	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2 EA		
0053	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	19 EA		
0054	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	34 EA		
005E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	33 EA		
0056	2396000000-N	840	FRAME WITH COVER, STD 840.54	10 EA		
0057	2418000000-M	SP	FRAME WITH GRATES, DRIVEWAY DROP INLET	11 M		
005E	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLETS	25 EA		
005E	2542000000-M	846	450MM CONCRETE CURB & GUTTER	1,010 M		
006C	2549000000-M	846	750MM CONCRETE CURB & GUTTER	4,775 M		
0061	2591000000-M	848	100MM CONCRETE SIDEWALK	3,250 M2		
0062	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	28 EA		
0063	2612000000-M	848	150MM CONCRETE DRIVEWAY	650 M2		
0064	2619000000-M	850	100MM CONCRETE PAVED DITCH	24 M2		
006E	2647000000-M	852	125MM MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	3,660 M2		
006E	2830000000-N	858	ADJUSTMENT OF MANHOLES	11 EA		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0067	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	16 EA		
006E	2875000000-N	859	CONVERT EXISTING CATCH BASIN TO DROP INLET	8 EA		
006E	2950000000-N	SP	CONVERT EXISTING JUNCTION BOX TO DROP INLET	1 EA		
007C	3030000000-M	862	STEEL BM GUARDRAIL	775 M		
0071	3045000000-M	862	STEEL BM GUARDRAIL, SHOP CURVED	75 M		
0072	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
007C	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0074	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	2 EA		
007E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
007E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
0077	3360000000-M	863	REMOVE EXISTING GUARDRAIL	280 M		
007E	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W-BEAM)	2 EA		
007E	3503000000-M	866	WOVEN WIRE FENCE, 1200MM FABRIC	3,190 M		
008C	3509000000-M	866	100MM TIMBER FENCE POSTS, 2.30M LONG	638 EA		
0081	3515000000-M	866	125MM TIMBER FENCE POSTS, 2.50M LONG	231 EA		
0082	3536000000-M	866	CHAIN LINK FENCE, 1200MM FABRIC	130 M		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0083	3542000000-M	866	METAL LINE POSTS FOR 1200MM CHAIN LINK FENCE	36 EA		
0084	3548000000-M	866	METAL TERMINAL POSTS FOR 1200MM CHAIN LINK FENCE	3 EA		
008E	3557000000-M	866	ADDITIONAL BARBED WIRE	300 M		
008E	3565000000-M	866	DOUBLE GATES, ****MM HIGH, ****MM WIDE, ****MM OPENING (1470MM, 1800MM, 3600MM)	1 EA		
0087	3628000000-M	876	RIP RAP, CLASS I	475 MTN		
008E	3649000000-M	876	RIP RAP, CLASS B	170 MTN		
008E	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	4,030 M2		
009C	4048000000-M	902	REINFORCED CONCRETE SIGN FOUNDATIONS	5 M3		
0091	4060000000-M	903	SUPPORTS, BREAKAWAY STEEL BEAM	1,476 KG		
0092	4066000000-M	903	SUPPORTS, SIMPLE STEEL BEAM	988 KG		
0093	4072000000-M	903	SUPPORTS, 4.5-KG STEEL U-CHANNEL	478 M		
0094	4078000000-M	903	SUPPORTS, 3-KG STEEL U-CHANNEL	2 EA		
009E	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		
009E	4102000000-N	904	SIGN ERECTION, TYPE E	79 EA		
0097	4108000000-N	904	SIGN ERECTION, TYPE F	7 EA		
009E	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	5 EA		
009E	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	5 EA		
010C	4114000000-N	904	SIGN ERECTION, MILEMARKERS	2 EA		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0101	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (A)	6 EA		
0102	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (D)	3 EA		
0103	4138000000-N	907	DISPOSAL OF SUPPORT, STEEL BEAM	6 EA		
0104	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	68 EA		
0105	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0106	4400000000-M	1110	WORK ZONE SIGNS (STATIONARY)	80 M2		
0107	4405000000-M	1110	WORK ZONE SIGNS (PORTABLE)	64 M2		
0108	4410000000-M	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	25 M2		
0109	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		
0110	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0111	4430000000-N	1130	DRUMS	700 EA		
0112	4435000000-N	1135	CONES	500 EA		
0113	4445000000-M	1145	BARRICADES (TYPE III)	182 M		
0114	4450000000-N	1150	FLAGGER	5,200 HR		
0115	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	6 EA		
0116	4480000000-N	1165	TMIA	4 EA		
0117	4485000000-M	1170	PORTABLE CONCRETE BARRIER	233 M		
0118	4490000000-M	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	60 M		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
011E	4495000000-M	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	234 M		
012C	4510000000-N	SP	POLICE	2,880 HR		
0121	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	71 EA		
0122	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	3,268 M		
012E	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	5,499 M		
0124	4688000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (150MM, 2.3MM)	8,223 M		
012E	4690000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (150MM, 3.1MM)	1,130 M		
012E	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	1,135 M		
0127	4700000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (300MM, 2.3MM)	903 M		
012E	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	290 M		
012E	4721000000-M	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (3.1MM)	6 EA		
013C	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	140 EA		
0131	4770000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (100MM) (III)	468 M		
0132	4770000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (100MM) (IV)	640 M		
013E	4780000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (200MM) (III)	19 M		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0134	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (III)	4 EA		
013E	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	53,286 M		
013E	4815000000-M	1205	PAINT PAVEMENT MARKING LINES (150MM)	29,139 M		
0137	4820000000-M	1205	PAINT PAVEMENT MARKING LINES (200MM)	4,714 M		
013E	4835000000-M	1205	PAINT PAVEMENT MARKING LINES (600MM)	1,244 M		
013E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	18 EA		
014C	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	434 EA		
0141	4855000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (150MM)	1,913 M		
0142	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	36 EA		
014E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	271 EA		
0144	4915000000-M	1264	2.1M U-CHANNEL POSTS	3 EA		
014E	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	73 EA		
014E	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	22 EA		
0147	4945000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL & RED)	12 EA		
014E	4950000000-N	1267	FLEXIBLE DELINEATORS (YELLOW & RED)	10 EA		
014E	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	3 EA		
015C	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0151	5325000000-M	1510	***MM WATER LINE (25MM)	58 M		
0152	5325200000-M	1510	50MM WATER LINE	29 M		
0153	5325600000-M	1510	150MM WATER LINE	975 M		
0154	5325800000-M	1510	200MM WATER LINE	245 M		
015E	5326200000-M	1510	300MM WATER LINE	2,566 M		
015E	5536000000-M	1515	50MM VALVE	1 EA		
0157	5540000000-M	1515	150MM VALVE	7 EA		
015E	5546000000-M	1515	200MM VALVE	2 EA		
015E	5558000000-M	1515	300MM VALVE	4 EA		
016C	5571600000-M	1515	150MM TAPPING VALVE	1 EA		
0161	5589400000-M	1515	100MM AIR RELEASE VALVE	1 EA		
0162	5643100000-M	1515	20MM WATER METER	1 EA		
0163	5648000000-N	1515	RELOCATE WATER METER	33 EA		
0164	5649000000-N	1515	RECONNECT WATER METER	11 EA		
016E	5653210000-M	1515	RELOCATE 50MM DCV BACK-FLOW PREVENTOR	1 EA		
016E	5656000000-M	1515	***MM RPZ BACK-FLOW PREVENTOR (25MM)	1 EA		
0167	5672000000-N	1515	RELOCATE FIRE HYDRANT	10 EA		
016E	5691300000-M	1520	200MM SANITARY GRAVITY SEWER	319 M		
016E	5691500000-M	1520	300MM SANITARY GRAVITY SEWER	162 M		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
017C	5709000000-M	1520	***MM FORCE MAIN SEWER (350MM)	528 M		
0171	5709000000-M	1520	***MM FORCE MAIN SEWER (65MM)	64 M		
0172	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	20 EA		
0173	5775000000-M	1525	1200MM DIA UTILITY MANHOLE	17 EA		
0174	5781000000-M	1525	UTILITY MANHOLE WALL, 1200MM DIA	17 M		
017E	5800000000-M	1530	ABANDON 150MM UTILITY PIPE	627 M		
017E	5801000000-M	1530	ABANDON 200MM UTILITY PIPE	708 M		
0177	5804000000-M	1530	ABANDON 300MM UTILITY PIPE	2,586 M		
017E	5805000000-M	1530	ABANDON 350MM UTILITY PIPE	595 M		
017E	5815000000-N	1530	REMOVE WATER METER	2 EA		
018C	5816000000-N	1530	ABANDON UTILITY MANHOLE	8 EA		
0181	5877000000-N	SP	SANITARY SEWER PUMP STATION	Lump Sum	L.S.	
0182	5882000000-N	SP	GENERIC UTILITY ITEM ABANDON EXISTING SEWER PUMP STATION	1 EA		
0183	6000000000-M	1605	TEMPORARY SILT FENCE	3,500 M		
0184	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	2,840 MTN		
018E	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	1,050 MTN		
018E	6012000000-M	1610	SEDIMENT CONTROL STONE	1,970 MTN		
0187	6015000000-M	1615	TEMPORARY MULCHING	33 HA		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
018E	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	650 KG		
018E	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	5 MTN		
019C	6024000000-M	1622	TEMPORARY SLOPE DRAINS	425 M		
0191	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7 EA		
019Z	6030000000-M	1630	SILT EXCAVATION	4,500 M3		
019C	6036000000-M	1631	MATTING FOR EROSION CONTROL	34,500 M2		
0194	6037000000-M	SP	COIR FIBER MAT	35 M2		
019E	6038000000-M	SP	PERMANENT SOIL REINFORCEMENT MAT	1,750 M2		
019E	6042000000-M	1632	6.4MM HARDWARE CLOTH	1,225 M		
0197	6071030000-M	SP	COIR FIBER BAFFLES	340 M		
019E	6071050000-M	SP	***MM SKIMMER (38MM)	6 EA		
019E	6071050000-M	SP	***MM SKIMMER (64MM)	1 EA		
020C	6084000000-M	1660	SEEDING & MULCHING	33.5 HA		
0201	6087000000-M	1660	MOWING	20.5 HA		
020Z	6090000000-M	1661	SEED FOR REPAIR SEEDING	450 KG		
020Z	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	1.5 MTN		
0204	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	475 KG		
020E	6108000000-M	1665	FERTILIZER TOPDRESSING	27.5 MTN		
020E	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0207	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
020E	7060000000-M	1705	SIGNAL CABLE	2,360 M		
020S	7120000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 3 SECTION)	41 EA		
021C	7132000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 4 SECTION)	4 EA		
0211	7144000000-M	1705	VEHICLE SIGNAL HEAD (300MM, 5 SECTION)	5 EA		
0212	7228000000-N	SP	RELOCATE EXISTING VEHICLE SIGNAL HEAD	5 EA		
0213	7252000000-M	1710	MESSENGER CABLE (6.35MM)	1,290 M		
0214	7264000000-M	1710	MESSENGER CABLE (9.52MM)	1,150 M		
021E	7288000000-M	1715	PAVED TRENCHING (*****) (1, 50MM)	130 M		
021E	7300000000-M	1715	UNPAVED TRENCHING (*****) (1, 50MM)	350 M		
0217	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	36 EA		
021E	7360000000-N	1720	WOOD POLE	22 EA		
021S	7372000000-N	1721	GUY ASSEMBLY	63 EA		
022C	7408000000-M	1722	25MM RISER WITH WEATHERHEAD	6 EA		
0221	7420000000-M	1722	50MM RISER WITH WEATHERHEAD	28 EA		
0222	7432000000-M	1722	50MM RISER WITH HEAT SHRINK TUBING	5 EA		
0223	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	3,620 M		
0224	7456000000-M	1726	LEAD-IN CABLE (*****) (14-2)	6,560 M		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
022E	7484000000-N	SP	MICROWAVE VEHICLE DETECTOR	2 EA		
022E	7516000000-M	1730	COMMUNICATIONS CABLE (**FIBER) (12)	1,700 M		
0227	7552000000-N	1731	INTERCONNECT CENTER	5 EA		
022E	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER, DROP & REPEAT	5 EA		
022E	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIV- ER	1 EA		
023C	7636000000-N	1745	SIGN FOR SIGNALS	15 EA		
0231	7684000000-N	1750	SIGNAL CABINET FOUNDATION	6 EA		
0232	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	5 EA		
023E	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	34 EA		
0234	7901000000-N	1753	CABINET BASE EXTENDER	5 EA		
023E	7980000000-N	SP	GENERIC SIGNAL ITEM RELOCATE CONTROLLER WITH CAB- INET	1 EA		
023E	7980000000-N	SP	GENERIC SIGNAL ITEM TERMINAL SPLICE CABINET	1 EA		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0237 AA1	0360000000-M	310	300MM RC PIPE CULVERTS, CLASS III	412.8 M		
023E AA1	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	1,371.7 M		
023E AA1	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	301.6 M		
024C AA1	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	504.3 M		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0241 AA1	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	498.2 M		
0242 AA1	0390000000-M	310	900MM RC PIPE CULVERTS, CLASS III	212.4 M		
0243 AA1	0396000000-M	310	1050MM RC PIPE CULVERTS, CLASS III	85.5 M		
0244 AA1	0528000000-M	310	****MM RC PIPE ELBOWS, CLASS III (300MM)	1 EA		
*** OR ***						
0245 AA2	0360000000-M	310	300MM RC PIPE CULVERTS, CLASS III	255.7 M		
0246 AA2	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	1,001.7 M		
0247 AA2	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	294.2 M		
0248 AA2	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	233.4 M		
0249 AA2	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	317.5 M		
0250 AA2	0390000000-M	310	900MM RC PIPE CULVERTS, CLASS III	102.6 M		
0251 AA2	0396000000-M	310	1050MM RC PIPE CULVERTS, CLASS III	52.5 M		
0252 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (1050MM)	33 M		
0253 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (300MM)	157.1 M		
0254 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (375MM)	370 M		
0255 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (450MM)	7.4 M		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0256 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (600MM)	270.9 M		
0257 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (750MM)	180.7 M		
0258 AA2	0536000000-M	SP	****MM HDPE PIPE CULVERTS (900MM)	109.8 M		
0259 AA2	0992000000-M	SP	GENERIC PIPE ITEM 300MM HDPE PIPE ELBOW	1 EA		
*** OR ***						
026C AA3	0360000000-M	310	300MM RC PIPE CULVERTS, CLASS III	255.7 M		
0261 AA3	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	1,001.7 M		
0262 AA3	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	294.2 M		
0263 AA3	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	233.4 M		
0264 AA3	0384000000-M	310	750MM RC PIPE CULVERTS, CLASS III	317.5 M		
026E AA3	0390000000-M	310	900MM RC PIPE CULVERTS, CLASS III	102.6 M		
026E AA3	0396000000-M	310	1050MM RC PIPE CULVERTS, CLASS III	52.5 M		
0267 AA3	0540000000-M	SP	****MM ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ****MM THICK (1000MM, 2.01MM)	33 M		
026E AA3	0540000000-M	SP	****MM ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ****MM THICK (300MM, 1.63MM)	157.1 M		
026E AA3	0540000000-M	SP	****MM ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ****MM THICK (400MM, 1.63MM)	370 M		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
027C AA3	0540000000-M	SP	****MM ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ****MM THICK (450MM, 1.63MM)	7.4 M		
0271 AA3	0540000000-M	SP	****MM ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ****MM THICK (600MM, 1.63MM)	270.9 M		
0272 AA3	0540000000-M	SP	****MM ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ****MM THICK (800MM, 2.01MM)	180.7 M		
0273 AA3	0540000000-M	SP	****MM ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ****MM THICK (900MM, 2.01MM)	109.8 M		
0274 AA3	0992000000-M	SP	GENERIC PIPE ITEM 300MM ALUMINIZED CORRUGATED STEEL PIPE ELBOWS	1 EA		
***** END SCHEDULE AA *****						
WALL ITEMS						
027E	8436000000-M	453	GRAVITY RETAINING WALLS	55 M2		
027E	8496000000-M	460	****MM GALVANIZED STEEL PIPE RAIL (75MM)	45 M		
STRUCTURE ITEMS						
0277	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (22 + 27.571-L-)	Lump Sum	L.S.	
027E	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 22 + 27.571-L-)	Lump Sum	L.S.	
027E	8112730000-N	SP	PDA TESTING	1 EA		
028C	8112740000-N	SP	PDA ASSISTANCE	1 EA		

County : Forsyth, Stokes

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0281	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (22+27.571-L-)	Lump Sum	L.S.	
0282	8147000000-M	420	REINFORCED CONCRETE DECK SLAB	2,138.5 M2		
0283	8161000000-M	420	GROOVING BRIDGE FLOORS	2,123.8 M2		
0284	8182000000-M	420	CLASS A CONCRETE (BRIDGE)	243 M3		
028E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (22+27.571-L-)	Lump Sum	L.S.	
028E	8217000000-M	425	REINFORCING STEEL (BRIDGE)	21,147 KG		
0287	8238000000-M	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	990 KG		
028E	8280000000-M	440	APPROX KG STRUCTURAL STEEL	398,500 LS		
028E	8364000000-M	450	HP310X79 STEEL PILES	2,545 M		
029C	8482000000-M	460	THREE BAR METAL RAIL	139.124 M		
0291	8531000000-M	462	100MM SLOPE PROTECTION	1,050 M2		
0292	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0293	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0294	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0958/Feb05/Q806770.784/D1183655410000/E294

Total Amount Of Bid For Entire Project :

Contract No: C202042

County: Stokes & Forsyth

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)