

**PROJECT: 33469.1.1 (B-4114)**

**COUNTY: WAKE**

**PROJECT SPECIAL PROVISIONS**

**UTILITY**

**GENERAL:**

**THE FOLLOWING UTILITY COMPANIES HAVE FACILITIES THAT WILL BE IN CONFLICT WITH THE CONSTRUCTION OF THIS PROJECT:**

- A. WAKE EMC**
- B. EMBARQ**

**THE CONFLICTING FACILITIES OF THESE CONCERNS WILL BE ADJUSTED PRIOR TO THE DATE OF AVAILABILITY UNLESS OTHERWISE NOTED AND ARE THEREFORE LISTED IN THESE SPECIAL PROVISIONS FOR THE BENEFIT OF THE CONTRACTOR. ALL UTILITY WORK LISTED HEREIN WILL BE DONE BY THE UTILITY OWNERS. ALL UTILITIES ARE SHOWN ON THE PLANS FROM THE BEST AVAILABLE INFORMATION.**

**THE CONTRACTOR’S ATTENTION IS DIRECTED TO ARTICLE 105.8 OF THE STANDARD SPECIFICATIONS.**

**A. WAKE EMC**

- 1. AFTER THE DETOUR HAS BEEN COMPLETED, THE TEMPORARY AERIAL POWER POLE LINES WITH TELEPHONE ATTACHED SHALL BE INSTALLED AND THE EXISTING AERIAL POWER LINE WITH TELEPHONE ATTACHED SHALL BE DISMANTLED AND REMOVED. THE CONTRACTOR SHALL GIVE WAKE EMC TWO (2) WEEKS NOTICE PRIOR TO WHEN THEY CAN BEGAN WORK AND TWO (2) WEEKS TO COMPLETE THEIR WORK. AFTER COMPLETION OF THE NEW BRIDGE, WAKE EMC SHALL INSTALL THE PERMANENT POWER POLE LINE AND THE TEMPORARY POWER LINES SHALL BE DISMANTLED AND REMOVED.THE CONTRACTOR SHALL GIVE WAKE EMC TWO (2) WEEKS NOTICE PRIOR TO WHEN THEY CAN BEGAN WORK AND TWO (2) WEEKS TO COMPLETE THEIR WORK. SEE UTILITIES BY OTHERS PLANS FOR DETAILS.**

**B. EMBARQ**

**1. AFTER EMBARQ HAS COMPLETED THE TEMPORARY AERIAL LINE MOVE WITH WAKE EMC THE EXISTING AERIAL POLE LINE SHALL BE DISMANTLED AND REMOVED. THE CONTRACTOR SHALL GIVE EMBARQ THREE (3) WEEKS NOTICE PRIOR TO WAKE EMC COMPLETING THEIR WORK AND ONE (1) WEEK TO COMPLETE THEIR WORK. AFTER COMPLETION OF THE NEW BRIDGE EMBARQ SHALL INSTALL THE PERMANENT AERIAL LINE MOVE WITH WAKE EMC AND THE TEMPORARY AERIAL POLE LINE SHALL BE DISMANTLED AND REMOVED. THE CONTRACTOR SHALL GIVE EMBARQ THREE (3) WEEKS NOTICE PRIOR TO WAKE EMC COMPLETING THEIR WORK AND ONE (1) WEEK TO COMPLETE THEIR WORK. SEE UTILITIES BY OTHERS PLANS FOR DETAILS.**