

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (14+88.59)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	20 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	36 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	108 LF		
0012	0995000000-E	340	PIPE REMOVAL	30 LF		
0013	1121000000-E	520	AGGREGATE BASE COURSE	310 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0015	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	450 TON		
0016	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	520 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	54 TON		
0018	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2000000000-N	806	RIGHT OF WAY MARKERS	8 EA		
0020	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0021	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0022	2556000000-E	846	SHOULDER BERM GUTTER	110 LF		
0023	2612000000-E	848	6" CONCRETE DRIVEWAY	75 SY		
0024	3030000000-E	862	STEEL BM GUARDRAIL	500 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0027	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0028	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	275 LF		
0029	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	4 EA		
0030	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0031	3635000000-E	876	RIP RAP, CLASS II	12 TON		
0032	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	380 SY		
0033	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0034	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	6 EA		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	156 SF		
0036	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	56 SF		

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4430000000-N	1130	DRUMS	60	EA	
0039	4435000000-N	1135	CONES	30	EA	
0040	4445000000-E	1145	BARRICADES (TYPE III)	32	LF	
0041	4450000000-N	1150	FLAGGER	2,000	HR	
0042	4609000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TEMPORARY TRAFFIC SIGNAL SYSTEM	270	DAY	
0043	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	101	EA	
0044	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	16,016	LF	
0045	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	40	LF	
0046	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,200	LF	
0047	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	20	LF	
0048	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	13	EA	
0049	6000000000-E	1605	TEMPORARY SILT FENCE	2,150	LF	
0050	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	200	TON	
0051	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	170	TON	
0052	6012000000-E	1610	SEDIMENT CONTROL STONE	170	TON	
0053	6015000000-E	1615	TEMPORARY MULCHING	4.5	ACR	
0054	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0055	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5	TON	

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6029000000-E	SP	SAFETY FENCE	600 LF		
0057	6030000000-E	1630	SILT EXCAVATION	570 CY		
0058	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,600 SY		
0059	6037000000-E	SP	COIR FIBER MAT	30 SY		
0060	6042000000-E	1632	1/4" HARDWARE CLOTH	310 LF		
0061	6071030000-E	SP	COIR FIBER BAFFLES	250 LF		
0062	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0063	6084000000-E	1660	SEEDING & MULCHING	5.5 ACR		
0064	6087000000-E	1660	MOWING	3 ACR		
0065	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0066	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0067	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0068	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0069	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0070	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0071	6123000000-E	1670	REFORESTATION	0.3 ACR		

STRUCTURE ITEMS

0072	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (14+88.59-L-)	Lump Sum	L.S.	
------	--------------	----	--	----------	------	--

County : Franklin

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+88.59-L-)	Lump Sum	L.S.	
0074	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (14+88.59-L-)	Lump Sum	L.S.	
0075	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	33.6 CY		
0076	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+88.59-L-)	Lump Sum	L.S.	
0077	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,830 LB		
0078	8364000000-E	450	HP12X53 STEEL PILES	180 LF		
0079	8503000000-E	460	CONCRETE BARRIER RAIL	135.3 LF		
0080	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	250 TON		
0081	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	270 SY		
0082	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0083	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	744.33 LF		

0831/Feb12/Q38644.03/D365137680000/E83

Total Amount Of Bid For Entire Project :

Contract No **C202099**

County (ies): **Franklin**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General