

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (16+57.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA-TION	650 TON		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,000 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRS	5 TON		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	40 LF		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	350 TON		
0012	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	300 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	35 TON		
0014	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0015	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0016	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
0017	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0018	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0020	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0022	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0023	2556000000-E	846	SHOULDER BERM GUTTER	270 LF		
0024	3030000000-E	862	STEEL BM GUARDRAIL	550 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0027	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0028	3649000000-E	876	RIP RAP, CLASS B	4 TON		
0029	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	364 SY		
0030	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	268 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	44 SF		
0033	4445000000-E	1145	BARRICADES (TYPE III)	64 LF		
0034	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,770 LF		
0035	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,770 LF		
0036	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	13 EA		
0037	6000000000-E	1605	TEMPORARY SILT FENCE	625 LF		

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	125 TON		
0039	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	100 TON		
0040	6012000000-E	1610	SEDIMENT CONTROL STONE	30 TON		
0041	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0042	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0043	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	2.25 TON		
0044	6024000000-E	1622	TEMPORARY SLOPE DRAINS	60 LF		
0045	6029000000-E	SP	SAFETY FENCE	250 LF		
0046	6030000000-E	1630	SILT EXCAVATION	460 CY		
0047	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,900 SY		
0048	6037000000-E	SP	COIR FIBER MAT	30 SY		
0049	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	100 SY		
0050	6042000000-E	1632	1/4" HARDWARE CLOTH	40 LF		
0051	6071030000-E	SP	COIR FIBER BAFFLES	200 LF		
0052	6071050000-E	SP	*** SKIMMER (1-1/2")	5 EA		
0053	6084000000-E	1660	SEEDING & MULCHING	9.5 ACR		
0054	6087000000-E	1660	MOWING	1 ACR		
0055	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0056	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0057	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0059	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0060	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
<b>STRUCTURE ITEMS</b>						
0061	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (16+57.00-L-)	Lump Sum	L.S.	
0062	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (16+57.00-L-)	Lump Sum	L.S.	
0063	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	28.9 CY		
0064	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (16+57.00-L-)	Lump Sum	L.S.	
0065	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,798 LB		
0066	8364000000-E	450	HP12X53 STEEL PILES	160 LF		
0067	8391000000-N	450	STEEL PILE POINTS	16 EA		
0068	8503000000-E	460	CONCRETE BARRIER RAIL	155.5 LF		
0069	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	140 TON		
0070	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	150 SY		
0071	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0072	8753100000-E	430	3'-0" X 2'-9" PRESTRESSED CONC BOX BEAMS	777.5 LF		

**Contract No**     **C202098**

**County (ies):**   **Richmond**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General