

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	3,200 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	100 CY		
0006	0106000000-E	230	BORROW EXCAVATION	6,250 CY		
0007	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	9,500 SY		
0008	0199000000-E	SP	TEMPORARY SHORING	420 SF		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	565 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	32 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,206 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,046 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	1,032 LF		
0014	0453000000-E	310	*** PIPE END SECTION (15")	4 EA		
0015	0453000000-E	310	*** PIPE END SECTION (18")	2 EA		
0016	0453000000-E	310	*** PIPE END SECTION (24")	3 EA		
0017	0995000000-E	340	PIPE REMOVAL	767 LF		
0018	0996000000-N	350	PIPE CLEAN-OUT	6 EA		
0019	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1077000000-E	SP	#57 STONE	245	TON	
0021	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	600	SY	
0022	1330000000-E	607	INCIDENTAL MILLING	400	SY	
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	220	TON	
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	7,925	TON	
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,775	TON	
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	810	TON	
0027	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	220	TON	
0028	1869000000-E	710	***** PORT CEM CONC PAVEMENT, MISCELLANEOUS (WITHOUT DOWELS) (10")	135	SY	
0029	2000000000-N	806	RIGHT OF WAY MARKERS	51	EA	
0030	2209000000-E	838	ENDWALLS	2.196	CY	
0031	2253000000-E	840	PIPE COLLARS	1.691	CY	
0032	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	53	EA	
0033	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	5.18	LF	
0034	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	11	EA	
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	9	EA	
0036	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	10	EA	

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	23 EA		
0038	2440000000-N	852	CONCRETE TRANSITIONAL SECTION FOR CATCH BASIN	3 EA		
0039	2535000000-E	846	***X *** CONCRETE CURB (9" X 16")	132 LF		
0040	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	190 LF		
0041	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	14,100 LF		
0042	2591000000-E	848	4" CONCRETE SIDEWALK	2,900 SY		
0043	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	63 EA		
0044	2612000000-E	848	6" CONCRETE DRIVEWAY	245 SY		
0045	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	765 SY		
0046	2830000000-N	858	ADJUSTMENT OF MANHOLES	6 EA		
0047	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	6 EA		
0048	3642000000-E	876	RIP RAP, CLASS A	5 TON		
0049	3649000000-E	876	RIP RAP, CLASS B	25 TON		
0050	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	145 SY		
0051	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	418 SF		
0052	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0053	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	106 SF		
0054	4430000000-N	1130	DRUMS	340 EA		
0055	4445000000-E	1145	BARRICADES (TYPE III)	238 LF		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4455000000-N	1150	FLAGGER	180	MD	
0057	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4	EA	
0058	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2	EA	
0059	4485000000-E	1170	PORTABLE CONCRETE BARRIER	698	LF	
0060	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	351	LF	
0061	4507000000-E	SP	WATER FILLED BARRIER	120	LF	
0062	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	388	LF	
0063	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	15,279	LF	
0064	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	161	LF	
0065	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	674	LF	
0066	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	382	LF	
0067	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	40	EA	
0068	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	53,831	LF	
0069	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	24	LF	
0070	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	395	LF	
0071	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	2	EA	
0072	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	29,524	LF	
0073	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	50	LF	

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	127 LF		
0075	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	329 EA		
0076	5325600000-E	1510	6" WATER LINE	100 LF		
0077	6000000000-E	1605	TEMPORARY SILT FENCE	6,600 LF		
0078	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	215 TON		
0079	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0080	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0081	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.03 TON		
0082	6029000000-E	SP	SAFETY FENCE	460 LF		
0083	6042000000-E	1632	1/4" HARDWARE CLOTH	1,800 LF		
0084	6070000000-N	SP	SPECIAL STILLING BASINS	1 EA		
0085	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
0086	6087000000-E	1660	MOWING	6.1 ACR		
0087	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0088	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	245 LB		
0089	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0090	6111000000-E	SP	IMPERVIOUS DIKE	230 LF		
0091	7060000000-E	1705	SIGNAL CABLE	50 LF		
0092	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	95 LF		
0093	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	1 EA		

County : Scotland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,460 LF		
0095	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	865 LF		
0096	7636000000-N	1745	SIGN FOR SIGNALS	6 EA		
0097	8126000000-N	414	CULVERT EXCAVATION, STA ***** (57+99.41 -L-)	Lump Sum	L.S.	
0098	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	186 TON		
0099	8196000000-E	420	CLASS A CONCRETE (CULVERT)	226 CY		
0100	8245000000-E	425	REINFORCING STEEL (CULVERT)	52,876 LB		

1007/Feb05/Q230462.947/D360690700000/E100

Total Amount Of Bid For Entire Project :

**Contract No**     **C202074**

**County (ies):**   **Scotland**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General