

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	14,300 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+96.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	950 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,500 TON		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	2,000 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	1,550 SF		
0011	0220000000-E	SP	ROCK EMBANKMENTS	4,350 TON		
0012	0241000000-E	SP	GENERIC GRADING ITEM FILTER FABRIC FOR ROCK EMBANKMENTS	2,600 SY		
0013	0255000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS IV (ABC)	1,150 TON		
0014	0255000000-E	SP	GENERIC GRADING ITEM SELECT MATERIAL, CLASS VI	250 TON		
0015	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	64.5 TON		
0016	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	116 LF		
0017	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	204 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	20 LF		
0019	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0020	0995000000-E	340	PIPE REMOVAL	143 LF		
0021	1121000000-E	520	AGGREGATE BASE COURSE	2,000 TON		
0022	1220000000-E	545	INCIDENTAL STONE BASE	150 TON		
0023	1275000000-E	600	PRIME COAT	1,250 GAL		
0024	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	900 SY		
0025	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,250 TON		
0026	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	960 TON		
0027	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,380 TON		
0028	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	185 TON		
0029	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	9.25 TON		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0031	2354000000-N	840	FRAME WITH GRATE, STD 840.22	1 EA		
0032	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	2 EA		
0033	2556000000-E	846	SHOULDER BERM GUTTER	310 LF		
0034	3030000000-E	862	STEEL BM GUARDRAIL	750 LF		
0035	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	100 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0037	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
0038	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0039	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4 EA		
0040	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	1,137.5 LF		
0041	3382000000-E	862	TEMPORARY STEEL BM GUARDRAIL (SHOP CURVED)	37.5 LF		
0042	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (AT-1)	1 EA		
0043	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77)	3 EA		
0044	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	6 EA		
0045	3649000000-E	876	RIP RAP, CLASS B	165 TON		
0046	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,275 SY		
0047	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	244 LF		
0048	4096000000-N	904	SIGN ERECTION, TYPE D	2 EA		
0049	4102000000-N	904	SIGN ERECTION, TYPE E	10 EA		
0050	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	15 EA		
0051	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	1 EA		
0052	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	428 SF		
0053	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	103	SF	
0055	4430000000-N	1130	DRUMS	70	EA	
0056	4435000000-N	1135	CONES	30	EA	
0057	4445000000-E	1145	BARRICADES (TYPE III)	84	LF	
0058	4455000000-N	1150	FLAGGER	450	MD	
0059	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1	EA	
0060	4480000000-N	1165	TMIA	1	EA	
0061	4485000000-E	1170	PORTABLE CONCRETE BARRIER	424	LF	
0062	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	80	EA	
0063	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	996	LF	
0064	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	23,162	LF	
0065	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	186	LF	
0066	4847000000-E	1205	POLYUREA PAVEMENT MARKING LINES (4", *****) (STANDARD GLASS BEADS)	6,424	LF	
0067	4847140000-E	1205	POLYUREA PAVEMENT MARKING LINES (24", *****) (STANDARD GLASS BEADS)	59	LF	
0068	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	2,300	LF	
0069	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	16	EA	
0070	5326000000-E	1510	10" WATER LINE	23	LF	
0071	5326200000-E	1510	12" WATER LINE	439	LF	

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	5552000000-E	1515	10" VALVE	1 EA		
0073	5558000000-E	1515	12" VALVE	1 EA		
0074	5648000000-N	1515	RELOCATE WATER METER	1 EA		
0075	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0076	5802000000-E	1530	ABANDON 10" UTILITY PIPE	75 LF		
0077	5804000000-E	1530	ABANDON 12" UTILITY PIPE	682 LF		
0078	6000000000-E	1605	TEMPORARY SILT FENCE	2,500 LF		
0079	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	180 TON		
0080	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	255 TON		
0081	6012000000-E	1610	SEDIMENT CONTROL STONE	500 TON		
0082	6015000000-E	1615	TEMPORARY MULCHING	3 ACR		
0083	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0084	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	1.5 TON		
0085	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0086	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7 EA		
0087	6029000000-E	SP	SAFETY FENCE	400 LF		
0088	6030000000-E	1630	SILT EXCAVATION	600 CY		
0089	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,600 SY		
0090	6037000000-E	SP	COIR FIBER MAT	15 SY		
0091	6042000000-E	1632	1/4" HARDWARE CLOTH	500 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	607000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0093	6071030000-E	SP	COIR FIBER BAFFLES	130 LF		
0094	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
0095	6084000000-E	1660	SEEDING & MULCHING	5.8 ACR		
0096	6087000000-E	1660	MOWING	2 ACR		
0097	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0098	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0099	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0100	6108000000-E	1665	FERTILIZER TOPDRESSING	2 TON		
0101	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0102	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0103	6123000000-E	1670	REFORESTATION	1 ACR		
STRUCTURE ITEMS						
0104	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (19+96.00 -L-)	Lump Sum	L.S.	
0105	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (19+96.00 -L-)	Lump Sum	L.S.	
0106	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+96.00 -L-)	Lump Sum	L.S.	
0107	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	85 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0108	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	54 LF		
0109	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	90.9 LF		
0110	8113000000-N	SP	SID INSPECTION	1 EA		
0111	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0112	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	930 CY		
0113	8156000000-E	SP	CONCRETE WEARING SURFACE	8,365 SF		
0114	8161000000-E	420	GROOVING BRIDGE FLOORS	9,601 SF		
0115	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	99.2 CY		
0116	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+96.00 -L-)	Lump Sum	L.S.	
0117	8217000000-E	425	REINFORCING STEEL (BRIDGE)	22,977 LB		
0118	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,148 LB		
0119	8364000000-E	450	HP12X53 STEEL PILES	385 LF		
0120	8503000000-E	460	CONCRETE BARRIER RAIL	401.75 LF		
0121	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	270 TON		
0122	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	300 SY		
0123	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0124	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0125	8753000000-E	430	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	3,009.39 LF		

Contract No **C201831**

County (ies): **Stanly**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General