

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	2 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	7,000 CY		
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	1,890 TON		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	220 CY		
0007	0192000000-N	260	PROOF ROLLING	10 HR		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	1,250 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	4,250 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	415 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	272 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	68 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	448 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	420 LF		
0015	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	232 LF		
0016	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	96 LF		
0017	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	1,072 LF		
0018	0995000000-E	340	PIPE REMOVAL	632 LF		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1044000000-E	501	LIME TREATED SOIL (SLURRY METHOD)	15,750	SY	
002C	1066000000-E	501	LIME FOR LIME TREATED SOIL	160	TON	
0021	1110000000-E	510	STABILIZER AGGREGATE	500	TON	
0022	1121000000-E	520	AGGREGATE BASE COURSE	14,500	TON	
0023	1176000000-E	542	SOIL CEMENT BASE	15,750	SY	
0024	1187000000-E	542	PORTLAND CEMENT FOR SOIL CEMENT BASE	434	TON	
002E	1220000000-E	545	INCIDENTAL STONE BASE	1,500	TON	
002E	1330000000-E	607	INCIDENTAL MILLING	1,200	SY	
0027	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	3,640	TON	
002E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	5,610	TON	
002E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	7,760	TON	
003C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	890	TON	
0031	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100	TON	
0032	2143000000-E	818	BLOTTING SAND	15	TON	
0033	2220000000-E	838	REINFORCED ENDWALLS	16	CY	
0034	2253000000-E	840	PIPE COLLARS	1	CY	
003E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1	EA	
003E	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	1	EA	

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3030000000-E	862	STEEL BM GUARDRAIL	1,518	LF	
003E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	128	LF	
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
004C	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (TES)	4	EA	
0041	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6	EA	
0042	3628000000-E	876	RIP RAP, CLASS I	230	TON	
0043	3649000000-E	876	RIP RAP, CLASS B	125	TON	
0044	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	3,530	SY	
004E	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
004E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	613	LF	
0047	4102000000-N	904	SIGN ERECTION, TYPE E	57	EA	
004E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	22	EA	
004E	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	1,534	SF	
005C	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	384	SF	
0051	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	194	SF	
0052	4435000000-N	1135	CONES	300	EA	
0053	4445000000-E	1145	BARRICADES (TYPE III)	400	LF	
0054	4455000000-N	1150	FLAGGER	120	MD	

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	24,000	LF	
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	29,850	LF	
0057	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	300	LF	
005E	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	240	LF	
005E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	310	LF	
006C	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	4	EA	
0061	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	31	EA	
0062	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	107,691	LF	
0063	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	600	LF	
0064	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	620	LF	
006E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	62	EA	
006E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	238	EA	
0067	4915000000-E	1264	7' U-CHANNEL POSTS	6	EA	
006E	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	6	EA	
006E	5326200000-E	1510	12" WATER LINE	1,530	LF	
007C	5672000000-N	1515	RELOCATE FIRE HYDRANT	1	EA	
0071	5691000000-E	1520	*** SANITARY GRAVITY SEWER (15")	238	LF	

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	5691600000-E	1520	16" SANITARY GRAVITY SEWER	131		LF
0073	5709200000-E	1520	4" FORCE MAIN SEWER	330		LF
0074	5775000000-E	1525	4' DIA UTILITY MANHOLE	3		EA
007E	5781000000-E	1525	UTILITY MANHOLE WALL, 4' DIA	17		LF
007E	5798000000-E	1530	ABANDON *** UTILITY PIPE (15")	350		LF
0077	5804000000-E	1530	ABANDON 12" UTILITY PIPE	1,470		LF
007E	5816000000-N	1530	ABANDON UTILITY MANHOLE	2		EA
007E	6000000000-E	1605	TEMPORARY SILT FENCE	8,100		LF
008C	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	1,400		TON
0081	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,950		TON
0082	6012000000-E	1610	SEDIMENT CONTROL STONE	570		TON
008E	6015000000-E	1615	TEMPORARY MULCHING	73		ACR
0084	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,400		LB
008E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	7.25		TON
008E	6024000000-E	1622	TEMPORARY SLOPE DRAINS	850		LF
0087	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	7		EA
008E	6029000000-E	SP	SAFETY FENCE	100		LF
008E	6030000000-E	1630	SILT EXCAVATION	6,725		CY
009C	6036000000-E	1631	MATTING FOR EROSION CONTROL	21,420		SY

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	6037000000-E	SP	COIR FIBER MAT	120 SY		
0092	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	3,945 SY		
0093	6042000000-E	1632	1/4" HARDWARE CLOTH	175 LF		
0094	6045000000-E	SP	*** TEMPORARY PIPE (24")	20 LF		
0095	6069000000-E	1638	STILLING BASINS	460 CY		
0096	6071030000-E	SP	COIR FIBER BAFFLES	1,175 LF		
0097	6071050000-E	SP	*** SKIMMER (1-1/2")	18 EA		
0098	6084000000-E	1660	SEEDING & MULCHING	76.5 ACR		
0099	6087000000-E	1660	MOWING	45 ACR		
0100	6090000000-E	1661	SEED FOR REPAIR SEEDING	650 LB		
0101	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.5 TON		
0102	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	900 LB		
0103	6108000000-E	1665	FERTILIZER TOPDRESSING	27 TON		
0104	6111000000-E	SP	IMPERVIOUS DIKE	110 LF		
0105	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0106	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	36 EA		
0107	6120000000-E	SP	CULVERT DIVERSION CHANNEL	50 CY		
0108	6126000000-E	SP	STREAMBANK REFORESTATION	0.12 ACR		

County : Stanly

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0109 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	144		LF
*** OR ***						
0110 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	144		LF
*** OR ***						
0111 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	144		LF
***** END SCHEDULE AA *****						
CULVERT ITEMS						

0112	8126000000-N	414	CULVERT EXCAVATION, STA ***** (13+58.50-Y2-)	Lump Sum		L.S.
0113	8126000000-N	414	CULVERT EXCAVATION, STA ***** (43+98.00-L-)	Lump Sum		L.S.
0114	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	145		TON
0115	8196000000-E	420	CLASS A CONCRETE (CULVERT)	188		CY
0116	8245000000-E	425	REINFORCING STEEL (CULVERT)	26,635		LB

1517/Feb05/Q341126.37/D450390180000/E116

Total Amount Of Bid For Entire Project :

Contract No **C202065**

County (ies): **Stanly**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General