

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0003	0057000000-E	226	UNDERCUT EXCAVATION	50 CY		
0004	0063000000-N	SP	GRADING	Lump Sum	L.S.	
000E	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	50 TON		
000E	0106000000-E	230	BORROW EXCAVATION	2,150 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	100 CY		
000E	0195000000-E	265	SELECT GRANULAR MATERIAL	50 CY		
000E	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	50 SY		
001C	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	60 TON		
0011	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	92 LF		
0012	0706000000-E	310	12" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	112 LF		
0013	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	28 LF		
0014	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	120 LF		
001E	0805000000-E	310	12" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
001E	0995000000-E	340	PIPE REMOVAL	417 LF		
0017	1121000000-E	520	AGGREGATE BASE COURSE	85 TON		
001E	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	490 TON		
0020	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	290 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	15 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	21 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	44.8 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	33.6 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	200 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	2 EA		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	12 EA		
0032	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	5 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	6 EA		
0034	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0035	2556000000-E	846	SHOULDER BERM GUTTER	210 LF		
0036	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	365 LF		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3030000000-E	862	STEEL BM GUARDRAIL	287.5 LF		
003E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
004C	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0041	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0042	3649000000-E	876	RIP RAP, CLASS B	30 TON		
004E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	470 SY		
0044	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	443 SF		
004E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	132 SF		
004E	4430000000-N	1130	DRUMS	18 EA		
0047	4445000000-E	1145	BARRICADES (TYPE III)	96 LF		
004E	4516000000-N	1180	SKINNY DRUM	18 EA		
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,280 LF		
005C	6000000000-E	1605	TEMPORARY SILT FENCE	1,050 LF		
0051	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	180 TON		
0052	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	85 TON		
005E	6012000000-E	1610	SEDIMENT CONTROL STONE	160 TON		
0054	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
005E	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25 TON		
0057	6024000000-E	1622	TEMPORARY SLOPE DRAINS	55 LF		
005E	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
005E	6029000000-E	SP	SAFETY FENCE	410 LF		
006C	6030000000-E	1630	SILT EXCAVATION	250 CY		
0061	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,900 SY		
0062	6037000000-E	SP	COIR FIBER MAT	20 SY		
0063	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	55 SY		
0064	6042000000-E	1632	1/4" HARDWARE CLOTH	255 LF		
006E	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
006E	6071030000-E	SP	COIR FIBER BAFFLES	75 LF		
0067	6071050000-E	SP	*** SKIMMER (1-1/2")	3 EA		
006E	6084000000-E	1660	SEEDING & MULCHING	8 ACR		
006E	6087000000-E	1660	MOWING	1 ACR		
007C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0072	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0073	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	6111000000-E	SP	IMPERVIOUS DIKE	260 LF		
0075	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0076	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0077 AA1	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	64 LF		
0078 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	148 LF		
*** OR ***						
0079 AA2	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	56 LF		
0080 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (12", 0.064")	8 LF		
0081 AA2	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	148 LF		
*** OR ***						
0082 AA3	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	56 LF		
0083 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (12")	8 LF		
0084 AA3	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	148 LF		
***** END SCHEDULE AA *****						
CULVERT ITEMS						
008E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+51.00-L-)	Lump Sum	L.S.	

County : Watauga

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	8196000000-E	420	CLASS A CONCRETE (CULVERT)	94 CY		
0087	8590000000-E	876	RIP RAP, CLASS ** (I)	41.6 TON		
008E	8804000000-N	SP	GENERIC CULVERT ITEM PRECAST REINF CONC THREE SIDED CULVERT AT STA 18+51.00 -L-	Lump Sum	L.S.	
0855/Feb02/Q17717.25/D295827180000/E88			Total Amount Of Bid For Entire Project :			

Contract No **C202023**

County (ies): **Watauga**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General