



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES. PERDUE  
GOVERNOR

EUGENE A. CONTI, JR.  
SECRETARY

April 15, 2009

**Addendum No. 2**

RE: Contract ID: C202223  
WBS# 45045.3.ST1  
F.A. # STM-0074(105)  
**Swain County (R-5145)**  
US-74 West In Swain County From SR-1159 To  
Jackson County Line

**April 21, 2009 Letting**

To Whom It May Concern:

Reference is made to the proposal recently furnished to you on this project.

The following revision has been made to the Proposal:

On Page No. 36, the Project Special Provision entitled "Material Transfer Vehicle (MTV)" has been added. Please void Page No. 36 in your proposal and staple the revised Page 36 thereto.

Sincerely,

A handwritten signature in black ink, appearing to read "R. A. Garris".

R. A. Garris, PE  
Contract Officer

RAG/jr  
Attachments

cc: Mr. J.G Nance, PE  
Mr. Ron Hancock, PE  
Mr. J. B. Setzer, PE  
Ms. D. M. Barbour, PE  
Mr. Art McMillan, PE  
Mr. J.V. Barbour, PE  
Mr. Mark Staley (2)  
Project File (2)

Mr. Robert Memory  
Mr. R. E. Davenport, Jr., PE  
Mr. Ronnie Higgins  
Mr. Larry Strickland  
Ms. Marsha Sample  
Ms. Norma Smith  
Ms. Lori Strickland

**PAVEMENT MARKING LINES:**

(11-21-06) (Rev. 9-18-07)

R12 R01

Revise the 2006 *Standard Specifications* as follows:

**Page 12-2, 1205-3(D) Time Limitations for Replacement**, add the following at the beginning of the chart:

Facility Type	Marking Type	Replacement Deadline
Full-control-of-access multi-lane roadway (4 or more total lanes) and ramps, including Interstates	All markings including symbols	By the end of each workday's operation if the lane is opened to traffic

**Page 12-14, Subarticle 1205-10, Measurement and Payment**, delete the first sentence of the first paragraph and replace with the following:

*Pavement Marking Lines* will be measured and paid for as the actual number of linear feet of pavement marking lines per application that has been satisfactorily placed and accepted by the Engineer.

**MATERIAL TRANSFER VEHICLE (MTV):**

The Contractor shall use a Material Transfer Vehicle (MTV) for the placement of all S9.5C mix. The Material Transfer Vehicle (MTV) shall be in accordance with the requirements of Article 610-8 of the *Standard Specifications*.