

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0057000000-E	226	UNDERCUT EXCAVATION	650 CY		
0004	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	1,150 TON		
0005	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,850 SY		
0006	1245000000-E	SP	SHOULDER RECONSTRUCTION	5.47 SMI		
0007	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	1,640 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	13,310 SY		
0009	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	1,231 TON		
0010	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	274 TON		
0011	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	10,964 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	66 TON		
0013	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	658 TON		
0014	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	37,000 LF		
0015	2752000000-E	SP	GENERIC PAVING ITEM REMOVE CONCRETE MEDIAN BARRIER	50 LF		
0016	2815000000-N	858	ADJUSTMENT OF DROP INLETS	3 EA		
0017	3030000000-E	862	STEEL BM GUARDRAIL	2,600 LF		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	3345000000-E	864	REMOVE & RESET EXISTING GUARD-RAIL	6,300 LF		
001E	3389200000-E	865	CABLE GUIDERAIL	100 LF		
002C	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	748 SF		
0021	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	965 SF		
0022	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4 EA		
0023	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	6 EA		
0024	4430000000-N	1130	DRUMS	370 EA		
002E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
002E	4480000000-N	1165	TMIA	2 EA		
0027	4485000000-E	1170	PORTABLE CONCRETE BARRIER	387 LF		
002E	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	387 LF		
002E	4510000000-N	SP	POLICE	1,000 HR		
003C	4516000000-N	1180	SKINNY DRUM	74 EA		
0031	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	38 EA		
0032	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	36,000 LF		
0033	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	32,600 LF		
0034	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	2,100 LF		
003E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	24 LF		

County : Forsyth

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	8	EA	
0037	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	169,163	LF	
003E	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	5,821	LF	
003E	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	6	EA	
004C	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	500	EA	
0041	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0042	6000000000-E	1605	TEMPORARY SILT FENCE	100	LF	
004C	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50	TON	
0044	6012000000-E	1610	SEDIMENT CONTROL STONE	50	TON	
004E	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
004E	6036000000-E	1631	MATTING FOR EROSION CONTROL	500	SY	
0047	6042000000-E	1632	1/4" HARDWARE CLOTH	100	LF	
004E	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
004E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
005C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	

1410/Mar02/Q328914.72/D185309300000/E50

Total Amount Of Bid For Entire Project :

Contract No **C202045**

County (ies): **Forsyth**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General