



PROJECT SPECIAL PROVISIONS  
Utility Construction

All proposed utility construction shall meet the applicable requirements of the NC Department of Transportation's "*Standard Specifications for Roads and Structures*" dated July 2006. Division 15 of the Standard Specifications is revised as follows:

Page 15-1, Paragraph 4 Add:

*The water and sewer lines on this project belong to the Town of Smithfield. The contact person for the Town of Smithfield is Mr. Earl Botkin, and he can be reached by phone at 919.934.2798. Any work on these lines must be coordinated through the Engineer and the utility owner before beginning.*

PROVIDED BY THE OWNER:

The Town of Smithfield will provide the Contractor with new fire hydrants for installation where utility construction plans call for "fire hydrant" or "relocate fire hydrant". The Contractor shall notify the owner's representative prior to removal or relocation of existing fire hydrants and arrange for the owner to take possession of the existing hydrant and remove it from the project site.

COMPENSATION:

No direct payment will be made for utility construction work required by the preceding provisions, which are general requirements applying to utility construction, and all of the requirements stated will be considered incidental work, paid for at the contract unit prices of the various utility items included in the contract.

ANTI-SEEPAGE COLLARS:

Anti-seepage collars for utility lines shall be installed in accordance with the applicable utility provisions herein and as shown on the utility construction plans, and/or as directed by the Engineer.

Anti-seepage collars installed in accordance with the plans and provisions herein and accepted, will be measured and paid for at the contract unit price per each for "Anti Seepage Collars". Such prices and payments shall be full compensation for all materials, labor, equipment, formwork, construction, and incidentals necessary to complete the work as required

PROJECT SPECIAL PROVISIONS  
Utility

UTILITIES BY OTHERS

General:

The following utility companies have facilities that will be in conflict with the construction of this project.

- A) Progress Energy (Distribution)
- B) Progress Energy (Transmission)
- C) Town of Smithfield Power (Distribution)
- D) Embarq – Telephone
- E) Time Warner Cable – CATV
- F) Piedmont Natural Gas

The conflicting facilities of these concerns will be adjusted prior to the date of availability, unless otherwise noted and are therefore listed in these special provisions for the benefit of the Contractor. All utility work listed herein will be done by the utility owner. All utilities are shown on the plans from the best available information.

The Contractor’s attention is directed to Article 105-8 of the Standard Specifications.

Utilities Requiring Adjustment:

- A) Progress Energy (Distribution)
  - 1) See Utilities by Others Plans.
- B) Progress Energy (Transmission)
  - 1) See Utilities by Others Plans.

Note: Progress Energy will complete the relocation of their power transmission facilities by April 15, 2009.

- C) Town of Smithfield Power (Distribution)
  - 1) See Utilities by Others Plans.
- D) Embarq – Telephone
  - 1) See Utilities by Others Plans.

Note: The contractor shall give Embarq 2 weeks notice prior to completion of clearing and grubbing at the intersection of -Y1- and -L-, and at the intersection of -Y2- and -L-, and then shall allow Embarq 8 weeks to complete the installation of their buried fiber optic facilities in those areas.

E) Time Warner Cable – CATV

1) See Utilities by Others Plans.

F) Piedmont Natural Gas

1) See Utilities by Others Plans.

NOTE: All other utilities will remain in place and will be adjusted as necessary.