

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+10.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	1,500 CY		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	22 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	400 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	1,300 SY		
0010	0199000000-E	SP	TEMPORARY SHORING	144 SF		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	51 TON		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	44 LF		
0013	0345000000-E	310	24" SIDE DRAIN PIPE	76 LF		
0014	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	72 LF		
0015	0995000000-E	340	PIPE REMOVAL	64 LF		
0016	1220000000-E	545	INCIDENTAL STONE BASE	300 TON		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,530 TON		
0018	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	820 TON		
0019	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	980 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	165 TON		
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	18 TON		
0022	2000000000-N	806	RIGHT OF WAY MARKERS	13 EA		
0023	2209000000-E	838	ENDWALLS	3 CY		
0024	2253000000-E	840	PIPE COLLARS	1 CY		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0026	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	1.3 LF		
0027	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0028	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		
0029	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	125 LF		
0030	2619000000-E	850	4" CONCRETE PAVED DITCH	20 SY		
0031	3030000000-E	862	STEEL BM GUARDRAIL	337.5 LF		
0032	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	50 LF		
0033	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0035	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0036	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	100 LF		
0037	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	1 EA		
0038	3572000000-E	867	CHAIN LINK FENCE RESET	330 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	3628000000-E	876	RIP RAP, CLASS I	265	TON	
0040	3649000000-E	876	RIP RAP, CLASS B	200	TON	
0041	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,545	SY	
0042	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	137	LF	
0043	4102000000-N	904	SIGN ERECTION, TYPE E	10	EA	
0044	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2	EA	
0045	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	21	EA	
0046	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1	EA	
0047	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	448	SF	
0048	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	220	SF	
0049	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	175	SF	
0050	4422000000-N	1120	CHANGEABLE MESSAGE SIGN (SHORT TERM)	42	DAY	
0051	4430000000-N	1130	DRUMS	48	EA	
0052	4435000000-N	1135	CONES	28	EA	
0053	4445000000-E	1145	BARRICADES (TYPE III)	192	LF	
0054	4450000000-N	1150	FLAGGER	2,880	HR	
0055	4516000000-N	1180	SKINNY DRUM	28	EA	
0056	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	45	EA	
0057	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,536	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,536 LF		
0059	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	12 LF		
0060	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (I)	628 LF		
0061	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	628 LF		
0062	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,144 LF		
0063	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	24 LF		
0064	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	23 EA		
0065	5326200000-E	1510	12" WATER LINE	113 LF		
0066	5804000000-E	1530	ABANDON 12" UTILITY PIPE	102 LF		
0067	6000000000-E	1605	TEMPORARY SILT FENCE	2,350 LF		
0068	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	350 TON		
0069	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	325 TON		
0070	6012000000-E	1610	SEDIMENT CONTROL STONE	115 TON		
0071	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0072	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	150 LB		
0073	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.5 TON		
0074	6029000000-E	SP	SAFETY FENCE	1,750 LF		
0075	6030000000-E	1630	SILT EXCAVATION	660 CY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0076	6036000000-E	1631	MATTING FOR EROSION CONTROL	3,700 SY		
0077	6037000000-E	SP	COIR FIBER MAT	15 SY		
0078	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,642 SY		
0079	6042000000-E	1632	1/4" HARDWARE CLOTH	175 LF		
0080	6071010000-E	SP	WATTLE	125 LF		
0081	6071020000-E	SP	POLYACRYLAMIDE (PAM)	50 LB		
0082	6071030000-E	SP	COIR FIBER BAFFLES	130 LF		
0083	6071050000-E	SP	*** SKIMMER (1-1/2")	2 EA		
0084	6084000000-E	1660	SEEDING & MULCHING	5.5 ACR		
0085	6087000000-E	1660	MOWING	2 ACR		
0086	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0087	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0088	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0089	6108000000-E	1665	FERTILIZER TOPDRESSING	2.25 TON		
0090	6111000000-E	SP	IMPERVIOUS DIKE	125 LF		
0091	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0092	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		
0093	6123000000-E	1670	REFORESTATION	0.5 ACR		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0094 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	188	LF	
*** OR ***						
0095 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	160	LF	
0096 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	28	LF	
*** OR ***						
0097 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	160	LF	
0098 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	28	LF	
***** END SCHEDULE AA *****						

STRUCTURE ITEMS

0099	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+12.00-L)	Lump Sum	L.S.	
0100	8156000000-E	SP	CONCRETE WEARING SURFACE	5,749	SF	
0101	8161000000-E	420	GROOVING BRIDGE FLOORS	6,518	SF	
0102	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	79.7	CY	
0103	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+12.00-L)	Lump Sum	L.S.	
0104	8217000000-E	425	REINFORCING STEEL (BRIDGE)	13,678	LB	
0105	8364000000-E	450	HP12X53 STEEL PILES	640	LF	
0106	8365000000-E	450	HP12X53 GALVANIZED STEEL PILES	685	LF	
0107	8475000000-E	460	TWO BAR METAL RAIL	237.86	LF	
0108	8517000000-E	460	1'***X ***** CONCRETE PARA-PET (1'-2" X 2'-10 3/4")	254.8	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	685 TON		
0110	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	760 SY		
0111	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0112	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0113	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	2,033.83 LF		
1008/Mar04/Q81336.99/D476726010000/E113			Total Amount Of Bid For Entire Project :			

Contract No **C202069**

County (ies): **Wake**

**ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION**

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General

Signature Sheet (Bid - Acceptance by Department)