

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0036000000-E	225	UNDERCUT EXCAVATION	2,000 CY		
0003	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	1,000 TON		
0004	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	5,000 SY		
0005	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	30 LF		
0006	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, T YPE B 0.064" THICK	2 EA		
0007	1245000000-E	SP	SHOULDER RECONSTRUCTION	15.55 SMI		
0008	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	236,897 SY		
0009	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	3,146 SY		
0010	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 5")	4,620 SY		
0011	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	34,620 TON		
0012	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	24,232 TON		
0013	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,635 TON		
0014	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	1,352 TON		
0015	1704000000-E	SP	PATCHING EXISTING PAVEMENT	250 TON		
0016	1737000000-E	SP	PATCHING CONCRETE PAVEMENT SPALLS	3,500 SF		
0017	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	107,712 LF		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1891000000-E	SP	GENERIC PAVING ITEM REPAIR OF JOINTED CONCRETE PAVEMENT SLABS	11,324 SY		
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0020	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		
0021	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	192 SF		
0022	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0023	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0024	4430000000-N	1130	DRUMS	200 EA		
0025	4480000000-N	1165	TMIA	2 EA		
0026	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	86 LF		
0027	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	31 EA		
0028	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	134,460 LF		
0029	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	1,862 LF		
0030	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	134,460 LF		
0031	4847120000-E	1205	POLYUREA PAVEMENT MARKING LINES (12", *****) (HIGHLY REFLECTIVE ELEMENTS)	1,862 LF		
0032	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	770 EA		
0033	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0034	6084000000-E	1660	SEEDING & MULCHING	9.41 ACR		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	8867000000-E	SP	GENERIC STRUCTURE ITEM EVAZOTE EXPANSION JOINT REPLACEMENT	864	LF	
0036	8893000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE DECK REPAIR (CLASS II) USING ELASTOMERIC CONCRETE	45	SY	
0037	8893000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE DECK REPAIR (CLASS III) USING ELASTOMERIC CONC- RETE	10	SY	
0038	8893000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE DECK REPAIR (CLASS I) USING ELASTOMERIC CONCRETE	100	SY	

1506/Apr20/Q712298.96/D127699520000/E38

Total Amount Of Bid For Entire Project :

Contract No **C202310**

County (ies): **Buncombe County**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General