

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1022000000-E	SP	SEALING EXISTING PAVEMENT CRACKS	109,800 LB		
0003	1220000000-E	545	INCIDENTAL STONE BASE	214 TON		
0004	1245000000-E	SP	SHOULDER RECONSTRUCTION	5.4 SMI		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (0-5/8")	1,101 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1")	363,488 SY		
0007	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	30,826 TON		
0008	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,850 TON		
0009	1567000000-E	SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-28	1,825 TON		
0010	1704000000-E	SP	PATCHING EXISTING PAVEMENT	7,100 TON		
0011	1839110000-E	661	ULTRATHIN HOT MIX ASPHALT, TYPE B	31,466 TON		
0012	1839200000-E	661	APPLICATION OF ULTRATHIN HOT MIX ASPHALT	899,104 SY		
0013	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	506,040 LF		
0014	2619000000-E	850	4" CONCRETE PAVED DITCH	950 SY		
0015	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	21,856 SF		
0016	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	4 EA		
0017	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
0018	4430000000-N	1130	DRUMS	500 EA		

County : Burke

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4480000000-N	1165	TMIA	2 EA		
0020	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	610 LF		
0021	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	136 EA		
0022	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	715,364 LF		
0023	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	23,902 LF		
0024	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	610 LF		
0025	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	136 EA		
0026	4847100000-E	1205	POLYUREA PAVEMENT MARKING LINES (6", *****) (HIGHLY REFLECTIVE ELEMENTS)	715,364 LF		
0027	4847120000-E	1205	POLYUREA PAVEMENT MARKING LINES (12", *****) (HIGHLY REFLECTIVE ELEMENTS)	23,902 LF		
0028	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0029	6084000000-E	1660	SEEDING & MULCHING	3.26 ACR		
0030	8893000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE DECK REPAIR (CLASS I) USING ELASTOMERIC CONCRETE	200 SY		
0031	8893000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE DECK REPAIR (CLASS II) USING ELASTOMERIC CONCRETE	115 SY		
0032	8893000000-E	SP	GENERIC STRUCTURE ITEM CONCRETE DECK REPAIR (CLASS III) USING ELASTOMERIC CONCRETE	15 SY		

Contract No **C202289**

County (ies): **Burke**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

**Execution of Contract and Bonds
Approved as to Form:**

Attorney General