

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1245000000-E	SP	SHOULDER RECONSTRUCTION	15 SMI		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2-1/2")	71,575 SY		
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1" TO 2-1/2")	3,000 SY		
0005	1330000000-E	607	INCIDENTAL MILLING	1,850 SY		
0006	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	11,266 TON		
0007	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	29,607 TON		
0008	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	530 TON		
0009	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	1,628 TON		
0010	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	70,550 LF		
0011	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT PLANT MIX, PAVEMENT REPAIR (B25.0C)	250 TON		
0012	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (I19.0D)	2,000 TON		
0013	1891000000-E	SP	GENERIC PAVING ITEM CONTINUOUSLY REINFORCED CON- CRETE REPAIR	525 SY		
0014	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	288 SF		
0015	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0016	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0017	4430000000-N	1130	DRUMS	275 EA		

County : Cabarrus

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0019	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	7 EA		
0020	4480000000-N	1165	TMIA	2 EA		
0021	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,000 LF		
0022	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	7,000 LF		
0023	4605000000-N	SP	GENERIC TRAFFIC CONTROL ITEM POLICE	120 HR		
0024	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	101,550 LF		
0025	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	11,000 LF		
0026	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	6,775 LF		
0027	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	6 EA		
0028	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	44,000 LF		
0029	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,025 EA		
0030	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	

0652/Apr03/Q365852.0/D9728130000/E30

Total Amount Of Bid For Entire Project :

Contract No **C202288**

County (ies): **Cabarrus**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General