



FINAL PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM	QUANTITY BREAKDOWN	TOTAL QUANTITY
PAVEMENT MARKINGS LINES				
P3	WHITE LINE, RR CROSSBAR (2X)	PAINT (16")	200 LF	TOTAL 200 LF
P4	WHITE STOPBAR (2X)	PAINT (24")	148 LF	TOTAL 148 LF
PD	2 FT. WHITE MINISKIP (2X)	PAINT (4")	39 LF	TOTAL 5,519 LF
PI	YELLOW DOUBLE CENTER (2X)		5,240 LF	
PA	WHITE EDGELINE (2X)		240 LF	
PV	YELLOW DIAGONAL (2X)	PAINT (8")	232 LF	TOTAL 232 LF
PAINTMARKING CHARACTERS				
QI	ALPHANUMERIC CHAR. (2X)		4 EA	TOTAL 4 EA
PAINTMARKING SYMBOLS				
QA	LEFT TURN ARROW (2X)		4 EA	TOTAL 10 EA
QB	RIGHT TURN ARROW (2X)		2 EA	
QC	STRAIGHT ARROW (2X)		2 EA	
QE	COMBO STRAIGHT/RIGHT. (2X)		2 EA	
SNOWPLOWABLE RAISED PAVEMENT MARKERS				
ME	YELLOW & YELLOW		48 EA	TOTAL 48 EA

PLANS PREPARED BY:
TGS ENGINEERS
 TGS ENGINEERS
 SUITE 141
 975 WALNUT STREET
 CARY, NC 27511
 PH (919) 319-8850

APPROVED: *[Signature]* DATE: 11-7-08
 SEAL
 NORTH CAROLINA PROFESSIONAL ENGINEER
 SEAL 25474
 CRAIG PARKER

FINAL PAVEMENT MARKINGS & SCHEDULE

SCALE: NONE		REVISIONS
DATE: FEB, 2008		
DWG. BY: JLT		
DESIGN BY: JLT		
REVIEWED BY: WCP		

I:\6\2008\1764\1764.dwg
 2:05:45 PM
 11/6/2008 2:05:45 PM

I:\6\2008\1764\1764.dwg
 11/6/2008 2:05:45 PM