

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	33812.1.1 B-4646	1	20

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
GEOTECHNICAL ENGINEERING UNIT

STRUCTURE
SUBSURFACE INVESTIGATION

CONTENTS

<u>SHEET</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2	LEGEND
3	SITE PLAN
4	PROFILE(S)
5-8	CROSS SECTION(S)
9-14	BORE LOG & CORE REPORT(S)
15	SOIL TEST RESULTS
16	SCOUR REPORT
17-20	CORE PHOTOGRAPH(S)

PROJ. REFERENCE NO. 33812.1.1 B-4646 F.A. PROJ. BRZ-2024 (2)
COUNTY SURRY
PROJECT DESCRIPTION BRIDGE NO. 132 ON SR 2024
OVER TOMS CREEK

SITE DESCRIPTION _____

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 250-4088. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

PERSONNEL

R.W. TODD

R.J. TUCKER


R.S. HINSON

INVESTIGATED BY J.P. ROGERS

CHECKED BY C.B. LITTLE

SUBMITTED BY C.B. LITTLE

DATE FEBRUARY 2008



PROJECT: 33812.1.1
ID: B-4646

DRAWN BY: J.K. McCLURE

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

SUBSURFACE INVESTIGATION

SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS


Main content table divided into sections: SOIL DESCRIPTION, GRADATION, ROCK DESCRIPTION, TERMS AND DEFINITIONS, SOIL LEGEND AND AASHTO CLASSIFICATION, MINERALOGICAL COMPOSITION, COMPRESSION, PERCENTAGE OF MATERIAL, GROUND WATER, MISCELLANEOUS SYMBOLS, ABBREVIATIONS, EQUIPMENT USED ON SUBJECT PROJECT, FRACTURE SPACING, BEDDING, PLASTICITY, COLOR, etc.

CL STA. 18+70 -L-
 OAL=145.00
 1@ 35.0, 1@ 65.0, 1@ 45.0
 SKEW=90°

6

ELIZABETH ANN FULK REID
 DB 994 PG 844 TRACT 2
 -BL- 6 16+72.65 PINC
 -L- POT 21+66.72
 (14.21' LT.)

-L- PCSta. 20+38.66



-BL- 5 13+01.08 POT
 -L- POT 17+97.72
 (14.03' LT.)


RESIDUAL

BM #1
 -L- STA. 20+67.95
 40.05' RIGHT
 ELEV = 891.66'

5

WADE L. BRYANT
 DB 320 PG 451
 DB 292 PG 672

5/28/99



18-FEB-2008 13:20
dt:projects\3426_4646_46_999_brdg0132_surry_co\cadd\geotech\site&sub\B4646_GEO_pf1&p1...brd060132.dgn

5/28/99



PROJECT REFERENCE NO.	SHEET
33812.1.1 B-4646	5
Section Thru End Bent One STA. 17+97.50 -L-	

920

920

910

910

900

900

890

890

880

880

870

870

860

860

50

40

30

20

10

0

10

20

30

40

50

SS-3

EB1-A
17+90 -L-
10.00 LT.

SS-7
SS-8

EB1-B
17+90 -L-
15.00 RT.

ROADWAY EMBANKMENT
(FILL)

GROUND SURFACE

TAN LOOSE WET F. SAND (A-2-4)

ALLUVIUM

BRN V. LOOSE WET
SILTY CLAYEY F. SAND
(A-2-4)

ALLUVIUM

BRN-TAN LOOSE DRY
CLAYEY SILTY F. SAND
(A-2-4)

WEATHERED ROCK
(BRN SEV. WEATH. CRYSTALLINE ROCK)

CRYSTALLINE ROCK

RESIDUAL
BRN-TAN V. DENSE DRY MICA
SILTY F. SAND (A-2-4)

CRYSTALLINE ROCK

TCR
DRY
(6/19/99)

AR
DRY
(5/20/99)


60

7

62

18-FEB-2008 13:38
c:\projects\33812.1.1 B-4646\18-FEB-2008 13:38\18-FEB-2008 13:38.dgn


5/28/99



I:\FEB-2008\3439
 di\projects\B4646\990-brdg0132.surry co\cadd\geotech\site&sub\B4646_0E0_xsc&xsl_Brdg0132.dgn
 15:52:12
 AT 15:52:12


5/28/99

06-MAR-2008 09:46
Subjects: AT DEF 2510
unclassified
co\cadd\geotech\site&sub\14646\geo\asc&xsi_brdg0132.dgn



5/28/99

PROJECT REFERENCE NO.		SHEET
33812.1.1 B-4646		8
Section Thru End Bent Two STA. 19+42.50 -L-		



18-FEB-2008 13:43
 d:\projects\3446\16-g99-brdg0132-surry co\cadd\geotech\site&sub\B4646_DEF0_xsc&xsl_Brdg0132.dgn
 johndec1 AT GHH21269

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.									
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)								
BORING NO. EB1-A		STATION 17+90		OFFSET 10ft LT		ALIGNMENT -L-									
COLLAR ELEV. 898.6 ft		TOTAL DEPTH 11.5 ft		NORTHING 962,769		EASTING 1,549,548									
DRILL MACHINE CME-550		DRILL METHOD NW Casing w/ SPT			HAMMER TYPE Automatic										
START DATE 05/18/99		COMP. DATE 05/18/99		SURFACE WATER DEPTH N/A		DEPTH TO ROCK 11.5 ft									
ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	LOG SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
		0.5ft	0.5ft	0.5ft	0	25	50	75	100						
900													898.6	GROUND SURFACE	0.0
895.2	3.4												896.6	ROADWAY EMBANKMENT TAN LOOSE WET F. SAND (A-2-4)	2.0
890.2	8.4	1	0	0							SS-3	W	890.6	ALLUVIAL BRN V. LOOSE WET SILTY CLAYEY F. SAND (A-2-4)	8.0
													890.6	WEATHERED ROCK (BRN SEV. WEATH. CRYSTALLINE ROCK)	8.0
													887.1	Boring Terminated BY TRI-CONE REFUSAL at Elevation 887.1 ft ON HARD CRYSTALLINE ROCK	11.5

NCDOT BORE SINGLE B4646_GEO_BH_BRDG0132.GPJ_NC_DOT_GDT_02/13/08

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.									
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)								
BORING NO. EB1-B		STATION 17+90		OFFSET 15ft RT		ALIGNMENT -L-									
COLLAR ELEV. 897.9 ft		TOTAL DEPTH 11.2 ft		NORTHING 962,782		EASTING 1,549,569									
DRILL MACHINE CME-550		DRILL METHOD H.S. Augers			HAMMER TYPE Automatic										
START DATE 05/19/99		COMP. DATE 05/19/99		SURFACE WATER DEPTH N/A		DEPTH TO ROCK 11.2 ft									
ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	LOG SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
		0.5ft	0.5ft	0.5ft	0	25	50	75	100						
900													897.9	GROUND SURFACE	0.0
893.7	4.2												891.1	ALLUVIAL BRN-TAN LOOSE DRY CLAYEY SILTY F. SAND (A-2-4)	6.8
888.7	9.2	4	3	4							SS-7	D	886.7	RESIDUAL BRN-TAN V. DENSE DRY MICA. SILTY F. SAND (A-2-4)	11.2
													886.7	Boring Terminated BY AUGER REFUSAL at Elevation 886.7 ft ON HARD CRYSTALLINE ROCK	11.2

NCDOT BORE SINGLE B4646_GEO_BH(RDY_CONVERTED).GPJ_NC_DOT_GDT_02/13/08

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.									
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)								
BORING NO. B1-A		STATION 18+35		OFFSET 6ft LT		ALIGNMENT -L-									
COLLAR ELEV. 884.9 ft		TOTAL DEPTH 21.0 ft		NORTHING 962,810		EASTING 1,549,528									
DRILL MACHINE CME-550		DRILL METHOD NW Casing w/ SPT Core				HAMMER TYPE Automatic									
START DATE 05/18/99		COMP. DATE 05/18/99		SURFACE WATER DEPTH N/A		DEPTH TO ROCK 5.4 ft									
ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
		0.5ft	0.5ft	0.5ft	0	25	50	75	100						
885													884.9	0.0	GROUND SURFACE
															ALLUVIAL BRN V. LOOSE TO MED. DENSE MOIST F. SAND (A-2-4) WITH BOULDERS
															CRYSTALLINE ROCK (GRAY MOD. SEV. WEATH. BIOTITE SCHIST)
	4.9	1	100/1												CRYSTALLINE ROCK BLACK SLI. WEATH. TO FRESH SOUND BIOTITE SCHIST FOLIATION & DIPS 70 DEG.
															Boring Terminated at Elevation 863.9 ft IN SLI. WEATH. TO FRESH SOUND BIOTITE SCHIST

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.				
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)			
BORING NO. B1-A		STATION 18+35		OFFSET 6ft LT		ALIGNMENT -L-				
COLLAR ELEV. 884.9 ft		TOTAL DEPTH 21.0 ft		NORTHING 962,810		EASTING 1,549,528				
DRILL MACHINE CME-550		DRILL METHOD NW Casing w/ SPT Core				HAMMER TYPE Automatic				
START DATE 05/18/99		COMP. DATE 05/18/99		SURFACE WATER DEPTH N/A		DEPTH TO ROCK 5.4 ft				
CORE SIZE NXBWL			TOTAL RUN 14.2 ft			DRILLER R.J. TUCKER				
ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
				REC. (ft) %	RQD (ft) %	REC. (ft) %	RQD (ft) %			
878.2										
878.2	6.7	4.7		(4.7) 100%	(4.7) 100%	(14.2) 100%	(14.2) 100%		Begin Coring @ 6.7 ft	6.7
873.5	11.4	4.6		(4.6) 100%	(4.6) 100%				CRYSTALLINE ROCK	
									BLACK SLI. WEATH. TO FRESH SOUND BIOTITE SCHIST. FOLIATION & DIPS 70 DEG.	
868.9	16.0	4.9		(4.9) 100%	(4.9) 100%					
864.0	20.9									
									Boring Terminated at Elevation 863.9 ft IN SLI. WEATH. TO FRESH SOUND BIOTITE SCHIST	20.9

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.									
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)								
BORING NO. B1-B		STATION 18+35		OFFSET 6ft RT		ALIGNMENT -L-									
COLLAR ELEV. 882.4 ft		TOTAL DEPTH 19.1 ft		NORTHING 962,815		EASTING 1,549,538									
DRILL MACHINE CME-550		DRILL METHOD NW Casing w/ SPT Core			HAMMER TYPE Automatic										
START DATE 05/19/99		COMP. DATE 05/19/99		SURFACE WATER DEPTH N/A		DEPTH TO ROCK 3.0 ft									
ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
		0.5ft	0.5ft	0.5ft	0	25	50	75	100						
885													882.4	GROUND SURFACE	0.0
													880.4	ALLUVIAL BRN MED. DENSE MOIST F. SAND (A-2-4) WITH BOULDERS & ASPHALT	2.0
	3.0												879.4	RESIDUAL GRAY DENSE MOIST MICA. F. SAND (A-2-4)	3.0
		100/0.1											878.4	CRYSTALLINE ROCK (GRAY MOD. SEV. WEATH. BIOTITE SCHIST)	4.0
														CRYSTALLINE ROCK GRAY FRESH SOUND BIOTITE SCHIST 60 DEG. FOLIATION DIP	
													869.5	CRYSTALLINE ROCK GRAY FRESH SOUND BIOTITE GRANITE	13.0
													863.3	Boring Terminated at Elevation 863.3 ft IN FRESH SOUND BIOTITE GRANITE	19.1

NCDOT BORE SINGLE B4646_GEO_BH_BRD00132.GPJ NC_DOT_GDT 02/13/08

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.					
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)				
BORING NO. B1-B		STATION 18+35		OFFSET 6ft RT		ALIGNMENT -L-					
COLLAR ELEV. 882.4 ft		TOTAL DEPTH 19.1 ft		NORTHING 962,815		EASTING 1,549,538					
DRILL MACHINE CME-550		DRILL METHOD NW Casing w/ SPT Core			HAMMER TYPE Automatic						
START DATE 05/19/99		COMP. DATE 05/19/99		SURFACE WATER DEPTH N/A		DEPTH TO ROCK 3.0 ft					
CORE SIZE NXBWL			TOTAL RUN 15.1 ft		DRILLER R.J. TUCKER						
ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
				REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %			
878.4	4.0	5.4		(5.4) 100%	(5.4) 100%	RS-4	(9.0) 100%	(9.0) 100%		Begin Coring @ 4.0 ft CRYSTALLINE ROCK GRAY FRESH SOUND BIOTITE SCHIST 60 DEG. FOLIATION DIP	4.0
873.1	9.4	4.9		(4.9) 100%	(4.9) 100%	RS-5					
868.2	14.3	4.9		(4.9) 100%	(4.9) 100%		(6.2) 100%	(6.2) 100%		CRYSTALLINE ROCK GRAY FRESH SOUND BIOTITE GRANITE	13.0
863.3	19.1					RS-6				Boring Terminated at Elevation 863.3 ft IN FRESH SOUND BIOTITE GRANITE	19.1

NCDOT CORE SINGLE B4646_GEO_BH_BRD00132.GPJ NC_DOT_GDT 02/13/08

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.								
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)							
BORING NO. B2-A		STATION 18+85		OFFSET 6ft LT		ALIGNMENT -L-								
COLLAR ELEV. 878.8 ft		TOTAL DEPTH 24.6 ft		NORTHING 962,853		EASTING 1,549,502								
DRILL MACHINE CME-550		DRILL METHOD NW Casing w/ SPT Core			HAMMER TYPE Automatic									
START DATE 05/18/99		COMP. DATE 05/18/99		SURFACE WATER DEPTH 0.8ft		DEPTH TO ROCK 13.8 ft								
ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	SOIL AND ROCK DESCRIPTION	DEPTH (ft)	
		0.5ft	0.5ft	0.5ft	0	25	50	75	100					
880													878.8	0.0
878.0	0.8												878.8	0.0
875.7	3.1	7	5	7									876.0	2.8
872.5	6.3	14	21	26									870.0	8.8
870.0	8.8	21	29	33									870.0	8.8
		40	60/4										865.0	13.8
865.0	13.8												865.0	13.8
		100/0.0											864.3	14.5
													854.2	24.6

NCDOT BORE SINGLE B4646 GEO_BH_BRD0132.GPJ NC_DOT.GDT 02/13/08

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.					
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)				
BORING NO. B2-A		STATION 18+85		OFFSET 6ft LT		ALIGNMENT -L-					
COLLAR ELEV. 878.8 ft		TOTAL DEPTH 24.6 ft		NORTHING 962,853		EASTING 1,549,502					
DRILL MACHINE CME-550		DRILL METHOD NW Casing w/ SPT Core			HAMMER TYPE Automatic						
START DATE 05/18/99		COMP. DATE 05/18/99		SURFACE WATER DEPTH 0.8ft		DEPTH TO ROCK 13.8 ft					
CORE SIZE NXBWL			TOTAL RUN 10.1 ft		DRILLER R.J. TUCKER						
ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
				REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %			
864.3											
864.3	14.5	5.4		(5.3) 98%	(4.4) 81%	RS-7	(9.9) 98%	(7.8) 77%		Begin Coring @ 14.5 ft CRYSTALLINE ROCK GRAY SLI. WEATH. TO FRESH SLI. FRACTURED TO SOUND BIOTITE-SERICITE SCHIST	14.5
858.9	19.9			(4.6) 98%	(3.4) 72%	RS-8					
854.2	24.6					RS-9				Boring Terminated at Elevation 854.2 ft IN SLI. WEATH. TO FRESH SOUND BIOTITE-SERICITE SCHIST	24.6

NCDOT CORE SINGLE B4646 GEO_BH_BRD0132.GPJ NC_DOT.GDT 02/13/08

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.									
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)								
BORING NO. B2-B		STATION 18+85		OFFSET 6ft RT		ALIGNMENT -L-									
COLLAR ELEV. 880.3 ft		TOTAL DEPTH 25.2 ft		NORTHING 962,858		EASTING 1,549,512									
DRILL MACHINE CME-550		DRILL METHOD NW Casing w/ SPT Core			HAMMER TYPE Automatic										
START DATE 05/19/99		COMP. DATE 05/19/99		SURFACE WATER DEPTH 0.7ft		DEPTH TO ROCK 11.6 ft									
ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
		0.5ft	0.5ft	0.5ft	0	25	50	75	100						
885															
880.3	0.0												880.3	GROUND SURFACE	0.0
876.3	4.0	6	3	3									877.3	ALLUVIAL BRN LOOSE MOIST F. SAND (A-2-4) WITH WOOD & DEBRIS	3.0
871.0	9.3	17	23	23									871.0	RESIDUAL GRAY & WHITE DENSE MOIST V. MICA. CLAYEY F. SAND (A-2-4)	9.3
		33	67/5										868.7	WEATHERED ROCK (SEV. WEATH. BIOTITE-SERICITE SCHIST)	11.6
													855.1	CRYSTALLINE ROCK GRAY FRESH SOUND BIOTITE-SERICITE SCHIST	25.2
														Boring Terminated at Elevation 855.1 ft IN FRESH SOUND BIOTITE-SERICITE SCHIST	

NCDOT BORE SINGLE B4646_GEO_BH_BRD00132.GPJ NC_DOT.GDT 02/13/08

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.					
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)				
BORING NO. B2-B		STATION 18+85		OFFSET 6ft RT		ALIGNMENT -L-					
COLLAR ELEV. 880.3 ft		TOTAL DEPTH 25.2 ft		NORTHING 962,858		EASTING 1,549,512					
DRILL MACHINE CME-550		DRILL METHOD NW Casing w/ SPT Core			HAMMER TYPE Automatic						
START DATE 05/19/99		COMP. DATE 05/19/99		SURFACE WATER DEPTH 0.7ft		DEPTH TO ROCK 11.6 ft					
CORE SIZE NXBWL			TOTAL RUN 13.6 ft		DRILLER R.J. TUCKER						
ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	RUN		SAMP. NO.	STRATA		LOG	DESCRIPTION AND REMARKS	DEPTH (ft)
				REC. (ft) %	RQD (ft) %		REC. (ft) %	RQD (ft) %			
868.7											
868.7	11.6	3.8		(3.7) 97%	(3.7) 97%	RS-1	(13.4) 99%	(12.7) 93%		Begin Coring @ 11.6 ft CRYSTALLINE ROCK GRAY FRESH SOUND BIOTITE-SERICITE SCHIST 45 DEG. TO 60 DEG. FOLIATION DIP	11.6
864.9	15.4	4.9		(4.9) 100%	(4.3) 88%	RS-2					
860.0	20.3	4.9		(4.8) 98%	(4.7) 96%						
855.1	25.2					RS-3				Boring Terminated at Elevation 855.1 ft IN FRESH SOUND BIOTITE-SERICITE SCHIST	25.2

NCDOT CORE SINGLE B4646_GEO_BH_BRD00132.GPJ NC_DOT.GDT 02/13/08

PROJECT NO. 33812.1.1		ID. B-4646		COUNTY SURRY		GEOLOGIST Todd, R. W.										
SITE DESCRIPTION BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK							GROUND WTR (ft)									
BORING NO. EB2-A		STATION 19+23		OFFSET 13ft LT		ALIGNMENT -L-										
COLLAR ELEV. 890.2 ft		TOTAL DEPTH 19.0 ft		NORTHING 962,881		EASTING 1,549,476										
DRILL MACHINE CME-550		DRILL METHOD H.S. Augers				HAMMER TYPE Automatic										
START DATE 05/19/99		COMP. DATE 05/19/99		SURFACE WATER DEPTH N/A		DEPTH TO ROCK 19.0 ft										
ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION			
		0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)	DEPTH (ft)		
895														890.2	0.0	GROUND SURFACE
885.6	4.6	3	2	3						SS-5	D					ALLUVIAL BRN LOOSE DRY TO MOIST F. SAND (A-2-4)
880.6	9.6	2	4	4							M					
875.6	14.6	7	7	7						SS-6	M			877.2	13.0	RESIDUAL GRAY & WHITE MED. DENSE MOIST MICA. SILTY F. SAND (A-2-4)
														871.2	19.0	Boring Terminated BY AUGER REFUSAL at Elevation 871.2 ft ON HARD CRYSTALLINE ROCK

NCDOT BORE SINGLE B4646_GEO_BHRDY_CONVERTED.GPJ NC_DOT_GDT_02/13/08

TEST RESULTS

PROJECT: 33812.1.1 B-4646

COUNTY: SURRY

SITE DESCRIPTION: BRIDGE NO. 132 ON SR 2024 OVER TOMS CREEK

SOIL SAMPLE RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	AASHTO CLASS	N	L.L.	P.I.	% BY WEIGHT				% PASSING SIEVES			% MOISTURE	% ORGANIC	UNIT WT. (d)	VOID RATIO
								C. SAND	F. SAND	SILT	CLAY	10	40	200				
EB1-A																		
SS-3	10.0 LT	17+90 -L-	3.40-4.90	A-2-4(0)	0	20	NP	19.2	52.5	10.1	18.2	100	95	33				
EB1-B																		
SS-7	15.0 RT	17+90 -L-	4.10-5.60	A-2-4(0)	7	26	NP	22	54.3	13.5	10.1	100	96	29				
SS-8			9.20-11.70	A-2-4(0)	62	34	NP	28.5	57.6	13.9	0	100	88	22				
B1-A																		
SS-2	5.5 LT	18+35 -L-	0.00-5.40	A-2-4(0)	2	24	NP	23.4	62.6	5.9	8.1	96	88	19				
B2-A																		
SS-1	5.5 LT	18+85 -L-	3.10-4.60	A-2-4(0)	47	31	NP	33.9	52.5	9.5	4	96	81	19				
B2-B																		
SS-4	5.5 RT	18+85 -L-	4.00-5.50	A-2-4(0)	46	30	NP	26.1	54.5	1.2	18.2	98	85	29				
EB2-A																		
SS-5	13.0 LT	19+23 -L-	4.60-7.10	A-2-4(0)	5	20	NP	23.2	60.8	7.9	8.1	100	96	21				
SS-6			14.60-16.10	A-2-4(0)	14	30	NP	28.3	52.9	14.7	4	87	74	26				

ROCK SAMPLE RESULTS

SAMPLE NO.	OFFSET	STATION	DEPTH INTERVAL	RQD	UNIT WT	Q(MPa) (MPsi)	E(MPa) (MPsi)
B1-A							
RS-10	5.50 LT.	18+35 -L-	9.45-10.00	100%			AWAITING DATA
RS-11			12.40-12.90	100%			
RS-12			20.40-20.90	100%			
B1-B							
RS-4	5.50 RT.	18+35 -L-	4.00-4.60	100%			AWAITING DATA
RS-5			9.70-10.20	100%			
RS-6			18.70-19.10	100%			
B2-A							
RS-7	5.50 LT.	18+85 -L-	14.70-15.10	82%			AWAITING DATA
RS-8			21.60-22.45	72%			
RS-9			24.00-24.60	72%			
B2-B							
RS-1	5.50 RT.	18+85 -L-	11.60-12.10	98%			AWAITING DATA
RS-2			15.40-15.80	88%			
RS-3			24.50-25.20	96%			



FIELD SCOUR REPORT

WBS: 33812.1.1 TIP: B-4646 COUNTY: SURRY

DESCRIPTION(1): BRIDGE NO. 132 ON SR 2024 OVER TOM'S CREEK.

EXISTING BRIDGE

Information from: Field Inspection Microfilm _____ (reel _____ pos: _____)
 Other (explain) _____

Bridge No.: 132 Length: 126' Total Bents: 4 Bents in Channel: 2 Bents in Floodplain: 4
 Foundation Type: END BENTS - ABUTMENTS. INTERIOR BENTS - FOOTINGS

EVIDENCE OF SCOUR(2)

Abutments or End Bent Slopes: NONE

Interior Bents: MINOR SCOURING/LATERAL EROSION OCCURING AT B1-B.

Channel Bed: A CHANNEL HAS BEEN SCoured OUT THAT CROSSES SOMEWHAT DIAGONALLY ACROSS STREAM BED ON UPSTREAM SIDE OF BRIDGE.

Channel Bank: STABLE, BUT MINOR LATERAL EROSION IN THE BANK NEAREST B1-B.

EXISTING SCOUR PROTECTION

Type(3): NONE

Extent(4): N/A

Effectiveness(5): N/A

Obstructions(6): NONE

INSTRUCTIONS

- 1 Describe the specific site's location, including route number and body of water crossed.
- 2 Note scour evidence at existing end bents or abutments (e.g. undermining, sloughing, degradations).
- 3 Note existing scour protection (e.g. rip rap).
- 4 Describe extent of existing scour protection.
- 5 Describe whether or not the scour protection appears to be working.
- 6 Note obstructions such as dams, fallen trees, debris at bents, etc.
- 7 Describe the channel bed material based on observation and/or samples. Include any lab results with report.
- 8 Describe the channel bank material based on observation and/or samples. Include any lab results with report.
- 9 Describe the material covering the banks (e.g. grass, trees, rip rap, none).
- 10 Determine the approximate floodplain width from field observation or a topographic map.
- 11 Describe the material covering the floodplain (e.g. grass, trees, crops).
- 12 Use professional judgement to specify if the stream is degrading, aggrading, or static.
- 13 Describe potential and direction of the stream to migrate laterally during the bridge's life (approx. 100 years).
- 14 Give the design scour elevation (DSE) expected over the life of the bridge (approx. 100 years). This elevation can be given as a range across the site, or for each bent. Discuss the relationship between the Hydraulics Unit theoretical scour and the DSE. If the DSE is dependent on scour counter measures, explain (e.g. rip rap armoring on slopes). The DSE is based on the erodability of materials, giving consideration to the influence of joints, foliation, bedding characteristics, % core recovery, % RQD, differential weathering, shear strength, observations at existing structures, other tests deemed appropriate, and overall geologic conditions at the site.

DESIGN INFORMATION

Channel Bed Material(7): LIGHT GRAY SILTY SAND AS SS-2.

Channel Bank Material(8): BRN. FINE SAND AS SS-5.

Channel Bank Cover(9): TREES - MOST STRAIGHT.

Floodplain Width(10): APP. 150'

Floodplain Cover(11): WOODS/FIELDS

Stream is(12): Aggrading _____ Degrading Static _____

Channel Migration Tendency(13): SLIGHT TENDENCY FOR NORTHWARD MIGRATION.

Observations and Other Comments: _____

DESIGN SCOUR ELEVATIONS(14)

Feet x Meters _____

		BENTS											
		B1	B2	B3	B4								
100 yr		879	870.5										


Comparison of DSE to Hydraulics Unit theoretical scour:
 THE DSE AT B1 WAS REVISED UPWARD FROM THE HYDRO. PREDICTION DUE TO PRESENCE OF CRYSTALLINE ROCK. THE DSE AT B2 IS THE SAME AS THE HYDRO. PREDICTION.

SOIL ANALYSIS RESULTS FROM CHANNEL BED AND BANK MATERIAL

	SEE	SAMPLE	RESULTS			
Sample No.						
Retained #4						
Passed #10						
Passed #40						
Passed #200						
Coarse Sand						
Fine Sand						
Silt						
Clay						
LL						
PI						
AASHTO						
Station						
Offset						
Depth						



33812.1.1 B-4646
SURRY COUNTY
BRIDGE NO. 132 ON SR 2024 OVER TOMS CREEK

CORE PHOTOS





33812.1.1 B-4646
SURRY COUNTY
BRIDGE NO. 132 ON SR 2024 OVER TOMS CREEK

CORE PHOTOS



33812.1.1 B-4646
SURRY COUNTY
BRIDGE NO. 132 ON SR 2024 OVER TOMS CREEK

CORE PHOTOS



33812.1.1 B-4646
SURRY COUNTY
BRIDGE NO. 132 ON SR 2024 OVER TOMS CREEK

CORE PHOTOS

