

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (18+70)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	250 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	168 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	12 TON		
0010	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	48 LF		
0011	1121000000-E	520	AGGREGATE BASE COURSE	30 TON		
0012	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		
0013	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	340 TON		
0014	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	225 TON		
0015	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	30 TON		
0016	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	30 TON		
0017	2000000000-N	806	RIGHT OF WAY MARKERS	11 EA		
0018	2022000000-E	815	SUBDRAIN EXCAVATION	26 CY		

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2033000000-E	815	SUBDRAIN FINE AGGREGATE	18 CY		
0020	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0021	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0022	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0024	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0025	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0026	2556000000-E	846	SHOULDER BERM GUTTER	105 LF		
0027	2580000000-E	846	CONCRETE VALLEY GUTTER	35 LF		
0028	3030000000-E	862	STEEL BM GUARDRAIL	87.5 LF		
0029	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0030	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III SHOP CURVED)	1 EA		
0031	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	1 EA		
0032	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
0033	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0034	3635000000-E	876	RIP RAP, CLASS II	29 TON		
0035	3649000000-E	876	RIP RAP, CLASS B	18 TON		
0036	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	854 SY		
0037	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	534 SF		

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144	SF	
0039	4430000000-N	1130	DRUMS	10	EA	
0040	4445000000-E	1145	BARRICADES (TYPE III)	102	LF	
0041	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	5,000	LF	
0042	6000000000-E	1605	TEMPORARY SILT FENCE	275	LF	
0043	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	150	TON	
0044	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	200	TON	
0045	6012000000-E	1610	SEDIMENT CONTROL STONE	250	TON	
0046	6015000000-E	1615	TEMPORARY MULCHING	2.5	ACR	
0047	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0048	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25	TON	
0049	6024000000-E	1622	TEMPORARY SLOPE DRAINS	75	LF	
0050	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1	EA	
0051	6029000000-E	SP	SAFETY FENCE	250	LF	
0052	6030000000-E	1630	SILT EXCAVATION	485	CY	
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,000	SY	
0054	6037000000-E	SP	COIR FIBER MAT	50	SY	
0055	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	250	SY	
0056	6042000000-E	1632	1/4" HARDWARE CLOTH	100	LF	

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6070000000-N	SP	SPECIAL STILLING BASINS	8	EA	
0058	6071030000-E	SP	COIR FIBER BAFFLES	200	LF	
0059	6071050000-E	SP	*** SKIMMER (1-1/2")	5	EA	
0060	6084000000-E	1660	SEEDING & MULCHING	5	ACR	
0061	6087000000-E	1660	MOWING	1	ACR	
0062	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0063	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0064	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0065	6108000000-E	1665	FERTILIZER TOPDRESSING	1.25	TON	
0066	6114000000-N	SP	SPECIALIZED HAND MOWING	5	HR	
0067	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12	EA	

\*\*\*\*\* BEGIN SCHEDULE AA \*\*\*\*\*  
 \*\*\*\*\* ( 3 ALTERNATES ) \*\*\*\*\*

0068 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	60	LF	
*** OR ***						
0069 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32	LF	
0070 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	28	LF	
*** OR ***						
0071 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	32	LF	
0072 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	28	LF	

\*\*\*\*\* END SCHEDULE AA \*\*\*\*\*

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0073	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18+70.00-L-)	Lump Sum	L.S.	
0074	8105520000-E	SP	3'-0" DIA DRILLED PIERS IN SO IL	38.84 LF		
0075	8105620000-E	SP	3'-0" DIA DRILLED PIERS NOT IN SOIL	39 LF		
0076	8111200000-E	SP	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	41.72 LF		
0077	8113000000-N	SP	SID INSPECTION	2 EA		
0078	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0079	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (18+70.00-L-)	Lump Sum	L.S.	
0080	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	63 CY		
0081	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (18+70.00-L-)	Lump Sum	L.S.	
0082	8217000000-E	425	REINFORCING STEEL (BRIDGE)	15,836 LB		
0083	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,998 LB		
0084	8364000000-E	450	HP12X53 STEEL PILES	300 LF		
0085	8475000000-E	460	TWO BAR METAL RAIL	270.5 LF		
0086	8517000000-E	460	1'****X ***** CONCRETE PARA- PET (1'-2" X 2'-10 7/8")	285.5 LF		
0087	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	283 TON		
0088	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	314 SY		
0089	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Surry

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,567.5 LF		

1414/Apr02/Q33272.81/D395424920000/E90

Total Amount Of Bid For Entire Project :

**Contract No**     **C202113**

**County (ies):**   **Surry**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

**Contract Officer**

---

**Date**

Execution of Contract and Bonds  
Approved as to Form:

---

**Attorney General**