

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-E	225	UNCLASSIFIED EXCAVATION	13,400 CY		
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (19+64.00)	Lump Sum	L.S.	
0004	0036000000-E	225	UNDERCUT EXCAVATION	250 CY		
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0106000000-E	230	BORROW EXCAVATION	13,690 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	185 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	250 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	250 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	72 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	100 TON		
0013	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (72", 0.138")	260 LF		
0014	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	72 LF		
0015	0995000000-E	340	PIPE REMOVAL	724 LF		
0016	1121000000-E	520	AGGREGATE BASE COURSE	2,075 TON		
0017	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0018	1275000000-E	600	PRIME COAT	1,425 GAL		
0019	1330000000-E	607	INCIDENTAL MILLING	270 SY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,100	TON	
0021	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	830	TON	
0022	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	1,750	TON	
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	205	TON	
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50	TON	
0025	2000000000-N	806	RIGHT OF WAY MARKERS	21	EA	
0026	2022000000-E	815	SUBDRAIN EXCAVATION	34	CY	
0027	2033000000-E	815	SUBDRAIN FINE AGGREGATE	26	CY	
0028	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	150	LF	
0029	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	5	EA	
0030	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
0031	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0032	2199000000-E	SP	SANDBAG HEADWALL	964	SF	
0033	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8	EA	
0034	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	12.1	LF	
0035	2354200000-N	840	FRAME WITH GRATE, STD 840.24	2	EA	
0036	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	5	EA	
0037	2396000000-N	840	FRAME WITH COVER, STD 840.54	1	EA	
0038	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	950	LF	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	2591000000-E	848	4" CONCRETE SIDEWALK	300 SY		
0040	3030000000-E	862	STEEL BM GUARDRAIL	556.25 LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0042	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	3 EA		
0043	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	3 EA		
0044	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	787.5 LF		
0045	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	4 EA		
0046	3628000000-E	876	RIP RAP, CLASS I	445 TON		
0047	3649000000-E	876	RIP RAP, CLASS B	210 TON		
0048	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,500 SY		
0049	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	97 LF		
0050	4102000000-N	904	SIGN ERECTION, TYPE E	6 EA		
0051	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) (E)	2 EA		
0052	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	6 EA		
0053	4158000000-N	907	DISPOSAL OF SIGN SYSTEM, WOOD	3 EA		
0054	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	1 EA		
0055	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	176 SF		
0056	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	96 SF		
0057	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	96 SF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	4430000000-N	1130	DRUMS	110 EA		
0059	4435000000-N	1135	CONES	110 EA		
0060	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0061	4455000000-N	1150	FLAGGER	100 MD		
0062	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
0063	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,125 LF		
0064	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	95 EA		
0065	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,050 LF		
0066	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	3,621 LF		
0067	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	314 LF		
0068	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	4 EA		
0069	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	9 EA		
0070	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (III)	736 LF		
0071	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	1,104 LF		
0072	4780000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (8") (IV)	115 LF		
0073	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	12,936 LF		
0074	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,821 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0075	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	30 EA		
0076	5326600000-E	1510	16" WATER LINE	319 LF		
0077	5572600000-E	1515	16" TAPPING VALVE	2 EA		
0078	5672000000-N	1515	RELOCATE FIRE HYDRANT	1 EA		
0079	5810000000-E	1530	ABANDON 16" UTILITY PIPE	570 LF		
0080	5871900000-E	1550	TRENCHLESS INSTALLATION OF 16" IN SOIL	273 LF		
0081	6000000000-E	1605	TEMPORARY SILT FENCE	1,050 LF		
0082	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	120 TON		
0083	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	210 TON		
0084	6012000000-E	1610	SEDIMENT CONTROL STONE	860 TON		
0085	6015000000-E	1615	TEMPORARY MULCHING	6.5 ACR		
0086	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0087	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	2 TON		
0088	6024000000-E	1622	TEMPORARY SLOPE DRAINS	80 LF		
0089	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	1 EA		
0090	6029000000-E	SP	SAFETY FENCE	1,750 LF		
0091	6030000000-E	1630	SILT EXCAVATION	900 CY		
0092	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,650 SY		
0093	6037000000-E	SP	COIR FIBER MAT	40 SY		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0094	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	1,150 SY		
0095	6042000000-E	1632	1/4" HARDWARE CLOTH	2,710 LF		
0096	6071010000-E	SP	WATTLE	220 LF		
0097	6071020000-E	SP	POLYACRYLAMIDE (PAM)	85 LB		
0098	6071030000-E	SP	COIR FIBER BAFFLES	270 LF		
0099	6071050000-E	SP	*** SKIMMER (1-1/2")	6 EA		
0100	6084000000-E	1660	SEEDING & MULCHING	10 ACR		
0101	6087000000-E	1660	MOWING	5 ACR		
0102	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0103	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0104	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	150 LB		
0105	6108000000-E	1665	FERTILIZER TOPDRESSING	4 TON		
0106	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0107	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	27 EA		
0108	6123000000-E	1670	REFORESTATION	0.5 ACR		
0109	6129000000-E	1670	WETLAND REFORESTATION	0.5 ACR		
0110	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	0.5 ACR		
0111	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	0.5 ACR		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0112 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	124	LF	
0113 AA1	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	472	LF	
*** OR ***						
0114 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	96	LF	
0115 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	28	LF	
0116 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	472	LF	
*** OR ***						
0117 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	96	LF	
0118 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (15", 0.064")	28	LF	
0119 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, ***** THICK (30", 0.064")	472	LF	
***** END SCHEDULE AA *****						

STRUCTURE ITEMS

0120	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (19+64.00-L-)	Lump Sum	L.S.	
0121	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVATION	1,400	CY	
0122	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	11,207	SF	
0123	8161000000-E	420	GROOVING BRIDGE FLOORS	10,268	SF	
0124	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	126.9	CY	
0125	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (19+64.00-L-)	Lump Sum	L.S.	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0126	8217000000-E	425	REINFORCING STEEL (BRIDGE)	21,866 LB		
0127	8262000000-E	430	45" PRESTRESSED CONCRETE GIRDERS	1,435.08 LF		
0128	8364000000-E	450	HP12X53 STEEL PILES	520 LF		
0129	8384200000-E	450	HP14X73 GALVANIZED STEEL PILES	440 LF		
0130	8475000000-E	460	TWO BAR METAL RAIL	348.14 LF		
0131	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 3'-2 3/4")	181.89 LF		
0132	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-2" X 3'-8")	181.92 LF		
0133	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	435 TON		
0134	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	484 SY		
0135	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0136	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

1627/Mar26/Q133690.53/D563689910000/E136

Total Amount Of Bid For Entire Project :

Contract No **C202089**

County (ies): **Wake**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General