

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1245000000-E	SP	SHOULDER RECONSTRUCTION	3.1 SMI		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	308,175 SY		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (6")	3,000 SY		
0005	1330000000-E	607	INCIDENTAL MILLING	1,010 SY		
0006	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,110 TON		
0007	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	36,670 TON		
0008	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	52 TON		
0009	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	2,200 TON		
0010	1704000000-E	SP	PATCHING EXISTING PAVEMENT	230 TON		
0011	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	14,966 LF		
0012	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
0013	4605000000-N	SP	GENERIC TRAFFIC CONTROL ITEM POLICE	2,000 HR		
0014	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	164,491 LF		
0015	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	34,247 LF		
0016	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	16,095 LF		
0017	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	30 LF		

County : Wake, Durham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	16 EA		
0019	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	29 EA		
0020	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (III)	13,481 LF		
0021	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL, TYPE ** (III)	2 EA		
0022	4855000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (6")	13,481 LF		
0023	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	2 EA		
0024	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,668 EA		
0025	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0026	6084000000-E	1660	SEEDING & MULCHING	2.3 ACR		
0027	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	290 LF		

0918/Apr13/Q614253.4/D95290100000/E27

Total Amount Of Bid For Entire Project :

Contract No **C202306**

County (ies): **Wake & Durham**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General