



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES. PERDUE  
GOVERNOR

EUGENE A. CONTI, JR.  
SECRETARY

June 9, 2009

**Addendum No. 1**

RE: Contract ID: C202313

WBS# 45035.3.ST1, Etc.

F.A. # STM-1004(39), Etc.

**Durham County (R-5135, Etc.)**

1 Section of US-501 Bypass, 1 Section of NC-98 and 3 Sections of Secondary Roads

**June 16, 2009 Letting**

To Whom It May Concern:

Reference is made to the proposal recently furnished to you on this project.

The following revision has been made to the Proposal:

On New Page No. 42-A, the project special provision entitled "Adjustment Of Manholes and Water Valves (City of Durham)" has been added. Also, New Page Nos. 42-B and 42-C have been added to include the City of Durham details for manhole and valve box adjustments. Please staple New Page Nos. 42-A, 42-B and 42-C after Page No. 42 in your proposal.

Sincerely,

A handwritten signature in black ink, appearing to read "R. A. Garris".

R. A. Garris, PE  
Contract Officer

RAG/jag  
Attachment

cc: Mr. J.G Nance, PE  
Mr. Ron Hancock, PE  
Mr. J. W. Bowman, PE  
Ms. D. M. Barbour, PE  
Mr. Art McMillan, PE  
Mr. J.V. Barbour, PE  
Project File (2)

Mr. Robert Memory  
Mr. R. E. Davenport, Jr., PE  
Mr. Mark Staley  
Mr. Ronnie Higgins  
Mr. Larry Strickland  
Ms. Norma Smith  
Ms. Lori Strickland


**ADJUSTMENT OF MANHOLES AND WATER VALVES (CITY OF DURHAM):**

The Contractor's attention is directed to Section 858-3 of the *2006 Standard Specifications* and to included Details A-1 and B-2.

Concrete shall be Class A Concrete, 3000 psi and shall meet the requirements of Section 1000 of the *2006 Standard Specifications*.

The use of cast iron or steel fittings in the adjustment of manholes will not be permitted on this project except where it is considered by the Engineer to be in the best interest of the Department to allow rings to be used. When rings are permitted for the adjustment of manholes, the rings shall have satisfactory bearing on the existing manhole frames and 50 percent of the circumference shall be tack welded at four equally spaced locations as directed by the Engineer. If the existing covers do not fit the rings, furnish and install new covers at no additional expense to the Department.

42-B



MANHOLE ADJUSTMENTS IN PAVED STREETS




Engineering Department  
Water and Sewer Engineering Division, Durham, N.C.

Scale NONE  
Date OCT., 1990

Revised 6-9-09

42-C



VALVE BOX ADJUSTMENTS IN PAVED STREETS



Engineering Department

Water and Sewer Engineering Division, Durham, N.C.

Scale NONE

Date OCT., 1990