

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0001010000-N	200	SELECT TREE REMOVAL	1 EA		
0004	0036000000-E	225	UNDERCUT EXCAVATION	200 CY		
0005	0043000000-N	226	GRADING	Lump Sum	L.S.	
0006	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	200 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	200 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	100 TON		
0010	0343000000-E	310	15" SIDE DRAIN PIPE	116 LF		
0011	0344000000-E	310	18" SIDE DRAIN PIPE	160 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	620 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	24 LF		
0014	0453000000-E	310	*** PIPE END SECTION (15")	3 EA		
0015	0453000000-E	310	*** PIPE END SECTION (18")	14 EA		
0016	0453000000-E	310	*** PIPE END SECTION (24")	4 EA		
0017	0995000000-E	340	PIPE REMOVAL	30 LF		
0018	1121000000-E	520	AGGREGATE BASE COURSE	85 TON		
0019	1220000000-E	545	INCIDENTAL STONE BASE	40 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1330000000-E	607	INCIDENTAL MILLING	1,850 SY		
0021	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	13,300 TON		
0022	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	7,300 TON		
0023	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	22,900 TON		
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	915 TON		
0025	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,375 TON		
0026	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	75 TON		
0027	2253000000-E	840	PIPE COLLARS	4 CY		
0028	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	50 SY		
0029	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	150 SY		
0030	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	636 LF		
0031	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		
0032	4102000000-N	904	SIGN ERECTION, TYPE E	30 EA		
0033	4108000000-N	904	SIGN ERECTION, TYPE F	11 EA		
0034	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	38 EA		
0035	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	720 SF		
0036	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	576 SF		
0037	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	165 SF		
0038	4430000000-N	1130	DRUMS	75 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0040	4455000000-N	1150	FLAGGER	160 MD		
0041	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
0042	4485000000-E	1170	PORTABLE CONCRETE BARRIER	640 LF		
0043	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	78,000 LF		
0044	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	83,520 LF		
0045	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,600 LF		
0046	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	250 LF		
0047	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	24 EA		
0048	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	60,420 LF		
0049	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,600 LF		
0050	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	500 LF		
0051	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	24 EA		
0052	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	540 EA		
0053	6000000000-E	1605	TEMPORARY SILT FENCE	4,500 LF		
0054	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0055	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180 TON		
0056	6012000000-E	1610	SEDIMENT CONTROL STONE	10 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6036000000-E	1631	MATTING FOR EROSION CONTROL	500 SY		
0058	6042000000-E	1632	1/4" HARDWARE CLOTH	35 LF		
0059	6084000000-E	1660	SEEDING & MULCHING	6 ACR		
0060	6090000000-E	1661	SEED FOR REPAIR SEEDING	500 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1 TON		

1049/Apr29/Q285117.0/D184305510000/E61

Total Amount Of Bid For Entire Project :

Contract No **C201905**

County (ies): **Cumberland**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General