

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	BRIDGE APPROACH FILL - SUB REGIONAL TIER, STATION ***** (14 + 31.00)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0057000000-E	226	UNDERCUT EXCAVATION	200 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	9 TON		
0010	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	84 LF		
0011	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0012	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	145 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	194 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	19 TON		
0015	2000000000-N	806	RIGHT OF WAY MARKERS	9 EA		
0016	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0017	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0018	2556000000-E	846	SHOULDER BERM GUTTER	100 LF		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	3030000000-E	862	STEEL BM GUARDRAIL	150		LF
0020	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5		EA
0021	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4		EA
0022	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	4		EA
0023	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	225		SY
0024	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1		EA
0025	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	282		SF
0026	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94		SF
0027	4445000000-E	1145	BARRICADES (TYPE III)	96		LF
0028	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	3,200		LF
0029	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	6		EA
0030	6000000000-E	1605	TEMPORARY SILT FENCE	425		LF
0031	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75		TON
0032	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	70		TON
0033	6012000000-E	1610	SEDIMENT CONTROL STONE	75		TON
0034	6015000000-E	1615	TEMPORARY MULCHING	1.5		ACR
0035	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50		LB
0036	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1.25		TON

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	6029000000-E	SP	SAFETY FENCE	450 LF		
003E	6030000000-E	1630	SILT EXCAVATION	125 CY		
003E	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,000 SY		
004C	6037000000-E	SP	COIR FIBER MAT	10 SY		
0041	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	25 SY		
0042	6042000000-E	1632	1/4" HARDWARE CLOTH	225 LF		
004E	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	70 SY		
0044	6071010000-E	SP	WATTLE	60 LF		
004E	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB		
004E	6071030000-E	SP	COIR FIBER BAFFLES	20 LF		
0047	6071050000-E	SP	*** SKIMMER (1-1/2")	1 EA		
004E	6084000000-E	1660	SEEDING & MULCHING	5 ACR		
004E	6087000000-E	1660	MOWING	1 ACR		
005C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0051	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0052	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
005E	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
0054	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
005E	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	12 EA		

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6123000000-E	1670	REFORESTATION	0.1 ACR		

STRUCTURE ITEMS						

0057	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (14 + 31.00-L-)	Lump Sum	L.S.	

005E	8021000000-N	SP	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14 + 31.00-L-)	Lump Sum	L.S.	

005E	8096000000-E	SP	PILE EXCAVATION IN SOIL	37 LF		

006C	8097000000-E	SP	PILE EXCAVATION NOT IN SOIL	13 LF		

0061	8119000000-E	412	UNCLASSIFIED STRUCTURE EXCAVA- TION	540 CY		

0062	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	35.2 CY		

006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14 + 31.00-L-)	Lump Sum	L.S.	

0064	8217000000-E	425	REINFORCING STEEL (BRIDGE)	5,114 LB		

006E	8364000000-E	450	HP12X53 STEEL PILES	180 LF		

006E	8391000000-N	450	STEEL PILE POINTS	13 EA		

0067	8503000000-E	460	CONCRETE BARRIER RAIL	195.21 LF		

006E	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	227 TON		

006E	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	251 SY		

007C	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : Granville

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	976.04 LF		

1628/May04/Q15551.3/D347699810000/E71

Total Amount Of Bid For Entire Project :

Contract No **C202150**

County (ies): **Granville**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General