

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	2,380 SY		
0003	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	20 TON		
0004	0986000000-E	SP	GENERIC PIPE ITEM 24" RC PIPE CULVERTS, CLASS III (BORE AND JACK)	120 LF		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	13,555 SY		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	83,555 SY		
0007	1330000000-E	607	INCIDENTAL MILLING	2,330 SY		
0008	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	710 TON		
0009	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	240 TON		
0010	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,200 TON		
0011	1524200000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5D	13,880 TON		
0012	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	163 TON		
0013	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	11 TON		
0014	1567000000-E	SP	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-28	160 TON		
0015	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	763 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1839110000-E	661	ULTRATHIN HOT MIX ASPHALT, TYPE B	3,080	TON	
0017	1839200000-E	661	APPLICATION OF ULTRATHIN HOT MIX ASPHALT	88,000	SY	
001E	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	20,100	LF	
001E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1	EA	
002C	2352000000-N	840	FRAME WITH GRATE, STD 840.*** (840.20)	1	EA	
0021	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	1	EA	
0022	2619000000-E	850	4" CONCRETE PAVED DITCH	1,190	SY	
002E	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1	EA	
0024	3030000000-E	862	STEEL BM GUARDRAIL	1,225	LF	
002E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	268	EA	
002E	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	1	EA	
0027	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	8,300	LF	
002E	3360000000-E	863	REMOVE EXISTING GUARDRAIL	750	LF	
002E	3649000000-E	876	RIP RAP, CLASS B	3	TON	
003C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	15	SY	
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	750	SF	
0032	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	410	SF	
003E	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	130	SF	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	6 EA		
003E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4 EA		
003E	4430000000-N	1130	DRUMS	200 EA		
0037	4445000000-E	1145	BARRICADES (TYPE III)	100 LF		
003E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA		
003E	4480000000-N	1165	TMIA	3 EA		
004C	4485000000-E	1170	PORTABLE CONCRETE BARRIER	13,610 LF		
0041	4605000000-N	SP	GENERIC TRAFFIC CONTROL ITEM LAW ENFORCEMENT	624 HR		
0042	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	27,000 LF		
0043	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	11,650 LF		
0044	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	4,000 LF		
004E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	3 EA		
004E	4775000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (6") (IV)	14,000 LF		
0047	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	111,400 LF		
004E	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	8,000 LF		
004E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	6 EA		
005C	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	600 EA		
0051	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6012000000-E	1610	SEDIMENT CONTROL STONE	3 TON		
0053	6042000000-E	1632	1/4" HARDWARE CLOTH	12 LF		

1006/May12/Q435538.0/D168352810000/E53

Total Amount Of Bid For Entire Project :

Contract No **C202312**

County (ies): **Guilford**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General