

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000700000-N	SP	FIELD OFFICE	Lump Sum	L.S.	
0003	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0004	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUB- BING	5 ACR		
0005	0022000000-E	225	UNCLASSIFIED EXCAVATION	105,200 CY		
0008	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (211+80.69-L-RT)	Lump Sum	L.S.	
0009	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (211+96.72-L-LT)	Lump Sum	L.S.	
0010	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (247+69.78-L-RT)	Lump Sum	L.S.	
0011	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (248+69.15-L-LT)	Lump Sum	L.S.	
0012	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (29+01.31-Y1RPCA-)	Lump Sum	L.S.	
0013	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (51+72.74-L-LT)	Lump Sum	L.S.	
0016	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (97+12.41-Y1-LT)	Lump Sum	L.S.	
0017	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (97+40.48-Y1-RT)	Lump Sum	L.S.	
0018	0036000000-E	225	UNDERCUT EXCAVATION	34,100 CY		
0019	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	1,000 TON		
0020	0106000000-E	230	BORROW EXCAVATION	3,188,150 CY		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0021	0127000000-N	SP	EMBANKMENT SETTLEMENT GAUGES	2 EA		
0022	0134000000-E	240	DRAINAGE DITCH EXCAVATION	16,700 CY		
0023	0141000000-E	240	BERM DITCH CONSTRUCTION	300 LF		
0024	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	3,760 SY		
0025	0192000000-N	260	PROOF ROLLING	12 HR		
0026	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	5,500 SY		
0027	0234000000-E	SP	GENERIC GRADING ITEM SELECT GRANULAR MATERIAL	10,000 CY		
0028	0241000000-E	SP	GENERIC GRADING ITEM PERMANENT TURF REINFORCEMENT MAT	3,500 SY		
0029	0241000000-E	SP	GENERIC GRADING ITEM SECONDARY GEOGRID REINFORCEMENT	10,000 SY		
0030	0300000000-E	300	SELECT MATERIAL, CLASS II	5,650 TON		
0031	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	2,285 TON		
0032	0342000000-E	310	*** SIDE DRAIN PIPE (12")	52 LF		
0033	0343000000-E	310	15" SIDE DRAIN PIPE	100 LF		
0034	0344000000-E	310	18" SIDE DRAIN PIPE	84 LF		
0035	0345000000-E	310	24" SIDE DRAIN PIPE	36 LF		
0036	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	1,772 LF		
0037	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	548 LF		
0038	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	296 LF		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0039	0408000000-E	310	54" RC PIPE CULVERTS, CLASS III	600	LF	
0040	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	540	LF	
0041	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (30")	268	LF	
0042	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (36")	624	LF	
0043	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (48")	372	LF	
0044	0448000000-E	310	***** RC PIPE CULVERTS, CLASS IV (66")	308	LF	
0045	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (36", 0.079")	96	LF	
0046	0576000000-E	310	*** CS PIPE CULVERTS, ***** THICK (48", 0.109")	68	LF	
0047	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	200	LF	
0048	0706000000-E	310	12" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	136	LF	
0049	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	1,807	LF	
0050	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	276	LF	
0051	0720000000-E	310	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	92	LF	
0052	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	31	EA	
0053	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4	EA	

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	0995000000-E	340	PIPE REMOVAL	1,691 LF		
0055	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0056	1077000000-E	SP	#57 STONE	100 TON		
0057	1110000000-E	510	STABILIZER AGGREGATE	3,000 TON		
0058	1121000000-E	520	AGGREGATE BASE COURSE	18,800 TON		
0059	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
0060	1275000000-E	600	PRIME COAT	5,000 GAL		
0061	1330000000-E	607	INCIDENTAL MILLING	200 SY		
0062	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,030 TON		
0063	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	3,310 TON		
0064	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	9,710 TON		
0065	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	3,670 TON		
0066	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	8,910 TON		
0067	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	865 TON		
0068	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	535 TON		
0069	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	615 TON		
0070	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	6,960 LF		
0071	2022000000-E	815	SUBDRAIN EXCAVATION	2,184 CY		
0072	2033000000-E	815	SUBDRAIN FINE AGGREGATE	1,092 CY		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	6,500 LF		
0074	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	195 EA		
0075	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	13 EA		
0076	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	78 LF		
0077	2209000000-E	838	ENDWALLS	67.1 CY		
0078	2220000000-E	838	REINFORCED ENDWALLS	55.2 CY		
0079	2253000000-E	840	PIPE COLLARS	3 CY		
0080	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	158 EA		
0081	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	12.4 LF		
0082	2354000000-N	840	FRAME WITH GRATE, STD 840.22	5 EA		
0083	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	13 EA		
0084	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	75 EA		
0085	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	34 EA		
0086	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	7 EA		
0087	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	16 EA		
0088	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	8 EA		
0089	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	7,290 LF		
0090	2570000000-N	SP	MODIFIED CONCRETE FLUME	2 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	2,190 LF		
0092	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	18 EA		
0093	2612000000-E	848	6" CONCRETE DRIVEWAY	220 SY		
0094	2619000000-E	850	4" CONCRETE PAVED DITCH	50 SY		
0095	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	3,080 SY		
0096	2800000000-N	858	ADJUSTMENT OF CATCH BASINS	4 EA		
0097	2830000000-N	858	ADJUSTMENT OF MANHOLES	3 EA		
0098	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	7 EA		
0099	2938000000-N	SP	CONVERT EXISTING DROP INLET TO JUNCTION BOX WITH MANHOLE COVER	1 EA		
0100	3030000000-E	862	STEEL BM GUARDRAIL	2,500 LF		
0101	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0102	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0103	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0104	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	2 EA		
0105	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	5 EA		
0106	3345000000-E	864	REMOVE & RESET EXISTING GUARD- RAIL	213 LF		
0107	3380000000-E	862	TEMPORARY STEEL BM GUARDRAIL	63 LF		
0108	3389100000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY	1 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	3389400000-E	865	DOUBLE FACED CABLE GUIDERAIL	1,255 LF		
0110	3389600000-N	865	CABLE GUIDERAIL ANCHOR UNITS	2 EA		
0111	3503000000-E	866	WOVEN WIRE FENCE, 47" FABRIC	58,160 LF		
0112	3509000000-E	866	4" TIMBER FENCE POSTS, 7'-6" LONG	3,710 EA		
0113	3515000000-E	866	5" TIMBER FENCE POSTS, 8'-0" LONG	760 EA		
0114	3557000000-E	866	ADDITIONAL BARBED WIRE	500 LF		
0115	3628000000-E	876	RIP RAP, CLASS I	1,765 TON		
0116	3642000000-E	876	RIP RAP, CLASS A	30 TON		
0117	3649000000-E	876	RIP RAP, CLASS B	1,880 TON		
0118	3651000000-E	SP	BOULDERS	70 TON		
0119	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	8,850 SY		
0120	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	13 EA		
0121	4048000000-E	902	REINFORCED CONCRETE SIGN FOUN- DATIONS	6 CY		
0122	4060000000-E	903	SUPPORTS, BREAKAWAY STEEL BEAM	3,726 LB		
0123	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	8 LF		
0124	4082000000-E	903	SUPPORTS, WOOD	725 LF		
0125	4096000000-N	904	SIGN ERECTION, TYPE D	4 EA		
0126	4102000000-N	904	SIGN ERECTION, TYPE E	42 EA		
0127	4108000000-N	904	SIGN ERECTION, TYPE F	3 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0128	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	5 EA		
0129	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (B)	1 EA		
0130	4152000000-N	907	DISPOSAL OF SIGN SYSTEM, STEEL BEAM	2 EA		
0131	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	10 EA		
0132	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	343 SF		
0133	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	480 SF		
0134	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	90 SF		
0135	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		
0136	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0137	4430000000-N	1130	DRUMS	100 EA		
0138	4435000000-N	1135	CONES	60 EA		
0139	4445000000-E	1145	BARRICADES (TYPE III)	445 LF		
0140	4455000000-N	1150	FLAGGER	100 MD		
0141	4480000000-N	1165	TMIA	4 EA		
0142	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	385 EA		
0143	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	18,919 LF		
0144	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	21,032 LF		
0145	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	5,334 LF		



County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0146	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	478 LF		
0147	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	228 LF		
0148	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	390 LF		
0149	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	8 EA		
0150	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	41 EA		
0151	4770000000-E	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES, TYPE ** (4") (IV)	2,307 LF		
0152	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	14,192 LF		
0153	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	155 LF		
0154	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	8 EA		
0155	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	11 EA		
0156	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	3,900 LF		
0157	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	330 EA		
0158	4915000000-E	1264	7' U-CHANNEL POSTS	9 EA		
0159	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	15 EA		
0160	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	40 EA		
0161	4945000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL & RED)	8 EA		
0162	4950000000-N	1267	FLEXIBLE DELINEATORS (YELLOW & RED)	5 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0163	4955000000-N	1264	OBJECT MARKERS (END OF ROAD)	9 EA		
0164	5319000000-E	1505	CLASS B CONCRETE FOR ENCASING UTILITY LINES	109 CY		
0165	5325400000-E	1510	4" WATER LINE	220 LF		
0166	5325600000-E	1510	6" WATER LINE	60 LF		
0167	5325800000-E	1510	8" WATER LINE	418 LF		
0168	5326200000-E	1510	12" WATER LINE	471 LF		
0169	5326600000-E	1510	16" WATER LINE	821 LF		
0170	5571800000-E	1515	8" TAPPING VALVE	1 EA		
0171	5648000000-N	1515	RELOCATE WATER METER	4 EA		
0172	5649000000-N	1515	RECONNECT WATER METER	1 EA		
0173	5666000000-E	1515	FIRE HYDRANT	2 EA		
0174	5672000000-N	1515	RELOCATE FIRE HYDRANT	5 EA		
0175	5804000000-E	1530	ABANDON 12" UTILITY PIPE	447 LF		
0176	5810000000-E	1530	ABANDON 16" UTILITY PIPE	808 LF		
0177	5815000000-N	1530	REMOVE WATER METER	5 EA		
0178	5815500000-N	1530	REMOVE FIRE HYDRANT	2 EA		
0179	5836200000-E	1540	30" ENCASEMENT PIPE	280 LF		
0180	6000000000-E	1605	TEMPORARY SILT FENCE	144,000 LF		
0181	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	9,380 TON		
0182	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	20,895 TON		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0183	6012000000-E	1610	SEDIMENT CONTROL STONE	11,700 TON		
0184	6015000000-E	1615	TEMPORARY MULCHING	442 ACR		
0185	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	7,800 LB		
0186	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	32 TON		
0187	6024000000-E	1622	TEMPORARY SLOPE DRAINS	16,550 LF		
0188	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	119 EA		
0189	6029000000-E	SP	SAFETY FENCE	13,200 LF		
0190	6030000000-E	1630	SILT EXCAVATION	73,500 CY		
0191	6036000000-E	1631	MATTING FOR EROSION CONTROL	48,000 SY		
0192	6037000000-E	SP	COIR FIBER MAT	285 SY		
0193	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	650 SY		
0194	6042000000-E	1632	1/4" HARDWARE CLOTH	6,500 LF		
0195	6046000000-E	SP	TEMPORARY PIPE FOR STREAM CROSSING	100 LF		
0196	6069000000-E	1638	STILLING BASINS	1,395 CY		
0197	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0198	6071010000-E	SP	WATTLE	550 LF		
0199	6071020000-E	SP	POLYACRYLAMIDE (PAM)	300 LB		
0200	6071030000-E	SP	COIR FIBER BAFFLES	5,150 LF		
0201	6071050000-E	SP	*** SKIMMER (1-1/2")	15 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0202	6071050000-E	SP	*** SKIMMER (2")	9 EA		
0203	6084000000-E	1660	SEEDING & MULCHING	510 ACR		
0204	6087000000-E	1660	MOWING	533.5 ACR		
0205	6090000000-E	1661	SEED FOR REPAIR SEEDING	3,600 LB		
0206	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	17.25 TON		
0207	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	10,675 LB		
0208	6108000000-E	1665	FERTILIZER TOPDRESSING	320 TON		
0209	6111000000-E	SP	IMPERVIOUS DIKE	260 LF		
0210	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0211	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	54 EA		
0212	6120000000-E	SP	CULVERT DIVERSION CHANNEL	2,310 CY		
0213	6123000000-E	1670	REFORESTATION	3 ACR		
0214	6126000000-E	SP	STREAMBANK REFORESTATION	6.5 ACR		
0215	6129000000-E	1670	WETLAND REFORESTATION	1.143 ACR		
0216	6132000000-N	SP	GENERIC EROSION CONTROL ITEM LOG	18 EA		
0217	6133000000-N	SP	GENERIC EROSION CONTROL ITEM CONSTRUCTION SURVEYING FOR MITIGATION	Lump Sum	L.S.	
0218	6133000000-N	SP	GENERIC EROSION CONTROL ITEM DIVERSION PUMPING FOR MITIGATION	Lump Sum	L.S.	
0219	6133000000-N	SP	GENERIC EROSION CONTROL ITEM GRADING FOR MITIGATION	Lump Sum	L.S.	
0220	6135000000-E	SP	GENERIC EROSION CONTROL ITEM DISKING	1.143 ACR		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0221	6135000000-E	SP	GENERIC EROSION CONTROL ITEM RIPPING	1.143	ACR	
0222	6138000000-E	SP	GENERIC EROSION CONTROL ITEM IMPERVIOUS SELECT MATERIAL	140	CY	
0223	7060000000-E	1705	SIGNAL CABLE	1,917	LF	
0224	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	18	EA	
0225	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2	EA	
0226	7264000000-E	1710	MESSENGER CABLE (3/8")	1,625	LF	
0227	7279000000-E	1715	TRACER WIRE	2,900	LF	
0228	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	25	LF	
0229	7300000000-E	1715	UNPAVED TRENCHING (***** (1, 2")	4,085	LF	
0230	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	10	EA	
0231	7348000000-N	1716	JUNCTION BOX (OVER-SIZED, HEA- VY DUTY)	5	EA	
0232	7360000000-N	1720	WOOD POLE	3	EA	
0233	7372000000-N	1721	GUY ASSEMBLY	5	EA	
0234	7408000000-E	1722	1" RISER WITH WEATHERHEAD	1	EA	
0235	7420000000-E	1722	2" RISER WITH WEATHERHEAD	2	EA	
0236	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	1	EA	
0237	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	2,140	LF	
0238	7456000000-E	1726	LEAD-IN CABLE (***** (14-2)	7,268	LF	

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0239	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	4,210 LF		
0240	7540000000-N	1731	SPLICE ENCLOSURE	1 EA		
0241	7552000000-N	1731	INTERCONNECT CENTER	2 EA		
0242	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER, DROP & REPEAT	2 EA		
0243	7566000000-N	1733	DELINEATOR MARKER	5 EA		
0244	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIV- ER	1 EA		
0245	7575160000-E	1734	REMOVE EXISTING COMMUNICATIONS CABLE	1,266 LF		
0246	7576000000-N	SP	METAL STRAIN SIGNAL POLE	8 EA		
0247	7613000000-N	SP	SOIL TEST	8 EA		
0248	7614100000-E	SP	DRILLED PIER FOUNDATION	56 CY		
0249	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		
0250	7684000000-N	1750	SIGNAL CABINET FOUNDATION	2 EA		
0251	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	2 EA		
0252	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	13 EA		
0253	7901000000-N	1753	CABINET BASE EXTENDER	2 EA		
0254	7948000000-N	SP	TRAFFIC SIGNAL REMOVAL	1 EA		
0255	7960000000-N	SP	METAL POLE FOUNDATION REMOVAL	4 EA		
0256	7972000000-N	SP	METAL POLE REMOVAL	4 EA		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
***** BEGIN SCHEDULE AA ***** ***** (3 ALTERNATES) *****						
0257 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	6,608	LF	
0258 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	2,292	LF	
0259 AA1	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	928	LF	
0260 AA1	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	2,664	LF	
*** OR ***						
0261 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	5,728	LF	
0262 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,944	LF	
0263 AA2	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	880	LF	
0264 AA2	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,204	LF	
0265 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (15")	880	LF	
0266 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (18")	348	LF	
0267 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (24")	48	LF	
0268 AA2	0536000000-E	SP	**** HDPE PIPE CULVERTS (30")	1,460	LF	
*** OR ***						
0269 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	5,728	LF	
0270 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,944	LF	
0271 AA3	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	880	LF	
0272 AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,204	LF	

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0273 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064")	880 LF		
0274 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (18", 0.064")	348 LF		
0275 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (24", 0.064")	48 LF		
0276 AA3	0540000000-E	SP	**** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (30", 0.079")	1,460 LF		
***** END SCHEDULE AA *****						
<b>CULVERT ITEMS</b>						
0277	8126000000-N	414	CULVERT EXCAVATION, STA ***** (139+60.00-L-)	Lump Sum	L.S.	
0278	8126000000-N	414	CULVERT EXCAVATION, STA ***** (153+62.00-L-)	Lump Sum	L.S.	
0279	8126000000-N	414	CULVERT EXCAVATION, STA ***** (16+14.00-Y1RPCA-)	Lump Sum	L.S.	
0280	8126000000-N	414	CULVERT EXCAVATION, STA ***** (38+22.00-Y1-)	Lump Sum	L.S.	
0281	8126000000-N	414	CULVERT EXCAVATION, STA ***** (74+43.00-Y1-)	Lump Sum	L.S.	
0282	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	3,483 TON		
0283	8196000000-E	420	CLASS A CONCRETE (CULVERT)	7,541.4 CY		
0284	8245000000-E	425	REINFORCING STEEL (CULVERT)	1,062,147 LB		



County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>WALL ITEMS</b>						
0285	8801000000-E	SP	MSE RETAINING WALLS	23,971 SF		
<b>STRUCTURE ITEMS</b>						
0288	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 28+99.24-Y1RPCA-)	Lump Sum	L.S.	
0289	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 51+64.57-L-)	Lump Sum	L.S.	
0290	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 85+98.30-L-LT)	Lump Sum	L.S.	
0291	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (1, 85+98.30-L-RT)	Lump Sum	L.S.	
0292	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2, 85+98.30-L-LT)	Lump Sum	L.S.	
0293	8091000000-N	410	FOUNDATION EXCAVATION FOR BENT ** AT STATION ***** (2, 85+98.30-L-RT)	Lump Sum	L.S.	
0294	8112730000-N	SP	PDA TESTING	8 EA		
0295	8112740000-N	SP	PDA ASSISTANCE	8 EA		
0296	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	125,510 SF		
0297	8161000000-E	420	GROOVING BRIDGE FLOORS	133,259 SF		
0298	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	1,463.6 CY		
0299	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (113+38.09-L-LT)	Lump Sum	L.S.	
0300	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (113+38.09-L-RT)	Lump Sum	L.S.	

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0301	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (211+67.44-L-LT)	Lump Sum	L.S.	
0302	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (211+67.44-L-RT)	Lump Sum	L.S.	
0303	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (248+68.10-L-LT)	Lump Sum	L.S.	
0304	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (248+68.10-L-RT)	Lump Sum	L.S.	
0305	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (28+99.24-Y1RPCA-)	Lump Sum	L.S.	
0306	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (51+64.57-L-)	Lump Sum	L.S.	
0307	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (85+98.30-L-LT)	Lump Sum	L.S.	
0308	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (85+98.30-L-RT)	Lump Sum	L.S.	
0309	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (97+26.78-Y1-LT)	Lump Sum	L.S.	
0310	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (97+26.78-Y1-RT)	Lump Sum	L.S.	
0311	8217000000-E	425	REINFORCING STEEL (BRIDGE)	268,244 LB		
0312	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	10,951 LB		
0313	8274000000-E	430	MODIFIED 63" PRESTRESSED CONC GIRDERS	883.33 LF		
0314	8277000000-E	430	MODIFIED 72" PRESTRESSED CONC GIRDERS	1,030.64 LF		

County : Lenoir

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0315	8280000000-E	440	APPROX ..... LBS STRUCTURAL STEEL	4,640,041 LS		
0316	8364000000-E	450	HP12X53 STEEL PILES	26,185 LF		
0317	8384000000-E	450	HP14X73 STEEL PILES	8,355 LF		
0318	8391000000-N	450	STEEL PILE POINTS	52 EA		
0319	8393000000-N	450	PILE REDRIVES	220 EA		
0320	8503000000-E	460	CONCRETE BARRIER RAIL	5,014.41 LF		
0321	8531000000-E	462	4" SLOPE PROTECTION	5,223 SY		
0322	8650000000-N	SP	POT BEARINGS	Lump Sum	L.S.	
0323	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0324	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0325	8706000000-N	SP	EXPANSION JOINT SEALS	Lump Sum	L.S.	
1020/Jun05/Q10406479.659/D1377416090000/E319			Total Amount Of Bid For Entire Project :			