

County : Lincoln, Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	720 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	33.54 SMI		
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO *****" DEPTH (0" - 1.5")	1,684 SY		
0005	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	21,112 TON		
0006	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	2,150 TON		
0007	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,408 TON		
0008	1704000000-E	SP	PATCHING EXISTING PAVEMENT	2,640 TON		
0009	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
0010	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0011	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	71,500 LF		
0012	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	78,500 LF		
0013	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	44 LF		
0014	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	100 LF		
0015	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	510 LF		
0016	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	28 EA		
0017	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	48 EA		

County : Lincoln, Catawba

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	415,700	LF	
001E	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	810	EA	
1359/May06/Q596993.54/D58393100000/E19			Total Amount Of Bid For Entire Project :			

Contract No **C202347**

Counties: **Lincoln, Catawba**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)