

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0004	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	38 TON		
0005	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	134 LF		
0006	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	94 LF		
0007	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	126 LF		
0008	0995000000-E	340	PIPE REMOVAL	229 LF		
0009	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
0010	1243000000-E	SP	SHOULDER CONSTRUCTION	8.89 SMI		
0011	1245000000-E	SP	SHOULDER RECONSTRUCTION	7.49 SMI		
0012	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	143,425 SY		
0013	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	720 SY		
0014	1330000000-E	607	INCIDENTAL MILLING	1,110 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	9,795 TON		
0016	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	29,430 TON		
0017	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	421 TON		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	1,768 TON		
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	26 TON		
002C	1704000000-E	SP	PATCHING EXISTING PAVEMENT	350 TON		
0021	1880000000-E	SP	GENERIC PAVING ITEM JOINT REPAIR	910 TON		
0022	2209000000-E	838	ENDWALLS	2.4 CY		
002E	2253000000-E	840	PIPE COLLARS	1 CY		
0024	3030000000-E	862	STEEL BM GUARDRAIL	1,125 LF		
002E	3180000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** (III, MOD)	8 EA		
002E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	8 EA		
0027	3649000000-E	876	RIP RAP, CLASS B	10 TON		
002E	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	28 SY		
002E	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM TRAFFIC CONTROL	Lump Sum	L.S.	
003C	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	102,690 LF		
0031	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	93,935 LF		
0032	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	650 LF		
003E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	200 LF		
0034	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	24 EA		

County : Moore

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	157,590	LF	
003E	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	876	EA	
0037	6000000000-E	1605	TEMPORARY SILT FENCE	7,375	LF	
003E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	344	TON	
003E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,085	TON	
004C	6012000000-E	1610	SEDIMENT CONTROL STONE	571	TON	
0041	6015000000-E	1615	TEMPORARY MULCHING	4.2	ACR	
0042	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,660	SY	
004E	6071010000-E	SP	WATTLE	740	LF	
0044	6071020000-E	SP	POLYACRYLAMIDE (PAM)	11	LB	
004E	6071030000-E	SP	COIR FIBER BAFFLES	636	LF	
004E	6084000000-E	1660	SEEDING & MULCHING	24.15	ACR	

0925/May11/Q562694.13/D140992160000/E46

Total Amount Of Bid For Entire Project :

Contract No **C202301**

County (ies): **Moore**

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General